



कलाक्षेत्र प्रतिष्ठान

KALAKSHETRA FOUNDATION

THIRUVANMIYUR, CHENNAI- 600 041 PH- 044- 24524057 / 0836

15.04.2024

CORRIGENDUM

Sub: Corrigendum to the work – Drilling of bore well and providing submersible pump at Kalakshetra Foundation- Reg

Ref: ENQ No.004/2024-2025/EM dt.10.04.2024

1. This is with reference to tender enquiry No.ENQ-No.004/2024-2025/EM/ dt.10.04.2024 for the above-mentioned work, this corrigendum is issued due to the typographical error in tender document as detailed below.
2. The prospective bidders are requested to kindly pursue the following clarifications and corrigendum. This corrigendum is a part of the tender conditions and shall be submitted duly signed and stamped along with bid. All the other terms and conditions of the tender will remain same.

SL.NO	EXISTING DESCRIPTION	MODIFICATION
1.	At page no- 58/60 Schedule of Quantities Under Sl.No- 3 Supplying and laying 3 core 4 Sq.mm submersible PVC insulated copper conductor, single core cable in the existing surface /recessed steel/ PVC/DWC pipe etc., as required. <i>QTY- 3.00</i> <i>UNIT- NOS</i>	At page no- 58/60 Schedule of Quantities Under Sl.No- 3 Supplying and laying 3 core 4 Sq.mm submersible PVC insulated copper conductor, single core cable in the existing surface /recessed steel/ PVC/DWC pipe etc., as required. <i>QTY- 150.00</i> <i>UNIT- MTS</i>

The inconvenience caused is regretted.

This issues with the approval of the Director, Kalakshetra Foundation.



कलाक्षेत्र प्रतिष्ठान

KALAKSHETRA FOUNDATION

THIRUVANMIYUR, CHENNAI- 600 041 PH- 044- 24524057 / 0836

FINANCIAL BID DOCUMENT - (Part-II)

ENQ.NO-004/2024-2025/EM Dt-10.04.2024

(Schedule of Quantities)

The Director
Kalakshetra Foundation
Thiruvanmiyur,
Chennai – 600 041.

Dear Sir/Madam,

SUB: “DRILLING OF BORE WELL AND PROVIDING SUBMERSIBLE PUMP” AT KALAKSHETRA FOUNDATION, THIRUVANMIYUR, CHENNAI- 41

With reference to your tender enquiry cited we are pleased to enclose the following as our financial bid for your kind consideration (as per given format).

“DRILLING OF BORE WELL AND PROVIDING SUBMERSIBLE PUMP” AT KALAKSHETRA FOUNDATION, THIRUVANMIYUR, CHENNAI- 41					
S.No	Description of Item	Qty	Unit	Rate	Amount
1	Supply, installation, testing and commissioning of suitable capacity vertical type submersible pumpset in the existing borewell confirming to the following duty condition operated on 240 V, 50 Hz, AC supply with delivery side opening size of 40 mm dia etc. complete as required. a) Head Range : 117 to 23 m b) Discharge range: 0.33 to 1.67 lps.	3.00	Nos		
2	Supply, installation, testing and commissioning of DOL starter with ammeter, voltmeter, water level controller for auto on& off, dry run preventor suitable for single phase, 240 V, 50 Hz, 1.5 HP vertical submersible pump set in the existing starter panel / wall including connections etc. as required.	3.00	Nos		
3	Supplying and laying 3 core 4 Sq.mm submersible PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC/DWC pipe etc., as required.	150.00	Mtrs		



कलाक्षेत्र प्रतिष्ठान

KALAKSHETRA FOUNDATION

THIRUVANMIYUR, CHENNAI- 600 041 PH- 044- 24524057 / 0836

4	Providing 200mm dia New Borewell upto 15.00 Mtr. Depth etc., as required.	3.00	Job		
5	Supplying and laying 150mm dia slotted water line borewell pipe with suitable wire mesh etc., as required.	45.00	Mtrs		
6	Supplying and laying of following size HDPE pipe ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and cutting, jointing etc.direct in ground (60 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required.				
	a) 25mm dia	120.00	Mtrs		
	b) 40 mm dia	50.00	Mtrs		
7	Supplying and fixing of three layer 1000 litres capacity (Sintex) water tank with ISI mark i/c necessary connections etc., as required	2.00	Nos		
8	Supplying and laying following sizes of CPVC water line pipe direct in ground/surface i/c excavation and refilling he same etc., as required.				
	a) 25mm dia	50.00	Mtrs		
	b) 32mm dia	300.00	Mtrs		
9	Supplying and fixing of following size UPVC/CPVC accessories in the existing delivery pipeline system including testing etc complete as required				
	a. 40mm dia connection Nipple	3.00	Nos		
	b. 40mm x 32mm reducer	4.00	Nos		
	c. 40mm dia Gate Valve	7.00	Nos		
	d. 40mm dia NRV	3.00	Nos		
	e. 40mm MTA CPVC	10.00	Nos		
	f. 40mm FTA CPVC	10.00	Nos		
	g. 40mm Bend CPVC	20.00	Nos		
	h. 40mm Coupling CPVC	30.00	Nos		
	i. 40mm Union	3.00	Nos		
	j. 25mm dia Elbow	10.00	Nos		
	k. 25mm dia gate valve	3.00	Nos		



कलाक्षेत्र प्रतिष्ठान

KALAKSHETRA FOUNDATION

THIRUVANMIYUR, CHENNAI- 600 041 PH- 044- 24524057 / 0836

	l. 25mm dia Coupling	10.00	Nos		
	m. 200mm dia Bore well Dummy	3.00	Nos		
	n. 40mm dia Bore Clamp	3.00	Nos		
	o. 12mm dia Rope	50.00	Mtrs		
	p. 32mm tank floatball valve	3.00	Nos		
	q. 25mm brass gate valve	10.00	Nos		
	Sub Total-				
	Add GST @				
	Grand Total				
Figures & words					
Grand total in Figures & words					

- We confirm that on being successful in the tender we would take up and execute the work.
- We confirm that we will abide by all the tender conditions and we do not have any additional conditions.

Signature with date and name of the signatory

Name of the agency with seal