CENTRE FOR ARCHITECTURAL RESEARCH & DESIGN

ARCHITECTURE O LANDSCAPE O INTERIORS

14thSeptember 2010

Smt.Leela Samson, Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai – 600041.

Dear Smt.Leela Samson,

Sub: Koothambalam theatre complex-Electrical works. (Tender documents)

Please find four Tender documents received as indicated below are Handed over today (14th September 2010 -12.05pm) for opening the Same.

- 1. S.S.Electricals, (CRF.MRAI) Chennai-78
- 2. Kevin Electricals Pvt.Ltd., Chennai-20
- 3. K.K.Singh Electricals, Chennai-45
- 4. Polar Electricals, Chennai

Thanking you,

With best regards,

(J.Ra. Jagakumar

Encl. As above

Chop to preside.
Calal
14/9

1408/10



iv. M/s.S.S.Electricals, K.K.Nagar, Chennai 78.

The amount quoted is Rs.68, 00,113/-which is inclusive of service tax and VAT. The BOQ was submitted along with the specifications and special conditions of contract of the tender documents. The EMD of Rs.68,000/-(Being 1 % of quoted value) was submitted by the way of demand draft No.832184 dated 13.9.2010 drawn on Corporation Bank Chennai service branch.

The above documents as received and opened were handed over to Mr.J.Ra.Jayakumar-COW-M/s.CARD today at 4.00 PM, for further processing by M/s.CARD.

Signatures of the members present:

M/s.Madras Electrical consultants – Mr.Nagaraj, representing M/s.CARD.

Mr.J.Ra.Jayakumar – COW- M/s.CARD.

Chief Accounts Officer – Kalakshetra Foundation

Administrative Officer – Kalakshetra Foundation.

Engineer officer - Kalakshetra Foundation.

Theatre Manager – Kalakshetra Foundation.

1. R. Nagarajan 14/9/10.

J. la Dayane 14/9/10

As Thyloria

S-Ramach 1419116

The same in the

Director ml 10

Kalakshetra Foundation,

Chennai

Proceedings for opening of tender documents for the work 'Electrical Installations to be carried out for proposed for M/s.Kalakshetra Foundation, Chennai'

Members present

- M/s.Madras Electrical consultants Mr.Nagarajarepresenting M/s.CARD.
- Mr.J.Ra.Jayakumar COW- M/s.CARD.
- Chief Accounts Officer Kalakshetra Foundation
- Administrative Officer Kalakshetra Foundation.
- Engineer officer Kalakshetra Foundation.
- Theatre Manager Kalakshetra Foundation.

Four tenders received for the above work were opened on 14.09.2010 at 3.30 PM at CAO's Chamber in Kalakshetra Foundation. The description of tenders received along with the EMD amount is detailed below.

The EMD amount received by way of cheque / Demand draft are retained in Kalakshetra Foundation.

i. M/s.K.K.Singh Electricals, West Tambaram, Chennai.

The amount quoted is Rs.56, 69,650/- exclusive of service tax, 10.30 %,. The BOQ was submitted as required in the tender documents, the EMD amount of Rs. 57,000/- was enclosed by way of demand draft No.058663, dated 14.9.2010 drawn on Karur Vysya bank, payable at Chennai CCO.

ii. M/s.Kevin Electricals Pvt.Ltd, Adyar, Chennai.

The amount quoted is Rs.50,60,591/- Inclusive of service tax. The BOQ was submitted along with the specifications and special conditions of contract of the tender documents. The EMD amount of Rs.50,000/-(which is less than 1% of the quoted value) is submitted by the way of Demand draft No.682551 dated 13.9.2010 drawn on City Union Bank limted payable at service branch Chennai.

iii. M/s.Polar Electricals, Chennai. 600033.

The amount quoted is Rs. 63,74,080/-exclusive of service tax and VAT. The BOQ was submitted along with the specifications detailed in the tender documents. The EMD of Rs.63,740/-(Being 1% of the quoted value) is submitted by the way of cheque No.431219 dated 20.9.2010, drawn on Axis Bank Limited, Chennai 83.

iv. M/s.S.S.Electricals, K.K.Nagar, Chennai 78.

The amount quoted is Rs.68, 00,113/-which is inclusive of service tax and VAT. The BOQ was submitted along with the specifications and special conditions of contract of the tender documents. The EMD of Rs.68,000/-(Being 1 % of quoted value) was submitted by the way of demand draft No.832184 dated 13.9.2010 drawn on Corporation Bank Chennai service branch.

The above documents as received and opened were handed over to Mr.J.Ra.Jayakumar-COW-M/s.CARD today at 4.00 PM, for further processing by M/s.CARD.

Signatures of the members present:

M/s.Madras Electrical consultants – Mr.Nagaraja.representing M/s.CARD.

Mr.J.Ra.Jayakumar – COW- M/s.CARD.

Chief Accounts Officer - Kalakshetra Foundation

Administrative Officer – Kalakshetra Foundation.

Engineer officer – Kalakshetra Foundation.

Theatre Manager – Kalakshetra Foundation.

M.B. Nagarjan 14/9/10.

J. la Dujarel 14/9/10

As Tiylor 100

J. Ramack 1419116

Jas manum ju

eceived all the Big boccomerge

I Ra. Bayarural

(I.Ra. Jaya Kamer) (-0.W) (5.10pm, Director 14/10

Kalakshetra Foundation, 19

Chennai

9

Proceedings for opening of tender documents for the work 'Electrical Installations to be carried out for proposed for M/s.Kalakshetra Foundation, Chennai'

Members present

- M/s.Madras Electrical consultants Mr.Nagarajarepresenting M/s.CARD.
- Mr.J.Ra.Jayakumar COW- M/s.CARD.
- Chief Accounts Officer Kalakshetra Foundation
- Administrative Officer Kalakshetra Foundation.
- Engineer officer Kalakshetra Foundation.
- Theatre Manager Kalakshetra Foundation.

Four tenders received for the above work were opened on 14.09.2010 at 3.30 PM at CAO's Chamber in Kalakshetra Foundation. The description of tenders received along with the EMD amount is detailed below.

The EMD amount received by way of cheque / Demand draft are retained in Kalakshetra Foundation.

i. M/s.K.K.Singh Electricals, West Tambaram, Chennai.

The amount quoted is Rs.56, 69,650/- exclusive of service tax, 10.30 %,. The BOQ was submitted as required in the tender documents, the EMD amount of Rs. 57,000/- was enclosed by way of demand draft No.058663, dated 14.9.2010 drawn on Karur Vysya bank, payable at Chennai CCO.

ii. M/s.Kevin Electricals Pvt.Ltd, Adyar, Chennai.

The amount quoted is Rs.50,60,591/- Inclusive of service tax. The BOQ was submitted along with the specifications and special conditions of contract of the tender documents. The EMD amount of Rs.50,000/-(which is less than 1% of the quoted value) is submitted by the way of Demand draft No.682551 dated 13.9.2010 drawn on City Union Bank limted payable at service branch Chennai.

iii. M/s.Polar Electricals, Chennai. 600033.

The amount quoted is Rs. 63,74,080/-exclusive of service tax and VAT. The BOQ was submitted along with the specifications detailed in the tender documents. The EMD of Rs.63,740/-(Being 1% of the quoted value) is submitted by the way of cheque No.431219 dated 20.9.2010, drawn on Axis Bank Limited, Chennai 83.

S.S. ELECTRICALS (CHENNAI) PRIVATE LIMITED

ELECTRICAL ENGINEERS AND CONTRACTORS 'A' GRADE No.758, 94th Street, 15th Sector, K.K. Nagar, Chennai - 78.

Tel. : 044-64558095

044-43530320

Mobile: 98408 40612 : 98408 40613

E-mail:sse078@hotmail.com

sse078@gmail.com

22/09/10

SS/KF/01/10-11

To,

M/S.KALAKSHETRA FOUNDATION,

Chennai.

Sub: - Final Price Discount for Electrification Works for the Proposed Auditorium.

Dear Sir,

With Reference to the project and based on the discussion we had with the consultant our final discount will be 10% on the total BOQ value.

Hope our offer is in line with your requirements waiting for your valuable order please.

Thanking you

Yours sincerely

R.BHASKAR

FOR S.S.ELECTRICALS (CHENNAI) PVT LTD

VELACHERY CHENNAI-42.



(6)



Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/TA/100/2010/427

17.09.2010

To

The Director, Kalashetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation to be carried out for M/s. Kalashetra at Chennai - Submission of Revised offer - Reg.

REF: - Negotiation had with electrical consultant.

With reference to the negotiation, we are pleased to offer 3% discount from our total quoted value.

Total quoted value

- Rs. 50,60,591.00

Less: 3% Discount

- Rs. 1,51,817.73

Final Offer

- Rs. 49,08,773.27

We hope that, we have given best competitive offer and look forward your valuable order.

Thanking you, Your's faithfully,

for Kevin Electricals Pvt Ltd,

L.Wilson Susai Raj (Managing Director)







Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank) Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

K.K.SINGH ELECTRICALS GRADE -A-ELECTRICAL CONTRACTOR

TIN .NO.33970885459/05-06
CST. NO. 839866 Dt. 04.04.05
AREA CODE 0 4 5
No.3, NEW MARKET
WEST TAMBARAM,CHENNAI - 600 045.
PH: 22266663, 22260939 FAX: 22264551.

To

18.09.2010

The Director, M/s. Kalakshetra Foundation, Chennai.

Sir,

A

Sub: Electrical Installation to be carried out for proposed for M/s. Kalakshetra Foundation at Chennai.

Further to the negotiation we had with Mr.N.R.Nagarajan. MEC., on 17th Sep 2010 at MEC Office. We are pleased to offering a discount of 6.5% for all individual items quoted in this tender only. Our prices are inclusive of all taxes (Except Service Tax).

Looking forward to work with you.

Summary:

1. Supply Value

Rs.44,93,420.00

2. Erection Value

Rs. 8,07,675.00

3. Final Value

Rs.53,01,095.00

Thanking you, Yours faithfully,

For K.K.Singh Electricals

Manager







2. M/s.Kevin electricals.

M/s Kevin electricals, have submitted their technical offer, the vendor's offer is in line with the technical requirements of our enquiry specification which is acceptable and also they have submitted their revised offer in which they have provided a discount of 3% from the initial offer. Total value in the Final offer comes to Rs.49,08,773.27/-

3. M/s.S.S Electricals.

M/s SS electricals, have submitted their technical offer, the vendor's offer is in line with the technical requirements of our enquiry specification which is acceptable and also they have submitted their revised offer in which they have provided a discount of 10% from the initial offer. Total value in the Final offer comes to Rs.6,1,18,201.97

Recommendation

Based on the above all three vendors are technically acceptable, based on the commercial terms and conditions M/S.Kevin Electricals have quoted lower than the other two vendors and they have the manpower and their of quality of work executed by them in our earlier projects are good. Hence we recommend to place the order on M/S. Kevin electricals.

Attachments

- 1) Revised Comparative Statement(Soft Copy)
- 2) Offer from KK Singh Electricals(Hard Copy)
- 3) Offer from Kevin Electricals(Hard Copy)
- 4) Offer from SS Electricals(Hard Copy)
- 5) Tender opening(Hard copy)

I. Ra. Jayanel)
C. Ra. Jayanennar)



Recommendation for Placement of Order for Electrical supply and installation contract

The enquiry for Electrical supply and installation contract was sent to the following vendors via Email dt 10.09.2010

SI. No.	Description
1)	Electrical Technical specification
2)	Bill of quantities
3)	Makes of Material
4)	Special conditions of contract

The enquiry for the above Electrical supply and Installation work was sent to the following vendors.

- 1) KK Singh Electricals, Chennai.
- Kevin Electricals Pvt Ltd.., Chennai.
- 3) Polar Electricals, Chennai.
- 4) SS Electricals, Chennai

Hard copies of Offers were received from all the above vendors and offers were opened on 14.09.2010 in front of client.

Based on the initial offer, Polar electricals didn't follow the special conditions of contract and they didn't provide proper EMD Dated cheque, hence their offer is not considered for further evaluation.

Further we had Technical and commercial negotiation with the following vendors on 17.09.2010, at our office.

- 1) KK Singh Electricals, Chennai.
- 2) Kevin Electricals Pvt Ltd.., Chennai.
- 3) SS Electricals, Chennai

1. M/s.KK Singh Electricals.

M/s KK singh electricals, have submitted their technical offer, the vendor's offer is in line with the technical requirements of our enquiry specification which is acceptable and also they have submitted their revised offer in which they have provided a discount of 6.5% from the initial offer. Total value in the Final offer comes to

TO D. Ra. Daylow D.

Rs.5, 3,80,486.74

N.a. Nagarejar.



September 18th, 2010

M/S. Centre for Architectural Research & Design 10A, Dhanalakshmi Colony, 1st Street, Vadapalani CHENNAI - 600 026. Kind Attn: (i) Mr. Ravi Nilakandan

Dear Sir,

Sub: Revised comparative & Recommendation for placement of order for Electrical supply and installation contract for Koothambalam at M/s. Kalakshetra Foundation.

We are attaching herewith "Revised comparative and our recommendation" letter for placement of order for Electrical supply and installation contract.

Kindly acknowledge,

M.S.Ramesh

Madras Electrical Consultants

Velachery, Chennai - 600 042. Phone: 044 - 29728201 / 03

Email: mecramesh@eth.net/msramesh@mec-india.com

No.6, Park Avenue 1st Cross Street,



CENTRE FOR ARCHITECTURAL RESEARCH & DESIGN

ARCHITECTURE O LANDSCAPE O INTERIORS

Smt. Leela Samson,

Director,

Kalakshetra Foundations,

Thiruvanmiyur,

Chennai - 600041.

21st September 2010.

Sub: Award of works - KOOTHAMBALAM

1. Ms. Kevin Electricals

- Electrical supply and installation
- 2. M/s Unimech Systems (Chennai) Pvt Ltd
- **HVAC** works

Dear Smt. Leelaji,

As advised by our consultants Sri. Ramesh of Ms. Madras Electrical consultants and for electrical works and Sri. Ramesh of Ms. Air Treatment Engineering for HVAC works, you may please award the works to Ms. Kevin Electricals & Ms. Unimech systems. (HVAC)

Regards,

Ravi Nijlakantan

Encl: As above



If approved, the work order may be issued to M/s.Kevin Electricals at a total cost of Chennai Engineers at a a total cost of Rs. 49, 08,773.27/-(Rupees Forty Nine lakh eight thousand seven hundred and seventy three and paise twenty seven only) after given 3% discount from the initial offer.

DIRECTOR

P.T.Krishnan

Drate for approad

30

S. Rame D. 21/9/10

John, CAO

Inla DIRECTOR 24/9

(3)

C:\ 2010-2011\V.Admin\2. Engineering\i.Plan\b.	September 24, 2010
Electrical\Koothambalam-Electrical installation work	-

Sub: Koothambalam - Electrical Installation works - award of work- Reg

Ref : i) Consulting Architect (M/s.CARD recommendation) dated1st September 2010.

ii) Electrical consultant -M/s.Madras Electrical consultant's letter dated 18th September.2010.

In connection with, the upgradation of Koothambalam, M/s.Madras Electrical Consultants from Velachery representing the Consulting Architect (co-ordinating with M/s.Sound Wizard sound consultants, Heating ventilating and Air conditioning system (HVAC) consultants and Lighting consultant Mr.Gautam Bhattacharya from Delhi).has prepared the details of electrical installation works to be done for the Koothamabalam

Accordingly, M/s.Madras Electrical Consultants have invited the tenders and all the sealed tenders were received by Mr.J.Ra.Jayakumar – Clerks of Works and acknowledged. The tenders were opened in Kalakshetra Foundation / Central office by Architect nominated representative, in the presence of officials and contractors / his representatives in the Kalakshetra Foundation premises.

The entire opened tender bid documents submitted by the contractors have handed over to M/s.CARD –Consulting Architect Sri.Ravi Niilakantan through Mr/J.Ra.Jayakumar-Clerks of work with details of the tender for preparing comparative statement, comments and recommendation for award of work

Subsequent to the negotiation, M/s.Madras Electrical Consultants had with the qualified bidders, received the revised offer from the bidders, except M/s.S.S.Electricals.

Based on the revised quotations received by M/s.Madras Electrical Consultants have prepared the comparative statement drawn accordingly and submitted the recommendation for award the contract to M/s.Kevin Electricals at a total cost of Rs.49,08,773.27/-(Rupees Forty Nine lakh eight thousand seven hundred and seventy three and paise twenty seven only) after given 3% discount from the initial offer.

M/s.CARD – Shri.Ravi Niilakantan had recommended to awarding the work to M/s.Kevin Electricals based on M/s.Madras Electrical consultant advice.

.....2



M/s.CARD - Shri.Ravi Niilakantan had recommended to awarding the work to - Page 22 M/s.Kevin Electricals based on M/s.Madras Electrical consultant advice.

If approved, the work order may be issued to M/s.Kevin Electricals at a total cost of Chennai Engineers at a total cost of Rs. 49, 08,773.27/-(Rupees Forty Nine lakh eight thousand seven hundred and seventy three and paise twenty seven only) after given 3% discount from the initial offer.

Anla Danoro Washa Huffel DIRECTOR 24/9'10

P.T.Krishnan 28 9 10



C:\ 2010-2011\V.Admin\2. Engineering\i.Plan\b.	September 24, 2010
Electrical\Koothambalam-Electrical installation work	

Sub: Koothambalam - Electrical Installation works - award of work- Reg

Ref : i) Consulting Architect (M/s.CARD recommendation) dated1st September 2010. - Page 22

ii) Electrical consultant -M/s.Madras Electrical consultant's letter dated 18th September.2010.

In connection with, the upgradation of Koothambalam, M/s.Madras Electrical Consultants from Velachery representing the Consulting Architect (co-ordinating with M/s.Sound Wizard sound consultants, Heating ventilating and Air conditioning system (HVAC) consultants and Lighting consultant Mr.Gautam Bhattacharya from Delhi).has prepared the details of electrical installation works to be done for the Koothamabalam

Accordingly, M/s.Madras Electrical Consultants have invited the tenders and all the sealed tenders were received by Mr.J.Ra.Jayakumar – Clerks of Works and acknowledged. The tenders were opened in Kalakshetra Foundation / Central office by Architect nominated representative, in the presence of officials and contractors / his representatives in the Kalakshetra Foundation premises.

The entire opened tender bid documents submitted by the contractors have handed over to M/s.CARD –Consulting Architect Sri.Ravi Niilakantan through Mr/J.Ra.Jayakumar-Clerks of work with details of the tender for preparing comparative statement, comments and recommendation for award of work

Subsequent to the negotiation, M/s.Madras Electrical Consultants had with the qualified bidders, received the revised offer from the bidders, except M/s.S.S.Electricals.

Based on the revised quotations received by M/s.Madras Electrical Consultants have prepared the comparative statement drawn accordingly and submitted the recommendation for award the contract to M/s.Kevin Electricals at a total cost of Rs.49,08,773.27/-(Rupees Forty Nine lakh eight thousand seven hundred and seventy three and paise twenty seven only) after given 3% discount from the initial offer.2

16108

being 10

Founder: Smt. Rukmini Devi Chairman: Justice Sri S. Mohan Director and Secretary: Ms. Leela Samson

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

09.06 LT PANELS

Relay Setting, Testing at Site before commissioning.

09.07 TESTS FOR INTERNAL WIRING

AT SITE

Insulation Resistance Tests at

- a) Individual circuits
- b) Individual MCB and FUSE DISTRIBUTION BOARDS
- c) Each Panel Boards, Sub Panel Boards
- d) Main Incoming ACBs

NOTE:


All tests shall be carried out with final appliances / equipments connected and disconnected and with 1000 V Megger.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

DIRECTOR



M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

VISUAL / ELECTRICAL

- a) Clean moving and fixed contacts of LT Breakers, Contactors, Switch Fuse Unit with CRC 2 26.
- b) Check the rating of Power and Control Fuse against approved drawings. Fuses shall be undamaged and fit for service.
- c) Check for voltage rating of auxiliary equipment viz. Closing and tripping coils of breakers, auxiliary supply of all protection and auxiliary relays, spring charging / power drive motors against approved drawings.
- d) Insulation resistance tests as IS 732 Part III.

09.05 CABLES

Type test certificate for all the type of cables i.e. control L.T. and H.T. shall be furnished along with the tender.

All the tests as per relevant standards as per manufacturer's standard practices shall be carried out on all the type of cables.

The following minimum test shall be carried out on all the type of cables.

A. ACCEPTANCE TEST

- a) Annealing Test (for copper)
- b) Tensile Test (for Aluminum)
- c) Wrapping Test (for Aluminum)
- d) Resistance Test
- e) Test for thickness of insulation and sheath
- f) Partial discharge test (for 11 KV and above rated cables).
- g) Insulation Resistance Test
- h) High Voltage Test

C. ROUTINE TEST

- a) Conductor Resistance Test
- b) Partial discharge test (for cables rated 11 KV and above)
- c) High Voltage Test
- d) Insulation Resistance Test

C. AT SITE

- a) High Voltage Test
- b) Insulation Resistance Test
- c) Continuity Test

MADRAS ELECTRICAL CONSULTANTS

DIRECTOR Pag

Page 34 of 3,

For Kevin Electricals Pvt. Ltd.



M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

- d) Operational Tests
- e) Tests to prove interchangeability of similar parts

B. AT SITE

- a) Power frequency high voltage withstand test.
- b) Insulation Resistance Test.
- c) Operational Tests
- d) Tests to prove interchangeability of similar parts.

09.04.1 TESTING AND COMMISSIONING OF POWER DISTRIBUTION EQUIPMENTS

In addition to the checks and tests specified earlier or later the following shall be applicable for all Power Distribution equipments.

After installation but before any power supply in connected, the contractor shall make a complete mechanical and electrical check of the system. These shall include, but not restricted to the following:-

MECHANICAL CHECKS

- a) Visually inspect all equipment / items for defects if any, and check equipment numbers against approved drawings to ensure that equipment has been correctly located and proper installation is done.
- b) Check, name plate details and wiring diagrams indicated on the equipments viz switch boards, disconnecting switches load break switches, PDBs, etc., for conformity with the data given in approved drawings.
- c) Check that all moving parts, drive motors, linkages in the disconnecting switches, breakers are properly lubricated by approved / recommend type of lubricant.
- d) Check for mounting of all separately supplied accessories against approved GA Drawings for equipment viz. Breaker, disconnecting switch, busduct, Rising Main etc.

ELECTRICAL CHECKS

VISUAL / MECHANICAL

a) Check proper gasketing of outdoor, installed equipment, operating cabinets etc. Busduct end terminations, inspection openings, joints between standard erections, Switchboards, PDBS, DBs.

MADRAS ELECTRICAL CONSULTANTS

Page 33 of 35

1

For Kevin Electricals Pvt. Ltd.

Managing Director

DIRECTOR



M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

The Contractor shall provide Purchaser/ Engineer with complete test report in a form approved by the Engineer / Purchaser.

Test results obtained at site shall be compared with factory test results to ensure the condition of the equipment.

09.02 TESTING

Manufacture's test certificates shall be furnished by the supplier for all bought out materials, components etc.

Wherever such test certificates are not available, the item shall be got tested by the supplier at his own expense at the government recognised laboratories mutually agreed upon.

The main equipment and components shall be carefully examined to determine their conformance with this specification with respect to material and workmanship, finish marking, dimensions, arrangement, and to assess its conformance with other requirements stated or reasonably implied and not covered by specific tests.

Complete tests shall be made in factory by the contractor to ensure that the performance and operating characteristics of the equipment are satisfactory and to determine whether or not guarantee have been met.

At the conclusion of all test procedure the equipment shall be examined for signs of wear cracks, distortion or incipient damage of any sort and any defects shall be corrected before the equipment is shipped / commissioned.

In the event of failure of the product or any part thereof to fully meet any inspection or test requirement specified, the Contractor shall notify the Purchaser / Engineer, if he wishes to repair and / or use such product or part.

The tests to be carried at Works / Site for various items shall be as indicated against each item.

09.03 POWER DISTRIBUTION BOARDS /LIGHTING DISTRIBUTION BOARDS

Routine tests as per applicable standards shall be carried out at Contractors' works. The minimum tests at works and at site shall be as follows:-

A. AT WORKS

a) Power frequency high voltage withstand test

b) Insulation Resistance Test.

c) Dimensional tests

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

HETRA

ANMIYUR

ELA SAMSON

DIRECTOR

CHENNA OUT

de 32 of 35

E CAL CONCE

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

Inspection of equipment by the Purchaser / Engineer shall be only with a view to ensure that the equipment is fabricated / manufactured, assembled, tested, supplied and commissioned as per approved drawings and prescribed specifications.

Inspection by the Purchaser / his representative shall in no way relieve the supplier of his responsibilities as per the contract and shall be in no way binding on the purchaser / engineer.

Immediately after order placement, the Purchaser / Engineer shall in consultation with the supplier draw up a detailed inspection schedule to fix up the procedure and timing of inspection of various materials components, subassemblies, assemblies testing etc.

The supplier shall not despatch any materials from his works until they have been inspected and accepted by the Purchaser / Engineer by issuing a provisional acceptance certificate.

The supplier shall intimate the Purchaser / Engineer atleast 2 weeks in advance before any material is ready for inspection /tests. The supplier shall list out all such material / items with their respective weights.

The supplier at his own expense provide free and safe access and all necessary facilities, equipment etc., to facilitate inspection by the Purchaser / Engineer.

Immediately after approval of drawings / documents, the supplier shall give 4 sets of all such drawings / documents to the Purchaser to enable the Purchaser / Engineer to carry out inspection of the equipment.

Purchaser / Engineer may reject the whole or any part of the equipment at any time if after inspection / testing. Purchaser / Engineer at their sole discretion determine the equipment or any part there of to be unsatisfactory or does not fulfil the terms of the contract, Purchaser's / Engineer's decision regarding rejection shall be final and binding on the supplier.

Routine and type test certificates shall be submitted for approval on completion of the tests. Number of copies required for approval and procedure of submission shall be intimated to the supplier.

On successful completion of erection / installation, each item / equipment will be thoroughly inspected by the Purchaser / Engineer for correctness and completeness of installation.

The Site tests, pre commissioning tests and commissioning tests shall be carried out in the presence of the Contractor and the Purchaser / Engineer.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

DIRECTOR

Managing Director

CHEMINA AND OF

Page 31 of 35

Tender for Electrical Installation

Specification for Electrical

For all switch boards, control panels, power control centres, a clear space of not less than 1000 mm. shall be provided in front of the equipment. In case, where the equipment is provided with drawout unit, a minimum clearance of 2,000 mm shall be provided.

For all electrical equipment a minimum clearance headroom of 500mm shall be provided.

All motors located away from the feeding and control panels and for which control desk of posts are not within visible location, shall be provided with readily accessible and easily operated, locally mounted lockable type `stop' pushbuttons in the control circuits.

All electrical equipment operating on 415 V or higher voltage shall be provided with caution notice boards of approved type and shall be affixed permanently in a conspicuous position. Where a group of equipment is located within a switch / control room or within a fenced area, the notice board shall be fixed at the entrance.

All moving parts of the equipment which are exposed and liable to cause hazard to the operating and maintenance personnel shall be suitably protected by metallic guards.

In front of all the switch boards rubber mats shall be provided for personnel safety.

Open type control panel or open type busbars shall not be installed inside the plant building.

In accordance with the requirement of the Indian Electricity Rules, the following shall be provided:-

- Danger Boards and shock treatment charts in two languages viz. English and Tamil.
- ii. 750mm wide tested rubber mats of thickness not less than 19mm shall be provided in front of all switchboards and control panels.

09.00 TESTS AND EQUIPMENTS / INSTALLATION

GENERAL

VELACHERY CHENNAI-42

The Purchaser / Engineer shall have the right to Inspect / Witness on the equipment or any part there of at various stages of fabrication. manufacture, sub-assembly, assembly and testing, erection and commissioniong. Inspection / test shall be carried out at the supplier's works / his sub – contractor's works and at site as specified.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

DIRECTOR

Page 30 of 35

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

Earth conductors shall be kept electrically separated from the metal work of surface pipes which are carrying gases or inflammable liquids.

In explosive and hazardous locations like gas pipe lines, fuel oil tanks etc. provisions shall be made for protection against static discharage by suitably connecting the equipment to an earthing system which is segregated from the Hospital earthing system.

Conductor size adopted for earthing ring shall in no case be less than that of the earth continuity conductors connected to it. The size of earthing leads connected to earth electrodes shall not be less than that of the earthing main. Unless otherwise specified earthing ring for main buildings shall not be less than $50 \, \text{mm} \times 6 \, \text{mm}$. MS Galvanised Flats.

For earthing of building columns / structures 50 \times 6mm. galvanised MS Flats shall be used.

Conductors used for earthing shall be in no case have cross sectional area less than 4 sq.mm. stranded GI wire.

All 3 phase equipments shall have duplex earthing. Whereas single phase equipments shall have only one run.

The minimum size of galvanised GI flat/wire for earthing of various equipment shall be as follows unless otherwise specified:-

i. Power control centres auxiliary power

distribution boards, etc.

50 x 6 mm

ii. Sub Power Control Centres

25 x 6 mm

iii. LDBs & PDBs

2.5 sq.mm PVC Insulated copper wire

08.00 CLEARANCE AND SAFETY

For every electrical switchboard, control panel, power control centres etc., that require back access the space behind the equipment shall generally be 1,000 mm. but in no case be less than 762mm. This space shall also be adequate to permit at least a 90 Deg. opening of doors or hinged panels. In such cases where back clearances are provided, there shall be a passage-way from either end of the equipment clear to a height of 1800mm. Where the equipment are not required to be attended from the back, if equipment shall be placed along the wall/structure having clearances less than 200mm.

MADRAS ELECTRICAL CONSULTANTS

DIRECTOR

Page 29 of 35

For Kevin Electricals Pvt. Ltd.

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

and shall be provided with one coat of bituminised paint, at all welded joints to prevent corrosion.

Earthing ring wherever embedded in concrete shall be laid parallel to the column rows of buildings.

Earth continuity conductor embedded in concrete shall generally follow the shortest route and wherever possible shall be taken along pipes embedded for laying of cables. Earth conductors laid on cable racks, trays etc. shall be placed in accessible location keeping adequate clearance to

facilitate easy connections. Earth conductors laid along plant/equipment structure, wall, ceiling etc.

shall maintain symmetry with other installations and shall be uniformly spaced with cables/utility pipes running along the same route. Galvanized MS Saddles shall be used for clamping earth

conductors on structures, wall ceiling etc. Flats shall be supported at intervals of 500mm. Welding

shall be done wherever earth flats are to be run through rack/cable tray.

As far as possible all earth terminations and connections shall be visible for inspection. Each earthing system shall be so designed that testing of individual earth electrode is easily possible. For earth bus

embedded in floor slabs, stub-ups shall be provided at convenient locations near the equipment as well as building columns for connecting earth continuity wires leading to the equipment and structures.

Alternate columns of structural buildings shall be connected to earthing ring.

Where the power to the equipment is fed flexible training cables, the same shall contain one separate earth continuity conductor having the same cross section as that of the current carrying conductor.

Earth connections to equipment subjected to movement, vibrations and shocks shall be made by stranded wire having enough loop.

Connection of earthing leads to earth electrodes and terminations of flat earth continuity conductors to equipment shall be made by means of bolting. Connection of stranded earth wire to earth bus as well as

to equipment shall be made through crimping type lugs and bolting. Jointing and tapping of flat earth conductor shall be done by means of welding. Termination of earthing flats to building structures, shall be done by means of welding. Termination of earthing flats to building structures, shall be done by means of welding.

Cable screens and armours shall be bonded to earthing system in accordance with IS:1255. Also, metal pipes and conduit system carrying cables shall be bonded and effectively earthed.

MADRAS ELECTRICAL CONSULTANTS

ANMIYUR, CHENN

DIRECTOR

ELA SAMSON

2Page 28 of 35

For Kevin Electricals Pvt. Ltd.

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

For Plant building and Switch/Control room one main earthing ring shall be provided along the plant/building periphery connected to required number of earth electrodes. The earthing ring shall be taken 1000mm away from building column/wall and shall be laid directly buried in ground. Main earthing ring shall be further cross-connected and a mesh formed depending layout and location of the equipment. The cross-connections shall generally run in cable trenches, or embedded in concrete floor based on the layout. For buildings having a number of floors, separate earthing rings shall be established in each floor.

All non-current carrying metallic parts of various electrical equipment as well as cable armouring metallic conduit/GI pipe system, cable racks/trays brackets, supporting structures etc. shall be effectively earthed. Earthing of medium and high voltage equipment shall be done by means of two separate earth conductors connected either directly to earth electrodes or to an earthing ring irrespective of use of armoured cable or metallic conduit/GI pipe.

Building/technological steel structures, metallic utility pipes shall not be used as earth continuity conductor.

All earthing system shall be so designed as to ensure effective operation of protective gears in case of earthfaults. The total earth resistance at any point of the earthing system for substations and main plan buildings shall not be more than one ohm. However, at other points the value shall not exceed 5 ohms.

The earth resistivity values of soil will vary in different areas of the site. For all substations and main plant buildings, number of electrodes to be provided for the earthing system shall be decided after actual

measurement of soil earth resistivity at that location. However, after complete installation actual earth resistance shall be measured in all cases and, if required, additional electrodes shall be provided to achieve the values indicated above. No earth ring shall have less than two earth electrodes.

Earth copper plate shall comprise $600 \text{mm} \times 600 \text{mm} \times 600 \text{mm} \times 600 \text{mm}$ to 3000 mm in an earth pit of $700 \times 700 \times 3500 \text{mm}$.

Generally, main earthing rings and earthing leads shall be directly buried in ground. Additional earthing rings wherever provided inside plant buildings/substations and earth continuity conductors shall be taken either exposed on cable racks/trays, structures, walls, ceiling etc. or embedded in

concrete depending on installation. Earth conductor directly buried be taken at a depth of 600mm.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

LEELA SAMSON

NMIYUR, CHEN

Page 27 of 3

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

06.10 MEASUREMENT OF POINT WIRING

Points on the basis of length per point inclusive of circuit mains shall be classified as under:

Average point a)

Length per point not exceeding 10 M.

b) Special point for Light, Fan and 5A socket outlet points Length per point exceeding 10 M

The rate for average point shall be on a per point basis.

For special points, the extra length of wiring over and above the length of Meters specified shall be measured and paid for. Rate for the same shall be given in the offer separately.

In case of points with more than on light point controlled by the same switch, they shall be measured on a set basis (i.e.) Two lights controlled by one switch shall be considered a set and so on. The distance between the first point and subsequent point shall not be more than 5 mts. In case of more than two lights controlled by one switch only the average distance between light points shall be considered.

06.11 ADDITIONAL CONSIDERATION FOR INTERNAL WIRING

The minimum size of pipe shall be 25mm. dia only. The wall thickness shall 2mm. only. The chases in the wall shall be neatly made and in ample dimensions to permit the conduit to be fixed in the manner desired. In case of buildings under construction, conduits shall be burried in the wall before plastering. These shall be grouted and covered with cement and mortar, neatly finished at the plane of the unplastered brick work and scratched for providing key to the plaster and cured. Under no circumstances finished plastered surfaces shall be allowed to be chased for the conduit work. Before taking up chasing of the wall the routes shall be marked and got approved by Engineer. In case of exposed brick/rubble masonry work, special care shall be taken to fix the conduit and accessories in position along with the building work

07.00 EARTHING

SELECTION AND INSTALLATION OF SYSTEM AND EQUIPMENT EARTHING

The method adopted for system as well as equipment earthing shall be in accordance with the code of practice for earthing IS:3043-1966 and shall also comply with the relevant clauses of Indian Electricity Rules.

MADRAS ELECTRICAL CONSULTANTS

NMIYUR, CHENN

ASAMSON

Page 26 of 35

DIRECTOR



M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

The following shall be deemed to be included in the point wiring:-

- a) Switch
- b) Ceiling rose or connector as required
- c) Any special or suitable round block for neatly housing the connector and covering the fan hook in case of fan point.
- Bushed conduit, G.I.Sleeves where cables or pipes passes through wall etc.
- e) Earth wire from three pin socket outlet point/fan regulator to common earth including earth dolley.
- f) All wood or metal blocks, boards and boxes sunk of surface type, including those required for mounting fan regulator but excluding those under the main distribution switchgear.
- g) All fixing accessories such as clips, rails screws, rawl plugs, wooden plugs etc. as required.
- h) Connections to ceiling rose, connector socket outlet, lamp holder, switch and fan regulator etc.
- i) Looping the same switch board interconnections between points on the same circuit.
- j) Providing fish wire in conduits while recessed circuiting work is undertaken.

06.09 LENGTH PER POINT

The term "Length per point" in point wiring in the case of the fan and light points shall mean the distance between the switch and ceiling rose, connector or back plate, lamp holder depending upon the fitting, measured along the run of wiring irrespective of the number of wires in the run.

In the case of socket outlet points, the length shall mean the distance between the socket outlet and the tapping point of live wire on the nearest switch board.

MADRAS ELECTRICAL CONSULTANTS

VELACHERY

Page 25 of 3

For Kevin Electricals Pvt. Ltd.

Managing Director

VMIYUR, CHENN

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

The columns headed S applies to run of conduit which have distance not exceeding 4.25mm between draw in boxes and which do not deflect from the straight by an angle or more than 15 degrees. The columns headed 'B' apply to runs of conduit which deflect from the straight by an angle of more than 15 degrees.

06.08 SWITCHES AND ACCESSORIES

All switches shall be placed in the live conductor of the circuit and no single pole of fuse shall be inserted in the earthed neutral conductor of the circuit.

Single pole switches (other than for multiple control) carrying not more than 15 Amps may be of the piano key type/moulded plat type and the switch shall be ON' when the knob is down.

The switch box shall be placed in the live conductor of the circuit and no single pole of fuse shall be inserted in the earthed neutral conductor of the circuit.

Single pole switches (other than for multiple control) carrying not more than 15 Amps may be of the piano key type/moulded plat type and the switch shall be 'ON' when the knob is down.

The switch box shall be made of metal on all sides, except on the front. In the cases of cast iron boxes wall thickness shall be atleast 3mm. and in case of welded mild steel sheet boxes the wall thickness shall not less than 18 guage for boxes upto a size 20 cms x 30 cm. above this size 16 guage MS boxes shall be used. Except where otherwise stated 3mm, thick phenolic laminated sheets shall be fixed on the front with aluminium alloy/braa/cadmium plated iron screws as approved by Site Engineer. Clear depth of the box shall be minimum 60mm.

To facilitate drawing of wires in the conduit, GI Fish wire of 16 SWG shall be provided while laying recessed conduit.

Point wiring shall include all works necessary to complete wiring of a switch circuit of any length from the tapping point on the distribution circuit to the following (via the switch).

- Ceiling rose or contractor (in the case of ceiling / exhaust fan points) a)
- b) Back plate (in case of flourescent fitting with down rods etc).
- Socket outlet (in the case of socket outlet points) c)
- Lamp holder (in case of wall brackets, bulk head and similar fittings). d)

All civil works like chippiding, making good the damages, drilling holes in e) walls etc., are to be done by the contractor only

MADRAS ELECTRICAL CONSULTANTS

VELACHERY CHENNAL-42

POVANMIYUR, CHENNA For Kevin Electricals Pvt. Ltd.

Managing Director

ELA SAMSON

DIRECTOR

Page 24 of 3

TURAL

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

The termination of MS Pipe in rotating machines subject to vibration as well as connections to equipment required to be disconnected at periodic intervals shall be made by means of flexible pipes. Flexible metallic pipes shall also be used for termination of connection to limit switches, level switches, pressure switches etc. The equipment where the direct termination of rigid pipe is inconvenient, the termination can be done by means of flexible pipe. The use of flexible pipe in outdoor location shall be avoided as far as practicable.

Flexible pipes shall be of liquid tight galvanised heavy duty interlocked type generally conform to IS: 3480-1966 with PVC Jacket extruded over the pipe. The adapter for coupling rigid MS Pipe to flexible conduit and termination to equipment shall be of either cast aluminium or galvanised sheet steel.

Suitable junction/inspection boxes according to requirements shall be provided to permit periodical inspection and to facilitate replacement of wires. However, such boxes shall be located and arranged so that they are not in irregular postures. These locations shall also be specifically shown in the conduit layout of the shop drawings and approval shall be obtained before installation.

However, such installation and the number of such boxes shall be minimised. The boxes shall be mounted flush with the wall or ceiling. Minimum 65mm. depth junction boxes shall be used in roof slabs and depth of boxes in other places shall be as per IS: 2667-1977. All outlets such as switches wall, sockets etc. shall be flush mounting type.

06.07 CONDUIT CAPACITY

Maximum number of PVC insulated cable conforming to IS:694-1977 that can be drawn in one conduct shall be as follows:-

Nominal cross section area of conductor in Sa.mm.

	25mm		32mm		38mm		51mm		64mm	
	S	В	S	В	S	В	S	В	S	В
1.50	10	8	18	12		-	-	-	-	-
2.50	8	6	12	10	-	-	-	-	-	-
4	6	5	10	8	-	-	-	-	-	-
6	5	4	8	7	-	-	-	-	-	-
10	4	3	6	5	8	6	10	7	12	8
16	. 2	2	3	3	6	5	8	6	9	7
25	-	-	3	2	5	3	6	5	8	6
35	-	-	-	-	3	2	5	3	6	5
50	-		-	-	-	-	4	3	5	4
70	-	-	-	-	-	-	-	-	-	-

MADRAS ELECTRICAL CONSULTANTS

LEELA SAMSON DIRECTOR

Page 23 of 35

RUVANMIYUR, CHENN

For Kevin Electricals Pvt. Ltd.



M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

In case of open wiring M.S.Pipes shall be fixed by heavy guage saddles secured to suitable 6mm. thick MS Spacers of adequate size fixed to the concrete or plastered brick surface with proper methods at an interval of not more than one metre but on either side of the coupler of bends or similar fittings. Saddles shall be fixed at a distance of 30 cm. from the centre of such fittings. The saddles shall not less than 24 guage for conduits upto 25mm. dia and not less than 20 guage for larger dia.

All conduits after erection shall be tested for electrical continuity.

Fixing of standard bends or elbows shall be avoided as far as practical and all curves maintained by bending the conduit itself with a long radius which will permit easy drawing conductors. All thread joints of conduit shall be treated with some approved "preservating compound" to secure against rust.

Pipe runs between outlet and outlet or between outlet and equipment shall not contain more than two 90 Deg bends (180 Deg total) including those bends located immediately at the outlet or fittings. Straight run of cables in pipes shall be limited by provision of approved type of pull boxes once every 15 mts.

For equipment and devices having MS Pipe entry arrangement other than standard MS Pipe adapter, transition adapters shall be provided as required to enable the MS Pipes to be properly terminated.

Insulated type end bushings shall be used where conductors enter or leave pipes.

To facilitate pulling of cables in pipes, powdered soft, stone, plastic soap or other dry inert lubricant may be used but grease or other material harmful to the cable sheathes shall not be used.

Ends of MS Pipe shall be cut square and the threads cut in the field shall have the same effective length and the same dimensions and taper as specified for factory cut threads. Ends of pipe shall be reamed to remove burrs and sharp edge after threads are cut.

All joints shall be made tight with a minimum of 5 boxes, panels, cabinet etc. by means of one lock-nut outside and one inside and shall be provided with bushing of approved insulating materials unless the pipe is directly screwed into a thread hub in the box.

In damp locations the entire pipe system, including all boxes and fittings used, shall be made water-tight and the pipe shall be so mounted on spacers so as to leave minimum of about 6mm. gap between the GI pipe and the surface over which it passes.

A minimum separation of 700mm. shall be maintained between hot pipe lines and electrical pipelines. Also where required, electrical pipe shall be properly shielded from direct heat.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

DIRECTOR VANMIYUR, CHENT

Page 22 of 35

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

06.05 CIRCUIT WIRING

Circuit wiring shall mean the length of wiring from the Distribution Board upto the tapping point for nearest first point of that circuit - viz upto the nearest first switch board measured along the run of wiring. Such wiring shall not be measured on linear basis. The cost of Circuit mains shall be included in the point wiring rate itself.

Sub-main wiring shall mean the length of wiring from one main / distribution switchgear to another main/distribution switchgear measured along the run of wiring. Such wiring shall be measured on linear basis.

Lights, 5A sockets, Ceiling fans and Ex-haust fans may be wired on a common circuit. Such circuit shall have 10 points of light, ceiling and ex-haust fan and socket outlets or a load of 800 watts, whichever is less. A switch board might have more than two circuits but should be of same phases.

The smallest copper conductor to be used for lighting circuits shall be 1.0 Sq.mm. and for power circuits 4.0 Sq.mm. Wiring shall be done in the "looping system" and neutral conductor can be looped from the ceiling fan and exhaust fan or socket outlet. Neutral conductor and earth continuity wire shall be brought to each switchboard situated in rooms and halls. These shall be terminated inside the switchboards with adequate size to accommodate one number 5 Amps socket outlet and control switch in future.

06.06 CONDUIT WIRING

In this system of wiring, no bare or twist joints shall be made. In through run of cables, if the length of final circuits / submain is more than the length of the standard coil, joints shall be made by means of approved mechanical connector in suitable and approved junction boxes.

The chases in the wall shall be neatly made and n ample dimensions to permit the conduit to the fixed in the manner desired. In case of buildings under constructions, conduits shall be burried in the wall before plastering. These shall be grouted and covered with cement and mortar, neatly finished at the plate of the unplastered brick work and scratched for providing key to the plaster and cured. Under no circumstances finished plastered surfaces shall be allowed to be chased for the conduit work. Before taking up chasing of the wall, the routes shall be marked and got approved by the Engineer. The horizontal chases shall be avoided as far as possible. In case of exposed brick/rubble masonry work, special care shall be taken to fix the conduit and accessories in position along with the building work.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

DIRECTOR

MMIYUR, CHENNA

Page 21 of 3

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

06.02 BUNCHING OF WIRES

Wires carrying current shall be so bunched that the outgoing and return wires are drawn into the same conduit. Wires originating from two different phases shall not run in the same conduit.

Strands of wires shall not be cut for connecting terminals. The terminals shall have sufficient cross sectional area to take all strands and shall be soldered. At all bolted terminals, brass flat washer of large area and approved steel shall be used. Brass bolts and nuts shall be used for all connections.

Only certified wiremen and cable jointers shall be employed to do jointing work. All wires and cables shall bear the manufacturer's label and shall be brought to site in original packing. For all internal wiring, PVC Insulated wires of 1100V grade shall be carried out in loop system and no joints shall be allowed in the length of the conductors. If the use of joints/connections are unavoidable due to any reason prior permission, in writing shall be obtained from the Engineer. No wire shall be drawn into any conduit, until all work of any nature, that may cause injury to wire is completed. Care shall be taken in pulling the wires into the conduits. The conduits shall be thoroughly cleaned of moisture, dust, dirt or any obstruction by forcing compressed air through the conduits. The minimum size of PVC Insulated copper conductor wires for all sub-circuit wiring for light points shall be 1.5 Sq.mm.

All inspection boxes shall have a minimum depth of 65 mm. and shall be of circular nature (Dia 50 mm.) They shall have a cover securely fixed through screws and shall be fixed flush with the wall.

06.03 MAINS AND SUB-MAINS

Mains and sub-mains cable or wires called for shall be of rated capacity and approved make. Every main and sub-main wires shall be drawn into an independent adequate size conduit. An independent earth wire of the proper rating shall be provided for every single phase sub-main. For every 3 phase sub-main, 2 Nos. earth wires of proper rating shall be provided along with the sub-main. Where mains and sub-mains cables are connected to switch gear, sufficient extra length of cable shall be provided to facilitate easy continuous and maintenance.

06.04 LOAD BALANCING

Balancing of circuits in three phases installation shall be planned before the commencement of wiring and shall be adhered to.

Conduits must be placed inside conduit sleeves at all expansion joint crossings.

Conduit sleeves shall be provided at all beams to take point wiring conduit, so as to avoid the bend.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

Page 20 of 3

TRAL RE

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

06 WIRING

06.01 INTERNAL WIRING (OPEN) FOR SMALL POWER AND LIGHT

All wiring shall be carried out only with MS conduits of `B' class.

All light, fan sockets and any other equipment must be earthed.

Wiring shall be carried out with 1100 V grade PVC insulated single core multi stranded copper conductor wires as per IS: 694.

The method of wiring shall be as recommended in IS: 732 and its several parts.

The physical and electrical continuity of the conduit system shall be maintained throughout.

No wire shall be left exposed at any location, metallic flexible pipe shall be used to cover the same.

Colour coding of wire shall be carried out as detailed below:

PHASES

RED

YELLOW BLUE

NEUTRAL

BLACK (OR) GREY

EARTH

GREEN

The minimum diameter of the conduits shall be 25 mm. only.

The following sizes of PVC insulated multi stranded copper conductor wires shall generally be followed throughout:

a. From the final switch to individual outlets

1.5 sq.mm

b. From Distribution Boards to First Switch Board and subsequent switchboards

2.5 sq.mm

c. All 15A socket (Only Phase & Neutral)

4.0 Sq.mm.

d. Earth wire throughout for Lighting.

1.5 Sq.mm.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

Page 19 of 35

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

Joints by the fusion welding method shall be made by jointers experienced in this method. Particular care shall be taken to protect the cable insulation from heat by fixing substantial heat sinks to the cable near the joint. After completion of the weld the joint shall be wire brushed and all sharp projections filed smooth.

- b. Aluminum to copper connections shall be made by one of the following methods:-
 - Bi- metal connectors, or
 - Tinned copper ferrules or
 - Electro- tinned cast aluminum lugs

Bi-metal connections shall consist of lugs or pin type connectors having a cast copper palm or pin, friction –welded to an aluminum barrel section which is subsequently factory filled with oxide – inhibiting grease. The aluminum cable shall be inserted in the barrel section and fixed using the compression method as detailed above. The copper pin or palm section shall be fixed to copper or brass connectors or bus – bars in the conventional manner.

Tinned copper ferrules shall be terminated using the compression method.

Where electro-tinned aluminum lugs are used, they shall be fixed to the cable using the compression method. The palm of the lug shall be bolted to the copper bus – bar or terminal using a stainless steel bolt and nut, with one large diameter stainless flat waster or two "Belleville" spring cup washers.

All nuts shall be adequately torque tightened to manufacturers recommended levels.

Identification tags for feeder designation shall be by using 'Phoenix" plastic cable markers , tied to either end of each cable.

05.17 TESTING

CHENNAI-4

Cables shall be tested at the factory as per the requirements of IS 1554 Part 1. The tests shall incorporate routine tests, type tests and acceptance tests. A copy of such test certificates shall be furnished to the Consultant / Employer prior to despatch.

MADRAS ELECTRICAL CONSULTANTS

Page 18 of 35

HEN

For Kevin Electricals Pvt. Ltd.

Managing Director

ANMIYUR

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

05.12 ALUMINUM CABLE TERMIANTION METHODS.

GENERAL

The general requirements for all joints and terminations of aluminum cables shall be :

- a) To remove oxide from the conductor to prevent the oxide re-forming.
- b) To prevent corrosion resulting from contact between dissimilar metals.
- c) To retain contact pressure under cyclic loading conditions.

For all aluminum cables, the oxide shall be removed by thoroughly wire – brushing the bare end of the cable. After brushing, a liberal coating of an approved oxide – inhibiting, moisure- excluding thermally stable grease shall be applied, and the cable shall be wire- brushed again through the grease. Cable strands shall not be separated before brushing.

Bare aluminum lugs, ferrules and other connectors, unless factory-tinned or factory pre-filled with inhibiting grease, shall be wire- brushed and grease coated in the same way as cables.

Before making any joints or terminations in aluminum cables, the Contractor shall submit the proposed method for the Consultant / Employer approval. Notice of atleast three working days shall be given before making any joints or terminations to enable consultant/ Employer to witness the work.

05.13 ACCEPTANCE TERMIANTION METHODS

a) Aluminum to aluminum connections shall be made by one of the following methods:-

Aluminum crimp lugs or tinned copper ferrules

Fusion welding with aluminum lugs

Tinned copper ferrules shall be terminated using the compression method. For compression connections on stranded cables, a hexagonal die shall be used, on solid conductor cables, indent type dies shall be used, with at least two indentations per cable connection. Lugs of ferrules shall be selected to suit the size and shape of the conductor. Compression dies shall be selected to suit the particular lug or ferrule. Aluminum crimp lugs shall be filled with oxide inhibiting grease.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

VANMIYUR CHE

Page 17 of 35

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

- c) If made of Sheet metal, it shall be adequately strength protected against corrosion or shall be made of corrosion resistant material.
- d) It shall have side rails or equivalent structural members.
- e) It shall include fittings such as horizontal, vertical bends, tie rods, hooks etc., or other suitable means for cha8nges in direction and elevation of runs, fish plates and hard wire.

05.09 INSTALLATION

- a) Cable trays shall be installed as a complete system. Trays shall be supported properly from the building structure. The entire cable tray system shall be rigid.
- Each run of the cable tray shall be completed before the installation of cables.
- c) In- portions where additional protection is required , non-combustible covers / enclosure shall be used.
- d) Cable trays shall be exposed and accessible.
- e) Where cables of different system are installed on the same cable tray, non- combustible solid barriers shall be used for seggregating the cables.
- f) Cable trays shall be grounded by two nos. earth continuity wires. Cable trays shall not used as equipment grounding conductors.

05.10 JOINTING AND TERMINATIONS

Cable jointing shall be done as per the recommendations of the cable manufacturer. Jointing shall be done by qualified cable jointers.

Each terminations shall be carried out using brass compression glands and cable sockets. Hydraulic crimping tool shall be used for making the end terminations. Cable gland shall be bonded to the earth by using suitable GI Wire / tape.

Suitable identification tags with the feeder designation inscribed on an aluminum / G.I. Sheet steel be tied to either ends of each cable.

05.11 TESTING

Cables shall be tested at factory as per the requirements of IS 1554 Part I. The tests shall incorporate routine tests, type tests and acceptance tests. Copy of such test certificates shall be furnished to the Employer-Rrior to dispatch.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

ETRA FOU

Page 16 of 3

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

Multi-core control cables shall be laid touching each other on trays and wherever required may be taken in two layers.

Ladder type cable racks shall be selected from two sizes viz. 300 mm. and 600 mm. Ladder type trays shall be galvanised after fabrication.

Vertical spacing between cable racks/trays shall be 250 mm.

Power cables of different voltage grades shall be laid in separate racks / brackets / hooks. Control cables as well as signal and communication cables shall be laid in a separate trays. However, in cases where smaller size power cables (below 16 sq.mm) of fewer numbers cables provided suitable vertical barriers are installed between them. As far as possible AC and DC Power cables shall be laid in separate trays.

Order of laying of various cables in racks/trays brackets/hooks shall be such that control cables are located at the bottom-most tier and 1100 V grade cables at top tier. In case of duplicate feeders of same consumer, these shall be laid in two separate racks/brackets.

Where there is possibility of mechanical damage, cable rack / trays shall be adequate protected by sheet steel covers.

For future installation of cables, provision shall be made to keep 20% space as spare on each tray/rack/bracket.

05.07 CABLES IN INDOOR TRENCHES

Cables shall be laid in indoor trenches wherever specified. Suitable angle iron brackets, clamps, hoods and saddles shall be used for securing the cable in position.

05.08 CABLES ON TRAYS / RACKS

Cables shall be laid on cable trays/ racks wherever specified. Cable racks/ trays shall be of perforated steel section slotted angles for suitable purpose. The trays / racks shall be complete with plates, tees elbows, risers and all necessary hardware. The steel trays shall be painted. Cable trays shall be erected properly to present a neat and clean appearance. Suitable cleats or saddles shall be used for securing the cables to the cable trays. The cable trays shall comply with the following requirements:-

a) The trays are ladder type and shall have suitable strength and rigidity to provide adequate support for all contained cables.

b) It shall not present sharp edges, burrs of projections injrious to the insulation of the wiring / cables.

MADRAS ELECTRICAL CONSULTANTS

Page 15 of 3

m 200

For Kevin Electricals Pvt. Ltd.

Managing Director

VANMIYUR CI

Tender for Electrical Installation

Specification for Electrical

All cables shall be provided with identification tags indicating the cable numbers in accordance with the cable/circuit schedule. Tags shall be fixed at both the ends of cable at joints and at 20 m. spacing for straight runs. When a cable passes through a wall tags shall be of durable fibre of aluminium sheet with the numbers punched on them, and securely attached to the cables with non-corrosive wire. For single core cables wire shall be non-ferrous material.

All cables shall be tested for proper insulation prior to laying. The cable drums shall be transported on wheels to the place of work. The cables shall be laid out in proper direction as indicated on the drum using cable drum stands. In case of higher size cables, the laid out cables shall run over rollers placed at close intervals and finally transferred carefully on to the trenches and racks. Care shall be taken so that links and twists or any mechanical damage does not occur in cables. Only approved cable pulling grips or other devices shall be used.

Adequate length of cables shall be pulled inside the switchboards, control panels, terminal boxes etc. so as to permit neat termination of each core/conductor.

Control cables cores entering switchboard or control panels shall be neatly bunched and strapped with PVC perforated tapes and suitably supported to keep it in position at the terminal block. All spare cores shall be neatly dressed and suitably taped at both ends.

Power cable terminations shall be carried out in such a manner to avoid strain on the terminals by providing suitable clamp near the terminals.

All power cable terminations shall be by means of crimping type cable lugs. Control cables shall be terminated by crimping or directly clamped in the terminal blocks by screws.

No jointing shall normally be made at any intermediate point in through runs of cables unless the length of the run is more than the length of the standard drum supplied by cable manufacturers. In such cases when jointing is unavoidable, the same shall be made by means of standard cable jointing boxes/kits.

All cables entry openings in the equipment shall be sealed and made proof against entry of creeping reptiles.

05.06 LAYING OF CABLES ON RACKS/TRAYS/BRACKERS/HOOKS

All power cables in trenches and on structures shall be laid on racks and shall be clamped by means of single or multiple galvanised MS saddles. The saddles shall be placed at an interval of 1000 mm. in both horizontal and vertical straight runs, at each bend and turnings from horizontal to vertical direction and vice versa. All 1100 V grade power cables shall be laid touching each other.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

MSON

Page 14 o

DIRECTOR

ANMIYUR, CHENN

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

04.03 CABLES SELECTION

The power cable sizes shall be adopted on the basis of current loading, ambient temperature condition, method of installation and permissible voltage drop in each circuit. The minimum cross-section of the cable shall be determined on the basis of available short circuit current and tripping characteristics of the circuit protective devices.

04.04 CORE IDENTIFICATIONS

Cores shall be provided with the following colour scheme of PVC insulation:

1 Core

Red / Black / Yellow / Blue

2 Core

. Red and Black

3 Core

Red , Yellow and Blue

3 ½ / 4 Core ..

Red, Yellow, Blue and Black

04.05 LAYING OF CABLES

METHOD OF LAYING CABLES

Cables laid exposed in racks/trays/hooks and routed from trenches to individual equipments etc. shall be taken in embedded / exposed rigid G.I pipes or flexible conduits unless directly terminated to the equipment in the panels located above the trench. Extra length of cables shall be provided wherever possible for any future contingency to the extent of 10% of the length of any section.

The cables laid fully buried in ground or partly in trench and partly in ground shall be armoured type. Cables are laid fully in rack/tray/hook or laid in G.I. pipes, shall be also armoured type.

The installation work shall be carried out in a neat workman like manner by skilled, experienced and competent workmen particularly with experience in jointing termination of aluminium conductor cables.

Cables runs shall be uniformly spaced properly supported and protected in an approved manner. All bends in runs shall be well defined and made with due consideration to avoid sharp bending and linking of the cable. The minimum bending radius of cables shall not be less than twelve times the overall diameter.

Cable installation shall be property co-ordinated at site with the routing of other services, utilities and the cable routings with a view to avoid interference with any part of the building, structure, equipment, utilities and services.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

VUVANMIYUR



m 8 gu

Page 13 of

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

04.00 LT CABLS

04.01 GENERAL

TYPE

Medium voltage cables shall be aluminum conductor, PVC insulated, PVC sheathed and steel wire armoured or steel tape armoured construction. The cables shall conform to IS 1554 Part I in all respects. Cables shall be laid in tray / hume pipe / in ready made trenches etc. as required.

All control cables shall be of solid copper conductors. The control cables used for mobile equipment shall be flexible type.

Cross-sectional areas of multi core power cables shall not exceed 400 sq.mm. unless otherwise specified.

Minimum cross-sectional area of power cable shall be 6 sq.mm. in case of aluminium conductor and 4.0 sq.mm in case of copper conductor.

The cross-sectional area of neutral conductor of multicore cables shall constitute about 50% of phase conductor for cables having cross-sectional are of 25 sq.mm and above.

For cables below 25 sq.mm. as well as flexible trailing cables, the neutral conductor shall be of same cross-section area as the phase conductor.

All cables 10 sq.mm. and above shall be of stranded type.

RATING

The cable shall be rated for a voltage of 1100 Volts.

04.02 TYPE OF CABLES

PVC CABLES

PVC insulated, PVC Sheathed armoured/unarmoured heavy duty cable shall be designed, manufacture and tested in accordance with IS: 1554 (PART - I). The insulation shall consists of polyvinyl chloride compound suitably extruded with softeners and plasticisers. The inner sheath shall be either vulcanised rubber or PVC. The outer sheath shall be of PVC compound. The armouring of multi-core cables where required shall be of single layer galvanised steel round wire or flat strip.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

ANMIYUR CHENNO

Page 12 of 3

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

Current transformers shall generally conform to IS: 2075.

Current transformers for instruments shall have an accuracy class 1.0 and accuracy limit factor less than 5.0. The current transformers shall be capable of withstanding the peak momentary short circuit current for 1.0 second. The neutral side of the current transformers shall normally be earthed through a link.

Wherever provided, the voltage transformers shall generally conform to IS: 3156 and shall be cast resin type. The voltage transformers shall be provided with primary fuses. Miniature circuit breakers with auxiliary contact shall be provided on the secondary side.

The voltage transformers shall have an accuracy class 3.0 from 50% to 110% of normal voltage and class 1.0 from 80% to 120% of normal voltage.

03.14 MEASURING INSTRUMENTS

All measuring instruments shall be of 144 \times 144 Sq.mm (or) 96 \times 96 sq.mm pattern, flush mounting box.

All A.C. Ammeters, Voltmeters, KW Meters shall be Of Digital type.

03.15 INDICATING LAMP

Indicating lamps shall be suitable for 6.0 volts A.C. complete with built in lamps resistors shall be provided with translucent covers to diffuse light.

03.16 DRAWINGS & DATA

Vendors shall furnish following drawings for consultant approval and no other drawing (including those referred) on these drawings shall be approved or considered to be approved by consultants.

- Switch board foundation/fixing details with all dimensions and details of shipping sections.
- Typical control schematic diagram for each type giving type designation to be refered on Single line diagram.
- Front and rear view of all switch boards indicating panel number arrangements of various feeders/starters giving its location numbers and tag numbers for each as per single line diagram.

MADRAS-ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

Page 11 of 35

RALRA

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

Facility should be there to monitor the load and initiate a free trip alarm (or) have load shedding feature.

Trip reset should be available Manual / Automatic.

03.11 SWITCHES

All switches shall be load break, heavy duty air break type provided with quick make/break manual operating mechanism. The operating handle shall be mounted in the door of the compartment having the switch.

Switches shall have Short Circuit Capacity of 36KA.

Switches shall be designed to carry the rated current continuously without overheating.

Barriers shall be provided to prevent interphase arcing and live terminals shall be shrouded to avoid accidental contact.

Rating of heavy duty switches for a particular starter module shall be as indicated in the Switchboard data sheet. Motor duty switches of smaller ratings meeting the requirements of AC 23 duty as per IS: 4064, may be accepted in place of specified heavy duty switch rating for particular starter module only if, motor duty switches have been tested and certified for use with the larger size of fuse link specified in the switchboard data sheet for the same starter module.

03.12 FUSES

Fuses shall be non deteriorating HRC Cartridge link type. Diazed Fuses are not acceptable.

The fuses shall be provided with operation indicator which shall be variable removal of fuses from service.

Fuses shall be pressure fitted type and shall preferably have ribs on the contact blades to ensure good line contact.

It shall be possible to handle fuses during off load conditions with full voltage available on the terminals. Wherever required fuse pullers shall be provided. The fuse bases shall be so located in the modules to permit insertion of fuse pullers and removal of fuse links without any problem.

03.13 INSTRUMENT TRANSFORMER

Current Transformers shall be tape wound or cast resin insulated type for feeders upto 200 A and cast resin insulated type for feeders rated above 200 A. The CT ratio and VA burden shall be such that it can power all meters.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

LEELA SOUSON Z DIHECTER

Page 10 of 35

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

- The Circuit Breaker shall be lockable in "Service", "Test" and "Full out" positions.
- The earth connection must remain connected in "Test" position, earthling of the unit shall be done with scrapping earth connections.

INTERLOCKS

Following interlocks shall be provided.

Compartment doors shall be interlocked against opening when switch is in closed or ON condition. However, it shall be possible to by pass this interlock for inspection purposes.

Any unused compartment shall be fully equipped and provided with compartment door, vertical bus bars and control terminals / wiring etc. such that the same could be used for fixing switches in future without any modifications to the panel. All quotations must indicate the number of switches which could be provided in unused space for each switchboard line up. Unit price for providing such outgoing switches shall be quoted which could be considered during placement of order.

03.10 SWITCHGEAR COMPONENTS

MCCB

MCCBs should comply with IEC 947 Part 2.

The MCCB shall be suitable for universal mounting (i.e) the Load / Line must be interchangeable.

The MCCB shall be suitable for operating Voltage of 415 V minimum and an Insulation Voltage of 600 V.

The withstanding capacity mentioned against each MCCBs shall be Ics only.

PROTECTION

All MCCBs shall have adjustable Thermal and Magnetic relays.

The Thermal setting shall be continuously adjustable from 63% to 100% of its normal current.

The magnet setting shall be continuously adjustable from 500% to 1000% of its normal current.

Local / Remote Electrical Indication of the Circuit Breaker status should be possible for all the position. HETRA FOL

MADRAS ELECTRICAL CONSULTANTS

VANMIYUR CHEN For Kevin Electricals Pvt. Ltd.

DIREC

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

03.08 SPECIFIC REQUIREMENTS OF CIRCUIT BREAKER PANELS

The circuit breaker compartment enclosure shall be IP: 31 as per IS: 2147 with the circuit breaker in position or withdrawn from the compartment. Spring actuated safety shutters shall be provided for isolating the bus bars and other live parts when the breaker is completely withdrawn. The design of compartment shall be such as to prevent movement of vermin from a particular circuit breaker compartment to any other portion of the panel when the breaker is withdrawn and the compartment door is closed.

Maximum two (2) Nos. of breakers with releases and only one (1) No. of breaker with static / electromagnetic relays shall be provided per vertical panel. KWhour Meter and protection relays associated with a particular breaker shall be preferably mounted on the same panel and in the front only.

Separate compartment totally enclosed from all sides shall be provided for cable termination, preferably on the rear side of circuit breakers. Access to cables shall be from the rear side after opening the cabling compartment door. The incoming / outgoing cable termination shall be staggered for each circuit and barriers of sheet steel or insulating material shall be provided between termination of two circuits such that maintenance on the circuit is possible

even if the other is live. Suitable clamping arrangements shall be provided for cables and cable termination / terminal blocks shall not be used for supporting the cables.

03.09 CIRCUIT BREAKER COMPARTMENT

The Circuit Breaker compartment shall be fully drawout, that is bus side and outgoing power and control connections shall be through drawout contacts. Suitable guides shall be provided to facilitate easy withdrawal of the trolley. All identical feeder compartments shall be interchangeable.

There shall be three positions for the drawout trolley viz;

- a. "Full in" or "service" position in this position both power and control circuits shall be connected. This shall be the normal operating position of the circuit breaker.
- b. "Test" position The power contacts shall be disconnected in this position but the control connections shall not be disturbed, it shall be possible to close and trip the breakers in this position.
- c. "Full out" position Both power and control circuits shall be disconnected in this position. It shall be possible to close the cubicle door in this position.

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

DIRECT

Page 8 of 35

RUVANMIYUR, CHE

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

A minimum of 10% spare terminals shall be provided on each terminal block. Conductors shall be terminated with adequately sized compression type lugs. "ELMEX" (direct conductor termination) type terminals will be acceptable for wires upto 10 sq.mm.

03.05 EARTHLING CONNECTION

All vertical panels shall be connected to an Aluminium earth bus bar running throughout the length of the switchboard. The minimum earth bus sizes shall be 300 sq.mm. unless otherwise specified. All doors and moveable parts shall be connected to the earth - bus with flexible copper connections. Provisions shall be made to connect the earthling busbar to the plant earthling grid at two ends. All non-current carrying metallic parts of the mounted equipment shall be earthed. Earthling bolts shall be provided to ground cable armours.

03.06 NAME PLATE

A name plate with switchgear designation shall be fixed at the top of the central panel. A separate name plate giving feeder details shall be provided for each compartment. A separate name plate giving details of bus section shall also be provided for switchgears having more than one bus section.

Engraved name plates shall preferably be of 3 - ply (Black - white - black) lamicoid sheets or anodised aluminium. However, back engraved perspex sheet name plates will also be acceptable. Engraving shall be done with square / vee groove cutters. Hard paper name plates will not be acceptable. Nameplates shall be fastened by screws and not by adhesives.

03.07 PAINTING

All metal surfaces shall be thoroughly cleaned and decreased to remove mill scale, rust, greased and dirt. Fabricated structures shall be pickled and then rinsed to remove any trace of acid. The under surface shall be prepared by applying a coat of phosphate paint and coat of yellow zinc chromed primer. The under surface shall be made free from all imperfections before undertaking the finishing coat.

After preparation of the under surface the switch board shall be power coated with two coats of final paint. Colour shade of final paint shall be SIEMENS GREY. The finished panels shall be dried in stowing ovens in dust free atmosphere. Panel finish shall be free from imperfections like pinholes, orange peels, run off paint etc. The vendor shall furnish painting procedure details along with the bids.

All unpainted steel parts shall be cadmium plated or suitably treated to prevent rust formation. If these parts are moving elements then they shall be greased.

SHETRA FOU

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

Page 7 of 3!

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

The busbar and supports shall be capable of withstanding 50 KA Short circuit current at 415 V. Only zinc passivated or cadmium plated high tensile strength steel bolts, nuts and washers shall be used for all bus bar joints and supports. All bus bar supports shall be SMC / DMC only.

The terminal design of the bus bar shall be based on installation of the switchgear in poorly ventilated condition. The cooling air volume shall take into account only the bus bar enclosure and not the air volume of the vertical panels. The maximum operating temperature of bus bars at maximum design temperature shall not exceed 85 Deg. C for normal condition and 200 Deg. C for short circuit condition.

All bus bars shall be colour coded by means of identifying colour rings at every power tap off point. Red, yellow and blue colour shall be used for Phase busbars and Black colour shall be used for neutral bus bars. Each bus bar shall be insulated with heat shrinkable sleeves.

Minimum clearance between live parts, between live parts / neutral to ground shall be minimum 25 mm.

Interconnections between the main bus bars and individual units shall be made by using vertical copper bus bars of adequate rating. These interconnections and the vertical bus bars shall be compartmentalized and fully shrouded. Vertical bus bars for circuit breaker panels shall be sized depending upon the rating and number of FSUs/ MCCBs per cross section and rating shall not be less than 300 A. Minimum size of vertical bus bars shall not be less than 25 x 10 mm. copper per phase. All joint surfaces at aluminium to copper joints shall be silver / tin plated, alternatively, Cup-A1. washers (bimetallic washers may be used).

03.04 AUXILIARY WIRING AND TERMINALS

Inside the switch boards the wiring for power, control, signaling, protection and instrument circuits shall be done with PVC Insulated copper conductors. The insulation grade for these wires shall be 1100 volts. All control wiring shall preferably be enclosed in plastic channels or neatly bunched together.

1.5 Sq.mm size wires shall normally be used provided the control fuse rating is 10 Amps or less. For 16 AMPS control fuse circuit , 2.5 sq.mm size wires shall be used. Each wire shall be terminated at a separate terminal. Termination of two outgoing wires on a single terminal will not be acceptable. Wires shall not be joined or tied between terminal parts. Shorting links shall be provided for all C.T. Terminals.

Each wire shall be identified at both ends by self sticking wire marker tapes or PVC Ferrules. Ferruling of wires shall be as per relevant IS.

MADRAS ELECTRICAL CONSULTANTS

Page 6 of 3

For Kevin Electricals Pvt. Ltd.

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

The switchgear shall be provided with integral base frame for each vertical panel. The switchgear integral base frame shall be suitable for directly bolting with the help of foundation bolts and also be suitable for tack welding at two diagonally opposite points.

All openings, covers and doors shall be provided with neoprene gaskets around the perimeters to make the Switchgear dust and vermin proof.

All hardware shall be corrosion resistant. All joints and connections of the panel members shall be made by galvanised, zinc passivated or cadmium plated high quality steel bolts, nuts and washers, secured against loosening.

Suitable lifting hooks and / or jacks shall be provided on each panel or shipping section for ease of lifting of Switchboard.

03.02 PANEL DESIGN REQUIREMENTS

A Completely metal enclosed horizontal busbar compartment running horizontally at top unless specified at bottom.

Individual feeder modules organised in multitier mode.

Completely enclosed vertical bus bars serving all feeder modules in the vertical panel.

Cable termination compartment shall be provided.

Perforated sheet steel / insulating material enclosed horizontal auxiliary bus way for control, interlock, indication and metering wiring running horizontally.

Metal sheets shall be provided between two adjacent vertical panels running to the full width of the wider panel and upto full useful height of the switchgear.

Panel shall be in single front execution. For single front, cables and gear access shall be provided in the front of the switchgear.

The switchgear shall be compartmentalised, modular construction. All equipment associated with a particular circuit shall be housed in a separate and independent compartment earmarked for that particular circuit fixed portion of the vertical panel.

03.03 BUSBAR SIZING, CONNECTION AND SUPPORTS

Busbars shall be of high conductivity Aluminium / Copper supported on insulators made of non-hygroscopic, non-inflammable material.

The main busbars shall have uniform current ratings through their length. The current rating of the neutral shall be half that of the phase busbars throughout the length of the switchboard. Removable neutral links shall be provided on feeders to permit isolation of the neutral busbar.

MADRAS ELECTRICAL CONSULTANTS

Page 5 of 35

For Kevin Electricals Pvt. Ltd.



M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

VOLTAGE DROP IN CABLES

The total allowable voltage drop in the power circuits from the load centres to any motor or other consumers shall not exceed 5%. The distribution of this voltage drop in different parts of the System shall depend on the layout of the installation. General the voltage drops in main feeders from the load centres to the PCCs or PDBs shall not exceed 2% and in the sub-feeders from the PCC or PDB to individual equipments or other consumers shall not exceed 3%.

03.00 LT PANELS

Medium voltage Switchgear shall be metal enclosed, compartmentalised, modular type suitable for indoor installation. The M.V. Switchgear shall be dust and vermin proof and the enclosure shall provide a degree of protection of not less than IP: 51 as per IS: 2147.

The Switchgear shall be assembled out of vertical sections of uniform height not exceeding 2100 mm.

The Switchgear shall be easily extensible on either side by the addition of vertical sections. It shall be possible to extend the switchgear, irrespective of the type of end panel and the design shall be such as to permit addition of extension panels of a type other than the type of end panel. Any other panels required shall be included in the basic price.

The Switchgear shall be designed to ensure maximum safety during operation, inspection, connection of cables, relocation of outgoing circuits and maintenance, with the busbar system energized and without taking any special precautions. Means shall be provided to prevent shorting of power and / or control terminals due to accidental dropping of maintenance tools etc. inside the Switchboard. Checking and removal of components shall be possible without disturbing adjacent equipment. All auxiliary equipment should be easily accessible.

All identical equipment and corresponding parts shall be fully interchangeable without any need for resorting to structural modifications.

03.01 FABRICATION REQUIREMENTS

The frame of individual vertical panels shall be fabricated using pressed and shaped cold rolled sheet steel of adequate thickness or by using suitable mild steel structural sections. The frames shall be enclosed by using minimum 14 SWG cold rolled sheet steel and the doors and covers shall be made of minimum 16 SWG cold roller sheet steel. Wherever required, stiffeners shall be provided to increase stiffens of large size doors and covers.

MADRAS ELECTRICAL CONSULTANTS

Page 4 of 35

URAL RE

For Kevin Electricals Pvt. Ltd.

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

S.No.	ISI Codes	Description
(1)	(2)	(3)
30.	IS 13953	Low Voltage Switch-gear - General Rules
31.	IS 13947 (Part 2)	Low Voltage Switch-gear - Circuit Breakers
32.	IS 13947 (PART 3)	Low Voltage Switch-gear and Control gear – Switches Disconnectors, Switch Disconnectors, and Fuse Combination Switches.
33.	IS 13947(PART 4)	Low Voltage Switch-gear and controlgear – Contactors and Motor Starters

All electrical equipment and installation shall also conform to the latest Indian Electricity Rules as regard Safety, earthling and other essential provisions specified therein for installation and operation of electrical plants.

02. DESIGN

SITE CONDITIONS

All equipment shall be designed for operation in tropical climate for 35 Deg. C ambient as a 24 hours average with a short time of maximum of 45 Deg. C and relative humidity of 100%. Maximum temperature and maximum humidity however are not likely to occur simultaneously. The derating of all equipment shall be done for if specifically mentioned in the Technical Specification. The equipment to be installed outdoor subject to direct incidence of sun rays shall be deigned for operation at a maximum ambient temperature of 50 Deg.C and shall be weather proof design.

RELIABILITY AND SAFETY

Continuity of Power supply is the first consideration and the installation shall be such as to provide facilities to simplify inspection, testing, maintenance, cleaning and general repairs at Site.

Special care shall be taken to make the enclosed equipment proof against entry of creeping reptile which may create electrical short circuits inside the live equipment.

All ventilating and forced-draft opening shall have suitable screen protection. When screens are provided on top of the equipment, means shall be provided to protect them from falling objects.

SYSTEM VOLTAGE

Electric power will be available at 415 KV, 3 phase, 4 wire, 50 Hz. The system will be earthen solidly at transformer neutral.

All Alternating Current Equipments shall be designed to suit supply with a voltage variation not exceeding $\pm 15\%$ and frequency variation not exceeding $\pm 3\%$.

MADRAS ELECTRICAL CONSULTANTS

Page 3 of 35

For Kevin Electricals Pvt. Ltd.

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

S.No.	ISI Codes	Description
(1)	(2)	(3)
01.	IS:3072-1975	Code of Practice for Installation and Maintenance of Switch gear.
02.	IS:732-1963	Code of Proactive for electrical wiring Installations (Systems Voltage not exceeding 1100V)
03.	IS:2274-1963	Code of Practice for Electrical wiring Installation (System Voltage exceeding 1100V) Code of Proactive for Earthing
04.	IS:3043-1966	Ceiling fan
05.	IS:374	Aluminum Bus bar
06.	IS:375	Paints
07.	IS:631	Wires
08.	IS:694	Wires
09.	IS:732	Wiring Installation
10.	IS:1293	5A & 15A Switches & Sockets
11.	IS:1897/2927	Lugs & Sockets
12.	IS:1951	PVC Pipes
13.	IS:2551	Specifications for Danger Plates
14.	IS:4064/1978	Four Pole Switches & Sockets
15.	IS:5077	Light Fittings
16.	IS:5216/1982	Safety in Electrical work general
17.	IS:7752/1975 PART I	Guide for PF Improvement (L.V. & M.V.)
18.	IS:8623	MCB DBs
19.	IS:8828	MCBs.
20.	IS:13947 PART II	Air Circuit Breaker / Fuse Switch Units /
24	IC.12017 DADT IV	Module case Circuit Breaker.
21.	IS:13947 PART IV	Contractor / Over load Relays
22.	IS: 722	AC Electric Meters
23.	IS 2705	Current Transformers
24.	IS 3156	Voltage Transformer
25.	IS 3231	Electrical Relays for Power System Production
26.	IS 5578	Guide for making of insulated conductors
27.	IS 10118	Code of Practice for selection, installation and Maintenance of Switchgear and controlgear.
28.	IS 11353	Conductors and apparatus terminals.
29.	IS 13947(Part -1)	Low Voltage Switch-gear - General Rules

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

Page 2 of

M/S.Center for Architectural Research & Design

Tender for Electrical Installation

Specification for Electrical

01. SCOPE

This Specification covers general principles to be followed for the selection of electrical equipment and accessories and their installation, testing and commissioning. The term selection of electrical equipment means, the electrical equipment and accessories as well as materials. This also covers installation procedure of electrical equipment as well as materials.

The selection of electrical equipment and their installation work as well as during testing and commissioning, safety of equipment and operating personnel, ease of operation and maintenance shall be given the prime considerations.

The electrical installation shall be complete in all respects and any item not included in the specifications but essential for proper installation and functioning of the electrical system shall be deemed to be included in the scope of the specification whether specifically mentioned in the Technical and General specifications or not.

All electrical equipment, installation materials and accessories shall be selected from the standardized types and ratings and shall be oriented towards maximizing the inter change ability and minimising the maintenance.

In the interest of standardization the Purchaser reserves the right of selecting particular types and makes of installation materials and accessories and the supplier shall provide materials and accessories of the particular makes if so required.

STANDARDS

The equipment and accessories covered by this specification shall be designed, manufactured and tested in accordance with Indian Standards and codes of practice published by the Indian Standards Institution wherever available, in order that specific aspects under Indian Conditions are taken care of.

In case where Indian Standards are not available, then equipment and accessories shall conform to the latest publications and codes of practice by any other recognized National Standards Institutions.

All electrical equipments and installations shall conform to the latest publication of Indian Standards maintenance as listed below :

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

Managing Director

Page 1 of 35

M/S.Center for Architectural Research & Design

- 12. Unless demand or claim under this Guarantee is made within 3(three) months from the date of expiry of validity of this Guarantee, all the rights of Owner hereunder shall be forfeited and Bank shall be relieved and discharged of all liabilities hereunder.
- 13. Any notice by way of request, demand or otherwise hereunder may be sent by post to Bank addressed as aforesaid and if sent by registered post A.D. it shall be deemed to have been given at the time when it would be delivered in due course of post. In case it is sent by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate signed by an Officer of Owner that the envelope was so posted shall be conclusive.

	was so posted shall be conclusive.
14.	We shall not assign or transfer any of our obligations under this Guarantee.
15.	We have full powers to issue this Guarantee and the undersigned has full powers to sign this Guarantee on behalf of [insert name of bank] Bank.
16.	This Guarantee shall be governed by and construed in accordance with Indian Law and all disputes relating to this Guarantee or any matter(s) incidental thereto shall be subject to the jurisdiction of Courts at Chennai.
17.	Notwithstanding anything contained herein above our liability under this Guarantee is restricted to Rs
	The confirmation of this Bank Guarantee is available with our controlling office. The beneficiary in his own interest should obtain such confirmation from the controlling office at the following address:
	TNESS WHEREOF the said surety (Bank) subscribed and set its name and seal hereun- the day, month and the year first written herein above.

Authorised Signatory

Madras Electrical Consultants

26 of 26

For Kevin Electricals Pvt. Ltd.

Managing Director

AKSHETRA FOUNDON DIRECTOR

DIRECTOR

TULANMIYUR, CHENNALA

M/S.Center for Architectural Research & Design

65

request of the Owner on or before the expiry of the Guarantee without any cost to the Owner. If for any reasons the extension is not granted after receiving written request from the Owner, the amount covered under this Guarantee shall forthwith become payable to the Owner notwithstanding that the Contract is continuing and/or the Owner has or has not terminated the Contract or preferred any claim against the Contractor.

- 4. Our liability under this Guarantee is absolute, unconditional, irrevocable and unequivocal and this Guarantee is distinct and independent of the Contract subsisting between you and the Contractor. The payment made by us under this Guarantee shall be a valid discharge of our liability and the Contractor shall have no claim whatsoever against us for making such payment.
- 5. We further agree and undertake to pay you any money so demanded notwithstanding any dispute(s) raised by the Contractor in any suit or proceedings before any court or tribunal relating thereto.
- 7. The Guarantee shall be in addition to and not in substitution for any other Guarantee or Security by Contractor given or to be given to Owner in respect of said Contract by Bank (whether alone or jointly with others).
- 8. Our liability under this Guarantee shall not be impaired, discharged or affected in any way by reason of any time or indulgence which may be granted or shown by Owner to the Contractor or any forbearance whether as payment, time, performance or otherwise.
- 9. This Guarantee shall not be affected by any change in the constitution / management of Owner/ Contractor / Bank by absorption with any other body, corporation or otherwise and this Guarantee will be available for enforcement by such body or corporation.
- 10. All compensations and payments received by Owner from or on behalf of Contractor shall be regarded as payments in gross and in the event of Contract being terminated/suspended/stalled on any account whatsoever, Owner will be entitled to proceed against the properties of Contractor in respect of the whole of Contractor's indebtedness to Owner without any right on the part of Bank to stand in Owner's place in respect of or to claim the benefits of, such compensation and payment or any security held by Owner until Owner shall have recovered the full amount of the claim against Contractor.

11. In order to give effect to this Guarantee, Owner will be entitled to act as if Bank were the principal debtor and Bank hereby waives all and any of its right of suretyship.

Madras Electrical Consultants

25 of 26

For Kevin Electricals Pvt. Ltd.

M/S.Center for Architectural Research & Design

the due fulfillment by the Contractor of the terms and conditions contained in the said Contract and to ensure rectification by the Contractor of defects identified in the Defects Liability Period.

WHEREAS Contractor has agreed to furnish a Bank Guarantee from a Nationalized Bank , Scheduled Bank [retain whichever is applicable] which shall be for Rs [Insert amount in words]
AND WHEREAS the Bank has, at the request of Contractor agreed to give in favour of Owne a Guarantee in the manner hereinafter appearing, which Owner has agreed to accept.
NOW THIS DEED WITNESSETH AS FOLLOWS:
1. In consideration of Owner having agreed to exempt the Contractor from deduction of Rs[Insert amount in figures] (Rupeesonly) [Insert amount in words], being% of the final Contract Value amounting to Rs[Insert amount in figures] (Rupeesonly) [Insert amount in words] as Retention Money from the running account bills of the Contractor in respect of the Work as stipulated in the Contract, on production of Bank Guarantee for the due fulfillment by the Contractor of the terms and conditions contained in the said Contract and to ensure rectification by the Contractor of defects identified in the Defects Liability Period, we,
2. We [insert name of Bank] further agree that the guarantee herein contained shall remain in full force / continue to be enforceable till all the dues of the Owner under or by virtue of the Contract have been fully paid and its claims satisfied or discharged by the Contractor and till the Owner certifies out the said Contractor and accordingly discharges this Guarantee. Unless a demand or claim under this Guarantee is made on us in writing on or before [specify here the last date of 3 months after the expiry of validity period of Guarantee], we shall be discharged from all liability under this Guarantee thereafter.
3. This Guarantee shall continue to be valid till [insert date up to which this guarantee will be valid]. Should it be necessary to extend this Guarantee for further period of six months or more, such extension shall be given be written

Madras Electrical Consultants

For Kevin Electricals Pvt. Ltd.

[insert date] day of he issuing Bank), tatus and address] and a branch nch] (hereinafter referred to as the context, include its legal repre-
f client) successors and assigns).
(hereinafter referred to as ne and address of the Contracted to as "Contractor") for Work] at[insert address of the site of "work") at a total cost of
in figures] (Rupees
f

M/S.Center for Architectural Research & Design

notice was posted and a certificate signed by an Officer of KALAKSHETRA , Chennai., that the envelope was so posted shall be conclusive. 13. We shall not assign or transfer any of our obligations under this Guarantee. 14. We have full powers to issue this Guarantee and the undersigned has full powers to sign this Guarantee on behalf of ______ [insert name of bank] Bank. 15. This Guarantee shall be governed by and construed in accordance with Indian Law and all disputes relating to this Guarantee or any matter(s) incidental thereto shall be subject to the jurisdiction of Courts at Chennai. 16. Notwithstanding anything contained herein above our liability under this Guarantee is restricted to Rs. ___ [Insert amount in figures] (Rupees _only) [Insert amount in words] and this Guarantee is [Insert date]. We shall be released and discharged from all valid up to liabilities herein provided unless a written claim for payment under this Guarantee is lodged on us within three months from the date of expiry of validity of the Guarantee i.e. on or before _____ [Insert date] irrespective of whether or not the original Guarantee is returned to us. The confirmation of this Bank Guarantee is available with our controlling office. The beneficiary in his own interest should obtain such confirmation from the controlling office at the following address: IN WITNESS WHEREOF the said surety (Bank) subscribed and set its name and seal hereunto on the day, month and the year first written herein above.

For Bank



Madras Electrical Consultants

22 of 26

For Kevin Electricals Pvt. Ltd

Managing Director

WSHETRA FOUNDATION OF THE PROPERTY OF THE PROP

M/S.Center for Architectural Research & Design

- 4. We further agree and undertake to pay you any money so demanded notwithstanding any dispute(s) raised by the Contractor in any suit or proceedings before any court or tribunal relating thereto.
- 5. This Guarantee shall continue to be in force notwithstanding the discharge of Contractor by operation of law and shall cease only on recovery of the full amount of said Mobilisation Advance by KALAKSHETRA FOUNDATION , Chennai.,. The payment under this Guarantee shall be made at the Bank of KALAKSHETRA FOUNDATION Chennai.,'s choice, at _ [insert place].
- 6. The Guarantee shall be in addition to and not in substitution for any other Guarantee or Security by Contractor given or to be given to KALAKSHETRA FOUNDATION Chennai., in respect of said Contract by Bank (whether alone or jointly with others).
- 7. Our liability under this Guarantee shall not be impaired, discharged or affected in any way by reason of any time or indulgence which may be granted or shown by KALAKSHETRA FOUNDATION , Chennai., to the Contractor or any forbearance whether as payment, time, performance or otherwise.
- 8. This Guarantee shall not be affected by any change in the constitution / management of KALAKSHETRA FOUNDATION , Chennai.,/ Contractor / Bank by absorption with any other body, corporation or otherwise and this Guarantee will be available for enforcement by such body or corporation.
- 9. All compensations and payments received by KALAKSHETRA FOUNDATION Chennai., from or on behalf of Contractor shall be regarded as payments in gross and in the event of Contract being terminated/suspended/stalled on any account whatso-, Chennai., will be entitled to proceed against ever, KALAKSHETRA FOUNDATION the properties of Contractor in respect of the whole of Contractor's indebtedness to , Chennai., without any right on the part of Bank to KALAKSHETRA FOUNDATION stand in KALAKSHETRA FOUNDATION , Chennai.,'s place in respect of or to claim the benefits of, such compensation and payment or any security held by KALAKSHETRA FOUNDATION , Chennai., until KALAKSHETRA FOUNDATION Chennai., shall have recovered the full amount of the claim against Contractor.
- 10. In order to give effect to this Guarantee, KALAKSHETRA FOUNDATION nai., will be entitled to act as if Bank were the principal debtor and Bank hereby waives all and any of its rights of surety ship.
- 11. Unless demand or claim under this Guarantee is made within 1 (one) month from the date of expiry of validity of this Guarantee, all the rights of KALAKSHETRA , Chennai., hereunder shall be forfeited and Bank shall be relieved FOUNDATION and discharged of all liabilities hereunder.
- 12. Any notice by way of request, demand or otherwise hereunder may be sent by post to Bank addressed as aforesaid and if sent by registered post A.D. it shall be deemed to have been given at the time when it would be delivered in due course of post. In Robercan sining the case it is sent by post, it shall be sufficient to prove that the ep

Madras Electrical Consultants

21 of 26

For Kevin Electricals Pvt. Ltd.

rector

DIRECTOR CHE

EELA SAMSON DIRECTOR

AUVANMIYUR, CHENNA

Madras Electrical Consultants

WHEREAS one of the terms of the Contract obligates the Contractor to furn KALAKSHETRA FOUNDATION , Chennai., with a Bank Guarantee from a Nationalis Bank / Scheduled Bank [retain whichever is applicable] which shall be for Rs. [Insert amount in figures] (Rupeesonly) [Insert amount words] and shall be valid until the aforesaid amount of Mobilisation advance is fully received from / adjusted against the bills of the Contractor in respect of said Work.	in
AND WHEREAS the Bank has, at the request of Contractor, agreed to give in favour KALAKSHETRA FOUNDATION , Chennai., an absolute, unconditional, irrevocable Guaratee in the manner hereinafter appearing, which KALAKSHETRA FOUNDATION , Chennahas agreed to accept.	an-
NOW THIS DEED WITNESSETH AS FOLLOWS:	
1. In consideration of your paying the mobilisation advance of Rs	of e-
 This Guarantee is a continuing Guarantee and is not revocable except with the prevous written consent of KALAKSHETRA FOUNDATION , Chennai., and it will continue to be in force until the said amount of Mobilisation Advance is fully recovered adjusted in terms of said Contract or till [Insert the datup to which this guarantee will be valid], whichever is earlier. 	n- d /
3. Our liability under this Guarantee is absolute, unconditional, irrevocable and u equivocal and this Guarantee is distinct and independent of the Contract subsisting between you and the Contractor. The payment made by us under this Guarante shall be a valid discharge of our liability and the Contractor shall have no claim what soever against us for making such payment.	ng ee

20 of 26

Managing Director

For Kevin Electricals Pvt. Ltd.

EELA SAMSON DIRECTOR

BANK GUARANTEE FOR MOBILISATION ADVANCE

a) Guarantee Number	:
b) Amount of Guarantee	:
c) Guarantee valid from	1
d) Guarantee valid up to :	
e) Last date of lodging claim	:
f) Name of Contractor :	
sert date] day of[insert month suing Bank), and a branch office at[in	ARANTEE ("Guarantee") is made on this[in- in] 2009 by (insert name of the is- [insert corporate status and address] insert address of the issuing branch] (hereinafter re- in shall, unless repugnant to the context, include its igns)
in favour of	
	ai (hereinafter called "KALAKSHETRA FOUNDATION ude its legal representatives, successors and as-
dated (horoinafter referred to	, Chennai., has entered into an Agreement as "Contract") with
[insert address of the site of Work] total cost of Rsonly) [Insert am	(hereinafter referred to as "work") at a[insert amount in figures] (Rupees count in words].
WHEREAS at the request of the Contractor agreed for giving an interest free mobilist amount in figures] (Rupeescution of the said work, recoverable/adjust	ation advance of Rs[insert
Madras Electrical Consultants	19 of 26
CONO	or Kevin Electricals Pvt. Ltd.

PUVANMIYUR, CHENN

M/S.Center for Architectural Research & Design

settle the amounts to be paid, including cost of reference and of the award including the fees, apportion of the amount to be paid by either party, and direct them to do so.

Format for PERFORMANCE GAURANTEE

	Date:	′2009
To: Kalakshetra Foundatio, Chennai		
Dear Sirs,		
Tender Number : (Site Development Works)		
Tenderer: (Name of the Contractor)		
Tender Amount: Rs (Rupees only)		
We hereby guarantee to pay KALAKSHETRA FOUNDATION , ((Rupees only) representing 5% of the Contantee for the due and proper performance of the Contractor's liability.	tract value as per gu	
2. This guarantee shall be paid to KALAKSHETRA FOUNDATION of first demand in writing without proof or conditions.	, Chennai., on recei	ipt
3. This guarantee shall be valid up to days i.e upto '200 offer.	09 from the date of	this
Notwithstanding anything contained hereinabove:		
<i>Our liability under this guarantee shall not exceed Rs Only) <ii>This guarantee will be valid upto '2009, whereafter it cearespects whether or not the original bank guarantee is returned</ii> <iii>Our liability under this guarantee will arise only if we receive a KALAKSHETRA FOUNDATION , Chennai., on or before of (name of the contractor) failure leading to our liability here</iii></i>	ases to be in effect i to us; and notice, in writing, f '2009, advising	from
Yours faithfully	CTURAL RE	
Authorised Signatory	CHENNA!	
(Bank)	STATE WOLF OF WAR	
Madras Electrical Consultants 18 of 26 For Kevin Electricals Pvt. Ltd.	(60)	ROUM

23. Termination of the contract by Employer

If the Contractor is unable to proceed with the work with due diligence for any reason whatsoever, or has abandoned the contract, and is unable to show, to the reasonable satisfaction of the Employer, that he is able to proceed with work, within fourteen days after written notice to him from the Employer, Employer may determine the contract by a notice in writing. The remaining works will be carried out by the Employer at contractors risk and cost and for this purpose Employer will be empowered to use contractors materials, consumables, tools and plants etc lying at site.

24. Arbitration

All disputes or differences of any kind whatsoever, which shall at any time arise between the parties hereto, concerning the works or execution of this contract, shall, after written notice by either party to the contract to the other, be referred for adjudication to a sole Arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole Arbitrator, the Employer will send to the contractor within thirty days of receipt of his notice, a panel of three names of persons who shall be presently unconnected with the organisation for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select any one of the persons' names to be appointed as sole Arbitrator and communicate his name to the Employer within thirty days of receipt of the names. The employer shall thereupon, without any delay, appoint the said person as the Sole Arbitrator. If the contractor fails to communicate such selection, the employer shall make the selection and appoint the selected person as the Sole Arbitrator.

If the Employer fails to send to the contractor the panel of three names, as aforesaid, the contractor shall send a panel of three persons names to the Employer, who shall be unconnected with either party. The Employer, on receipt of the names select one and appoint him as the sole Arbitrator. If the Employer fails to do so within thirty days, and inform the contractor , the contractor shall be entitled to appoint one of the persons from the panel as the sole Arbitrator and communicate the name to the Employer.

If the Arbitrator so appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever, another sole Arbitrator shall be appointed as aforesaid.

The work under the contract shall, however, continue during the arbitration proceedings and no payment due or payable to the contractor shall be withheld on account of such proceedings. The Arbitrator shall be deemed to have entered on the reference on the date he issues notice to both the parties fixing the date of the first hearing. The Arbitrator from time to time, with the consent of the parties, extend the time for making and publishing the award.

The Arbitrator shall give a separate award in respect of each dispute referred to him, and shall decide each dispute in accordance with the terms of the contract and give a reasoned award. The venue of the arbitration shall be such place as fixed by the Arbitrator at his sole discretion.

The fees, if any, of the Arbitrator shall, if required to be paid before the award is made, be paid half and half by each of the parties. The Arbitrator may, at his security, fix or

Madras Electrical Consultants

17 of 26
For Kevin Electricals Pvt. Ltd.

Managing Director

LEELA SAMSON DIRECTOR

HEN +C

19. Samples & Approvals

All items of work requiring bought out or manufactured items, a sample should be got approved from the Architects and kept at site at all times for reference, before and after finishing of works till handing over. Should the contractor desire to substitute any materials and workmanship, they must obtain approval of the Architects in writing.

20. Insurance

- i) Unless otherwise instructed, the contractor shall insure the works and keep them insured until the virtual completion of the contract against loss or damage caused by fire and/or earthquake, flood etc. The insurance must be placed with a company approved by the Employer, in the joint names of the Employer and the contractor for an amount equivalent to the contract value plus 25%. The contractor shall deposit the policy and the receipt for premiums paid with Employer within 21(twenty one) days from the date of issue of work order unless otherwise instructed. In default of the contractor insuring as provided above, the Employer may insure on his behalf, and deduct the premiums paid from any money due, or which may become due, to the contractor.
- ii) The contractor shall also be responsible for any or all injuries to his workmen, and shall adequately cover his workmen under the Workmen's Compensation Act and shall indemnify the Employer against any claims, expenses, liabilities and proceedings arising out of injuries caused during the execution of the works.
- iii) The contractor shall also have adequate third party insurance cover and indemnify the Employer against claims, expenses, liabilities and proceedings towards any injury/ damage to any persons or properties as a direct consequence of the execution of the works.
- iv) The contractor shall also be responsible for all damages to work, structure, and/or decorative part of property which may arise from the operations or neglect of himself or any of his or sub-contractors workmen/employers, whether such damages arise from carelessness, accident or any other cause whatsoever in anyway connected with the carrying out of this contract. This clause shall be held to include inter-alia, any damage to properties whether immediately adjacent or otherwise and any damage to adjacent roads, tool paths etc.

21 Local rules and Bye-laws

The contractor should conform to the provisions of all local Bye-laws, Acts and Regulations relating to the work.

22. Labour Laws

The contractor shall comply with the provisions of all labour legislation including the requirements of :-

- a) The payments of Wages Act
- b) Employer's Liability Act
- c) Workmen's Compensation Act
- d) Contract Labour (Legislation and Abolition) Act, 1970 and Central Rules 1971.
- e) Apprentices Act 1961

f) Any other Act or enactment relating thereto and rules framed there under from time to time.

Madras Electrical Consultants

16 of 26

For Kevin Electricals Pvt. Ltd.

Managing Director

DIRECTOR OLENNAM

M/S.Center for Architectural Research & Design



tractor should endeavour to proceed with the works with the intent to prevent all delays and his doing so will be a ground for consideration by the Employer / Architects for an extension of time. The decision of a reasonable extension of time by Employer / Architects will be final and binding on the contractor.

13. Progress of work:

During the execution of the work, the contractor shall maintain proportionate contractor shall maintain progress on the basis of work execution programme. Contractor should also plan for scarce material / or materials with long delivery period, to ensure that the work proceeds as per the accepted work execution programme.

14. Liquidated damages:

Should the work not be completed to the satisfaction of Employer / Architects within the stipulated or extended time period, the contractor will be liable to pay liquidated damages as under:

a. For contracts having time for week of delay completion of months or less mum of 10% of the value of the work.

1% of the value of the work per (or part thereof) subject to maxi-

b. For contracts having time for week of completion of more than a months ject to a maximum of but less than 24 months.

1/2% of the value of the work per delay (or part thereof) sub-

5% of the value of the work.

16. Defects Liability Period

During the defects liability period as specified in the Appendix, the contractor is liable to rectify, remove and re-do any defects that arise out of faulty workmanship or usage of bad/inferior quality materials and make good the same to the satisfaction of Employer/Architects.

17. Variations

During the execution of the work, the Employer/Architects may want certain items of work deleted, added or modified to suit the overall requirements of the work. Contractor should carry out the works as per Architects instructions without these variations in anyway vitiating the contract.

18. Extra Items

The prices of all non-tendered items shall be worked out on the basis of rates quoted for similar items in the contract. If similar item is not quoted for in the contract, rates for extra items will be worked out by engineering rate analysis based on prevailing fair price of all inputs including labour, material and other components, plus 15% for contractor overheads and profits.

Madras Electrical Consultants

15 of 26

For Kevin Electricals Pvt. Ltd.

Managing Director

LOCA SAMSON DIRECTOR

10. Contractor to provide everything necessary:

The contractor shall provide everything necessary for the proper execution of work according to the intent and meaning of the drawings, schedule of quantities and specifications taken together whether or not the same may be specifically shown or described therein, provided that the same can reasonably be inferred there from and if the contractor finds any discrepancy therein he shall immediately refer the same to the Architects whose decision shall be final & binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the item in all respects and no extra payment will be allowed for incidental or contingent works, labour and / or materials inclusive of all taxes, levies and duties whatsoever, except where specifically provided for in the contact.

The contractor shall supply, fix and maintain at his own cost, for the execution of works, all tools, tackles, machineries and equipments and all the necessary centering, scaffolding, staging, planking, timbering, strutting, shoring, pumping, fencing, boarding, watching and lighting by day and night required not only for proper execution and protection of works but also for the protection of public and safety of any adjacent roads, streets, walls, houses, building and all other erections, matters and things, and the contractor shall take down and remove any or all such centering, scaffolding etc., as required or when directed or on completion of works and shall fully reinstate and make good all matters and things disturbed during the execution of works to the satisfaction of Architects/Employer.

The contractor shall also provide such temporary road(s) as may be necessary for proper performance of contract.

The contractor shall at all times give access to workers employed by employer, and provide them with necessary scaffolding, ladders, hoists, water and lighting and leave or make any holes, grooves etc., in any work, where directed by Architect / Employer to enable such workmen to carry out their works. The quoted rates of the contractor shall include all the above contingent works.

11 Time Schedule

The entire work is to be completed in all respects within the period stipulated in Clause 7 of NIT. Time is the essence of the contract and shall be strictly observed by the contractor. The work execution Programme submitted by the contractor as per clause 16 of "General Instructions to Tenderer" and duly modified by Architects / Employer to suit their specific requirements , will form the basis for execution of works.

If the employer wants to occupy the premises in parts the contractor shall complete the works of these parts, as per employers requirements and handover the same without vitiating the contract agreement.

12. Extension of Time

If in the opinion of Architects / Employer the works are delayed (a) by reason of exceptionally inclement weather or (b) by reason of instructions from Employer / Architects (c) by reason of delay in works by nominated sub-contractors (d) by reasons of authorised extra / additions in works or (e) from any other causes which in the opinion of the Employer / Architects are beyond the control of the contractor, the contractor may be allowed a reasonable extension of time for completion of the work. The contractor is required to give written notice, in the event of likely delays based on the causes listed above.

Madras Electrical Consultants

14 of 26

For Kevin Electricals Pvt. Ltd.

Managing Director

CHENN

4

8. Contract Drawings & Specifications:

Two set of drawings, approved for execution will be issued to the contractor progressively during the contract period. One set of drawings shall be kept at site and the same shall be available at all reasonable times, for inspection and use by Architects / Engineers.

In general the drawings shall indicate dimensions, positions and type of work. The specifications shall indicate the quality and methodology of execution. The schedule of quantities shall indicate the quantum and rate for each item of work. Any work detailed in drawings and not mentioned in the specifications or vice-versa shall be finished as though set forth in both. Work not specifically detailed, marked or specified shall be the same as the similar parts that are detailed, marked or specified.

The contractor's works shall not deviate from the drawings and specifications unless called for specifically by Architects instructions. The Architects' interpretation of the drawings and specifications shall be final.

Errors or inconsistencies, if any, found in the drawings and specifications shall be promptly brought to the attention of the Architects / Engineer for interpretation or correction.

Technical specification will take precedence over general specifications and specifications detailed in schedule of quantities shall take precedence over technical specifications.

In general, drawings shall prevail over specifications and large scale drawings and details shall prevail over small scale drawings.

9. Contractor's field organisation & equipments:

The contractor should deploy sufficient numbers of competent engineers / supervisors for supervising the works and carrying it out to the true meaning of the drawings, specifications and Architects / Employer instructions to the satisfaction of Architects / Employer. The site Engineer will use any or all of the instruments and tools belonging to the contractor for checking the works executed or being executed. One set of latest revisions of all the drawings should be properly mounted and maintained and be available at site at all times for inspection by Architects / Employer / Engineer.

Contractor shall provide, at his own cost, all temporary lighting required for his work and also enable other contractors / sub-contractors to complete the work within the specified time.

Contractor shall also provide and install all necessary hoists, ladders, scaffolding, tools, tackles and plant for satisfactory completion of the work in the scheduled time frame.

Contractor shall make his own arrangement for security and watch and ward to guard the site, the work and all materials at site at all times at his own expense, till handing over of the works. Contractor shall provide, erect and maintain proper shed for storage & protection of materials (including owner - issue materials, if any). All such temporary arrangements such as temporary lighting, sheds etc. put in place by the contractor for execution of work should be cleared away and made good on completion of works.

Madras Electrical Consultants

13 of 26

For Kevin Electricals Pvt. Ltd.

Managing Director

DIRECTOR

RUVANA

M/S.Center for Architectural Research & Design

78

within a further period of seven days by the Architects, shall constitute Architects instructions within the scope of contract.

5. Contractors Representative:

The contractor should, at the time of taking over the site or at any time prior to that inform the Architect about the name and experience of his site representative who will be responsible for day-to-day work and to take instructions from Architects / Engineers. This site representative should have suitable qualification and experience.

6. Site Engineer / Engineer

Site engineer shall be appointed by the Employer / Architect to oversee the works. The contractor shall afford the Engineer every facility and assistance for examining the works and materials and for checking and measuring the works and materials.

The Engineer shall have the power to give notice to the contractor or his representative of non-approval of any work or material(s) and such works shall be suspended or the use of such materials shall be discontinued until decision of Employer / Architects is obtained.

Though the works will be examined from time to time by Architects / Engineer, such examination shall not in any way exonerate the contractor from the obligation to rectify any defects which may be found to exist at any stage of the work or after the same is complete.

7. Setting Out:

The Architects shall determine the lines and levels which may be required for the execution of the work and shall furnish the same to the contractor by way of accurately dimensioned drawings to enable the

contractor to set out the work at ground level. The contractor shall be responsible for the true and proper setting out of work and for the correctness of the position, levels, dimensions, and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith. The contractor is to construct and maintain proper benches of all main walls / columns centre lines to facilitate accurate checking of lines & levels at any time. Where construction of benches is not possible, the lines and levels should be maintained on the surface of the wall / columns etc. by means of paint or any permanent marking.

The contractor shall carefully protect all such benchmarks, levels and other things used in setting out the works.

The contractor shall provide all necessary instruments, appliances and labour required by the Architect or his representative for checking of the setting out. If at any time during the progress of the works any error shall appear or arise in the position, level, dimensions or alignment of any part of the works, the contractor shall rectify at his own cost such errors to Architects satisfaction, if required to do so by the Architects. The checking of any setting out by the Architect shall not in any way relieve the contractor of his responsibility for the correctness thereof.

Madras Electrical Consultants

12 of 26

For Kevin Electricals Pvt. Ltd.



xii) "Contract" shall include the Notice inviting tender, Instructions to tenderer, General & special conditions, Technical specifications and schedule of quantities, approved work completion schedule, drawings, details and instructions given by Employer / Architects from time to time, the work order / letter of acceptance along with all attachments and annexures.

2. HEADINGS:

The headings in the text of tender / contract documents shall not effect the interpretation thereof.

3. For the purpose of interpretation, the use of singular shall include the plural and viceversa.

4. SCOPE:

The scope of work consists of executing the works in accordance with the drawings & schedule of quantities and in accordance with the conditions of this contract. It includes furnishing of all materials labour, tools & equipments and management necessary for and incidental to the execution and completion of work. All works, during its progress and upon completion, shall conform to lines, levels and grades as shown on the drawings. Should any detail essential for efficient completion of the work be missing from the drawings and specifications, it shall be the responsibility of the contractor to approach the Architect / Employer for clarification, and to install such details with Architects / Employers concurrence, so that upon completion of the proposed work the same will be acceptable and ready for use.

The architects may in their absolute discretion, and from time to time, issue further drawings, instructions, details, directions and explanations which are, hereafter collectively referred to as "Architects Instructions" in regard to:

- a) The variation or modification of design, quality or quantity of works or the addition, omission or substitution of any work.
- b) Any discrepancy in the drawings or between the schedule of quantities and / or drawings and / or specifications.
- c) The removal from site of any material defective or otherwise, brought thereon by the contractor and the substitution by any other materials.
- d) The demolition, removal and / or re-execution of any work executed by the contractor.
- e) The dismissal from the work of any person(s) employed thereupon.
- f) The opening up for inspection of any work covered up.
- g) The rectification and making good of any defects during execution and those arising during maintenance period / defects liability period.

The contractor shall forthwith comply with and duly execute any work comprised in such Architects Instructions, provided always that verbal instructions directions & explanations given to the contractor or his representative by the Architects, shall, if involving a variation, be confirmed in writing by the contractor within three days, and if not dissented in writing

Madras Electrical Consultants

11 of 26

For Kevin Electricals Pvt. Ltd.

GENERAL CONDITIONS OF THE CONTRACT

1. Interpretation

In construing these conditions, the specifications, the schedule of quantities, tender and agreement and all other connected documents / drawings / details, the following words shall have the meaning herein assigned to them except where the subject or context otherwise requires:-

- i) Employer: The term employer shall denote KALAKSHETRA FOUNDATION, CHENNAI and any of its employee authorised on their behalf and / or their heirs, legal representatives, assigns and successors.
- ii) Architects: The terms Architects shall mean M/s. Centre for Architectural Research & Design, or in the event of their ceasing to be the Architects for the purpose of this contract, such other person(s) as the Employer shall nominate for the purpose.
- iii) Contractor: The term contractor shall mean with offices at who have been assigned to do the work, and their heir, legal representatives, assigns and successors.
- iv) "Work" shall mean the works described in the tender documents in individual work orders, accompanying drawings and specifications, further drawings / details that may be issued from time to time including all modifications, additions and deletions, as per Employer's / Architects instructions, to be carried out either at site, or at any workshop / factory or any other place, as required for performance and completion of the contract.
- v) "The site" shall mean the site where the works are to be executed, or any other land, including any building or erections thereon, allotted by the Employer for contractor's use.
- vi) "Engineer" or "Site Engineer" shall be the person appointed / nominated by the Employer, to oversee the works at site.
- vii) "Bill of quantities" or "Schedule of quantities" shall mean the schedule of quantities as specified and forming part of the tender and any modifications, additions and deletions thereof.
- viii) "Priced Bill of Quantities" shall mean the Bill of quantities duly priced with the accepted quoted rates of the contractor.
- ix) "Specifications" shall mean the technical specifications, details given in the drawings and bill of quantities and / or as per relevant Indian Standard codes, including all unto date amendments and revisions.
- x) "Approval" or "Direction" shall mean the approval or direction of the Employer / Architects or persons deputed by them for the purpose.
- xi) "Notice" shall mean notice given in writing, sent by post (ordinary or registered) or through courier / fax / e-mail, to the last known address of the addressee and shall be deemed to have been received when in the ordinary course of the post it would have been delivered.

Madras Electrical Consultants

10 of 26

For Kevin Electricals Pvt. Ltd.



- 8. The rates quoted in the tender should be for finished work and should include the cost of all materials, labour, equipments and tools and plants therein. The rate must also include the cost of transportation, all statutory levies such as sales tax, excise duty, octroi, works contract tax and any other taxes / duties as may be applicable.
- 9. The rates should also include all charges for clearing of site before commencement and after completion, temporary connection for power & water, fencing, hoarding, plant & equipment, storage sheds, watch & ward and work during nights & holidays / Sundays.
- 10. The rates quoted shall be firm for the entire contract period, including extended time if any, without any variation.
- 11. The tenderer should note that the tender is strictly on item rate basis and rates for each & every item should be correct, workable and self-supporting. The items of works and quantities shown in the Bill of quantities are only indicative and may vary to any extent and are liable to alteration by omissions, additions or deletions at the discretion of Employer / Architect. No claim shall be entertained on account of variation of quantities.
- 12. The employer reserves the right to assign the works in full or in part to one or more tenderer. The employer also does not bind himself to accepting the lowest or any tender and reserves the right to accept or reject any or all of the tenders, in part or whole, without assigning any reasons for doing so.
- 13. If the tender is submitted by an individual, it shall be signed and stamped with tenderers' full name and address. If the tenderer is a partnership firm, the names and addresses of all partners should be provided along with a power of attorney for the authorised signatory. If the tenderer is registered under the Registrar of Companies as a limited company, the tender should bear the official stamp of the company and a power of attorney with a copy of Memorandum and Articles of Association / incorporation certificate should be submitted along with the tender.
- 14. On receipt of intimation from the Employer / Architect confirming acceptance of the tender, the successful tenderer should execute the contract agreement within 10 (ten) days, as per the Articles of Agreement given in the tender document. However a written acceptance of the tender by the Employer will constitute a binding contract between the employer and the tenderer whether the formal agreement is executed or not.
- 15. The defects liability period for the contract will be 12 (twelve) months and will be reckoned from the date of virtual completion, as certified by the Architects.
- 16. The tenderer shall prepare and submit a work execution programme along with the tender indicating the expected date of starting and completion of each item of work. The programme shall also indicate the scheduling of samples / shop drawings and approval and shall be supported by manpower schedules, plant, tools, machinery and formwork availability, material procurement schedules etc. This programme duly modified to suit the specific requirement of Employer / Architect will form part of the contract Documents.
- 17. Sealed tenders should be addressed to M/s. Madras Electrical Consultants on or before 4.30p.m. on 10.09.2010 at the office of M/s Kalakshetra Foundation, Chennai

Madras Electrical Consultants

9 of 26

For Kevin Electricals Pvt. Ltd.





VMIYUR.

Abstract of Main Clause

1. **Power and water** : In contractor Scope, should have adequate power supply from start of the project till completion.

2. **Scaffolding** : Shall erect necessary scaffoldings for the scope of work.

3. Labour compliance : Shall strictly adhere to the state / central labour laws, shall have necessary insurance for labours and tools and plants.

4. Indemnification of principal employer: Contractor shall indemnify the principal employer through indemnification bond from all claims arising out of this contract.

5. EHS : Contractor shall submit the EHS plan along with the tender.

GENERAL INSTRUCTIONS TO THE TENDERERS

1.0 In interpreting the text following definitions will apply:-

- 1.1 Employer will mean KALAKSHETRA FOUNDATION , Chepauk, Chennai.
- 1.2 Architects will mean M/s. M/s. Centre for Architectural Research & Design, No.10-A First Floor, Dhanalakshmi Colony, Vadapalani.
- 1.3 Tender / tender documents will be taken to include Notice inviting tender, form of tender, General Instruction of Tender, General and Special conditions of the contract, Technical specifications, Bill of quantities and tender drawings, along with their annexure and attachments.
- 2. Tenderer is advised to go through all the documents / drawings in connection with this tender carefully. Any clarifications in the documents and drawings can be had from the office of the Architects.
- 3. Tenderer is expected to visit the site of work prior to quoting their rates and obtain for himself on his own responsibility and at his own expense, all the information which may be necessary for the purpose of making the tender and for entering into a contract, and must examine the drawings, inspect the site of work and against himself with all local conditions, means of access to the work, nature of the work and all matters pertaining thereto.
- 4. The tenderer must use only the forms issued by the Architects / Employers to fill in the rates.
- 5. The tender form must be filled in English and all entries must be handwritten. Tenders not filled properly or mutilated or generally not complying with the tender conditions may be rejected. If any document, including the tender drawings, is missing, or is unsigned, the tender may be considered invalid by the employer at his discretion.
- 6. All rates should be given both in figures and words. Erasures and over writings are not permitted. All corrections, cancellations and alterations in the entries must be attested by the tenderer's signature.

7. Each page of the tender documents and each of the drawings should be stamped and signed by the tenderer as a token of having read and understood them.

Madras Electrical Consultants

VELACHERY CHENNAL-42. 8 of 26

For Kevin Electricals Pvt. Ltd.

M/S.Center for Architectural Research & Design

10. Submittals:

- 1. Hand over certificate with the brief description of work.
- 2. No Claim certificate
- 3. List of inventory
- 4. Snag List with all snags status
- 5. Warranty / Guarantee certificate
- 6. Contact (Land Line and Mobile) list with complete address.
- 7. Escalation chart up to four levels
- 8. Emergency contact Nos for Life saving systems
- 9. Service level agreements for all major repairs. 10.

List of any surplus material.

- 11 As built, SLD's and GFC Drawings in hard and soft copies.
- 12. Test Certificates
- 13. Material Inspection report.
- 14. Key Management for related packages

CHENNA AND CHARACTER AND CHARA

7 of 26

For Kevin Electricals Pvt. Ltd.

Managing Director

Madras Electrical Consultants

VELACHERY CHENNAL42



Abstract of Fiscal Terms

1. Mobilisation Advance:

Upto 15% of Contract value of work against Bank Guarantee, (as per format attached) to be adjusted against payment of the Contractor's running bills.

2. EMD:

1% of the total value of EMD in favour of THE DIRECTOR,M/S.KALAKSHETRA FOUNDATIONS in the DD format at time of tender submission

3. Retention Money

@ 5% retention amount for a period of six month from the date of commissioning, if your are providing EMD or else it will be 10 % retention.

4. Time for Completion:

60 days

5. Defects Liability Period:

12 months from the date of issue of completion certificate by the Architect

6. Compensation for Delay by the Contractor: ½ % per week subject to maximum of 5% of the Contract Value

7. Bills

a. Period:

as discussed at the time of negotiation

b. Value:

as discussed at the time of negotiation

Bills will be cleared based on the remittance of ESI & PF of the previous month.

8. Certification of bills:

a) Only supply and erection bill will be certified, on an percentage basics.

9. Payment:

LEETA SAMSON MARIO.

a) Certification of bill cleared by client by 7 working days.

c) Final bill will be certified within two weeks of submission and payment will be released within 3 weeks thereafter.

Madras Electrical Consultants

VELACHER

6 of 26

For Kevin Electricals Pvt. Ltd.



M/S.Center for Architectural Research & Design



ARTICLES OF AGREEMENT

This Articles of Agreement of this contract is made at this day of between (hereinafter referred to as "Employer" which term shall include their heirs, executors, administrators and assigns) of the FIRST PART and

(herein after referred to as "Contractor", which expression shall include their heirs, executors, administrators and assigns) of the OTHER PART

Whereas the employer is desirous of carrying out the works of and has caused the drawings, details, specifications, and schedule of probable quantities describing the works, to be prepared by M/s. M/s. Centre for Architectural Research & Design, No.10-A First Floor, Dhanalakshmi Colony, Vadapalani, Chennai – 600 026. hereinafter referred to as "Architects";

And whereas it is understood that the said drawings as issued from time to time, the notice inviting tender, general instructions to the contractor, general & special conditions of the contract, technical specifications work completion schedule, priced schedule of quantities and details and instructions issued by Architects from time to time will be construed to form part of the contract;

NOW IT IS AGREED BY AND BETWEEN THE PARTIES AS FOLLOWS:

- 1. In consideration of payments to be made by the employer, the contractor shall execute and complete the works in accordance with the drawings, details and instructions to be issued by the Architects from time to time, and described in the priced schedule of quantities at the prices set forth therein and in accordance with the contract.
- 2. In consideration of the execution of the work by the contractor, the Employer undertakes to pay the contactor such sums as may become due to him from time to time in accordance with the conditions set forth in the contract.
- 3. The contract is neither a lump sum or a piece rate contract, but is a contract to carry out the works in its entirety, to be actually measured and paid for at the rates specified in the priced schedule of quantities or otherwise agreed to, regardless or whether such works are shown in the drawings or described in the schedule of quantities.

In witness whereof the employer and the contractor have set forth their hand to these presents on day of

Witnesses

(EMPLOYER)

1.

2.

Witnesses

1.

2.

CHENNAU CHENNAU

(CONTRACTOR)

Madras Electrical Consultants

5 of 26

For Kevin Electricals Pvt. Ltd.

Managing Director

DIRECTOR DIRECTOR

FORM OF TENDER

The Director, Ms. Kalakshetra Foundation

Dear Sir,

Having examined the drawings, specifications, design and schedule of quantities and all other relevant contract documents relating to the works specified in the memorandum hereinafter set out and having visited and examined the site of the works specified in the said memorandum and having acquired the requisite information relating thereto as affecting the tender, I / We hereby offer to execute the works specified in the said memorandum, within the time specified in the said memorandum at the rates mentioned in the attached schedule of quantities and in accordance in all respects with the specifications, drawings and instructions in writing referred to in conditions of tender, the articles of agreement, special conditions, schedule of quantities and conditions of contract in all respects in accordance with such conditions so far as they may be applicable.

MEMORANDUM

a. Description of works:

Electrical Works as per Specifications for Koothambalam at KALAKSHETRA FOUNDATION

b. Time allowed for completion of the Works from the date of agreement

60

days

The names of partners of our firm are:

(i)

(ii)

Name of the partner of the firm authorised to sign:

Name of the person having power of attorney to sign the contract (Certified true copy of the power of attorney should be attached) Signatures and address of witness:

(1)

(2)



Yours faithfully,

Signature of Contractor

ANMIYUR, CHEN

Madras Electrical Consultants

4 of 26

For Kevin Electricals Pvt. Ltd.





NOTICE INVITING TENDER

NAME OF WORK: Electrical works for KOOTHAMBALAM KALAKSHETRA FOUNDATION, CHENNAI.

- 1. KALAKSHETRA FOUNDATION, is renovating Electrical works carry out the **Electrical** works at Koothambalam their premises. Sealed tenders are hereby invited from competent contractors who have to experience of executing such works.
- 2. M/s. Centre for Architectural Research & Design with office at No.10-A First Floor, Dhanalakshmi Colony, Vadapalani, Chennai 600 026. Have been appointed Architects for the works.
- 3. Tender document duly completed in all respects and signed must be submitted in a sealed envelope super scribed with the name of the work before 4.30p.m. on 12.09.2010 at the office of M/s Madras Electrical Consultants, # 6, Park Avenue, First Cross Street, Velachery, Chennai 600 042. The name and address of the Tenderers must be clearly written / printed on the envelope.
- 4. The tender should be valid for 60 (Sixty) days from the date of opening of tender.
- 5. The time period for completion of the works will be 60 **days**, reckoned from the date of release of work order / letter of intent or handing over of site whichever is earlier.

CHENNAL LE COLLEGE

Madras Electrical Consultants

3 of 26

For Kevin Electricals Pvt. Ltd.

CONTENTS

- 1. NOTICE INVITING TENDER
- 2. FORM OF TENDER
- 3. ARTICLES OF AGREEMENT
- 4. GENERAL INSTRUCTIONS TO THE TENDERERS
- 5. GENERAL CONDITIONS OF CONTRACT
- 6. APPENDIX TO GENERAL CONDITIONS OF CONTRACT



Madras Electrical Consultants

2 of 26

For Kevin Electricals Pvt. Ltd.



M/S.KALAKSHETRA FOUNDATION, CHENNAI

ELECTRICAL WORKS TENDER DOCUMENT

ARCHITECTS

RAVI NIILAKANDAN
M/S.CENTER FOR ARCHITECTURAL
RESEARCH & DESIGN
No.10-A First Floor,
Dhanalakshmi Colony,
Vadapalani,
Chennai – 600 026.

ELECTRICAL CONSULTANTS

MADRAS ELECTRICAL CONSULTANTS # 6, PARK AVENUE I CROSS STREET VELACHERY CHENNAI – 600 042.



Madras Electrical Consultants

1 of 26

For Kevin Electricals Pvt. Ltd.



1.09	9.2010		
1AK	ES OF MATERIALS PROPOSED TO BE USED FOI	R M	/S. KALAKSHETRA AT CHENNAI.
1	MCCB RATED SERVICE VOLTAGE : 690V		SIEMENS / ABB / L&T
2	STARTERS & CONTACTORS		SIEMENS / ABB / L&T
3	MCB DBs		HAGER / LEGRAND / SIEMENS / MOELLER
4	ELMCB s/ MCBs		HAGER / LEGRAND / SIEMENS / MOELLER
5	LOCKABLE TYPE PLUG & SOCKETS (INDOOR) WEATHER PROOF JUNTION BOX / MCB CONTROL POWER PLUG AND SOCKET		MENNEKES / HENSEL
6	LT CABLES		UNIVERSAL / POLYCAB / GLOSTER
7	LT CABLE TERMINATIONS Double compression type		JAINSONS / DOWELLS / SIEMENS /COMET
8	PVC INSULATED COPPER CONDUCTOR WIRES		
	a) UPTO 6 SQ.MM.(FRLS)		RR KABEL / POLYCAB / HAVELLS
	b) ABOVE 6 SQ.MM.(FR)		RR KABEL / POLYCAB / HAVELLS
9	MS CONDUITS		GUPTA / BHARAT
10	PVC CONDUITS		ESSORKE / AVONPLAST
11	MODULAR SWITCHES/ SOCKETS & PLUGS		M K / CRABTREE / LEGRAND / SIEMENS
12	LIGHT FITTINGS	ļ	GE / ASIAN RAYMOLD / THORN
13	EXHAUST FAN		ALMONARD / Ebm NADI
14	FIRE EXTINGUISHER		CEASE FIRE / MINIMAX / USHA
15	LIGHTNING PROTECTION		INJESCO / ERICO
16	PVC TRUNKING		LEGRAND / MK
17	CABLE TRAY		PROFAB / HITECH (or) EQUIVALENT



1 of 1

For Kevin Electricals Pvt. Ltd.

Managing Director

LEELA SAMSON Z DIRECTOR

	(Rupees Fifty Lakhs Sixty Thousand Five Hundred a	nd Nir	nety One	Only)			5,060,591.00
					4,051,175.00		1,009,416.00
,	Add: Service Tax 10.3% on Erection						94,261.00
	Grand Total				4,051,175.00		915,155.00
0.07.00	Preparation of "As Built Drawings"	LS			,	10,000.00	10,000.00
	Supplying, erecting, connecting & commissioning WEATHER PROOF HENSEL MAKE JUNCTION BOXES with 6 - 20 Amps SP c curve MCB and supports, Connector and necessary accessories.	15	Sets	1,400.00	21,000.00	150.00	2,250.00
	LT cable route maker	20	Sets	250.00	5,000.00	200.00	4,000.00
20.04.00	Shifiting of pillar box with cable routing with EB person and related to necessary accessories etc. approximate shifted distance is 25 mtr.	LS				7,500.00	7,500.00
	Liasion with Electricity Board for enhancement of 1 no 100 Amps energy meter to CT Meter Board connections including submission of Application Forms and otherassociated works.	LS		,	-	25,000.00	25,000.00
20.02.00	Liasion with Electricity Board to avail 1 CT Meter Board connections including submission of Application Forms and otherassociated works.	LS				125,000.00	125,000.00
20.01.00	Providing Temporary lighting at site complete with wiring 20 Nos. of 1 x 40 W tube light fitting.	LS		10,000.00	10,000.00	2,500.00	2,500.00
20.00.00	MISCELLANEOUS	2	SET	450.00	900.00	50.00	100.00
19.06.00	First Aid Box						
19.05.00	Supplying and fixing 440 V Danger Board.	3	NOS.	100.00	300.00	10.00	30.00
19.04.00	Supplying, and laying 1800 mm. x 1200 mm x 6 mm. thick ISI Marked Rubber mats to be laid in Front of the Panel Boards.	10	NOS.	1,400.00	14,000.00	25.00	250.00
19.03.00	Supplying 440 V Gloves	2	SET	450.00	900.00		-
19.02.00	Supplying, erectingand connecting Treatment Chart in English and Tamil directly fixed on to the wall with necessary screws etc.	4	NOS.	350.00	1,400.00	25.00	100.00
19.01.00	Supplying, erecting and connecting a 5 KG FIRE EXTINGUISHER properly fixed on the wall with necessary clamps, screws, bolts and nuts etc. The extinguisher shall be suitable for all types of fires (A. B. & C).	5	NOS	2,900.00	14,500.00	50.00	250.00



N. R. Nagarejan.

CHENNA)

For Kevin Electricals Pvt. Ltd.

m / m /

Managing Director

PAGE 14 OF 14

DIRECTOR DIRECTOR

	*						
15.01.00	Fixing, connecting and commissioning of BOLLARD LIGHT FITTING OF PHILIPS MAKE CAT # HS 360 1x PL C 18 FOR shall be mounted on already constructed pedestal withnecessary Weather Proof Junctionboxes, interconnections between the Junction boxand the fitting shall bedone with 3 Runs of 2.5 Sq.mm. PVC Insulated copper conductor wires in 2 mm. thick PVCconduits concealed in gatepiller with necessaryclamps, screws etc. The Junction box shall	1					·
	bemade out of 2 mm. thick M.S.Sheet painted withtwo coats of red oxide primer,2 A rewireable Fuse units, 1 No. 5 A One way Switch loop in loop out arrangements concealedin the wall of gate pillar.	30	NOS.		<u>-</u>	1,100.00	33,000.00
15.02.00	Fixing, connecting and commissioning Bulk Head Light fittings to be fixed on the Compound Wall with necessary accessories required for the iob.	10	Nos		-	60.00	600.00
16.00.00	JUNCTION BOXES						
16.01.00	Supplying, erecting 14 G thick Junction boxes with cover of 40 mm. height of suitable sizes as per Site conditions. The Junction boxes shall be fixed flush with the floor (powder coated)	500	SQ.FT	120.00	60,000.00	25.00	12,500.00
17.00.00	ADVANCED TYPE LIGHTNING PROTECTION						
17.01.00	Supplying, erecting, connecting and commissioning the Dynosphere (CSE TYPE) with necessary foundation plate, mounting screws / bolts, andother associated accessories to complete the system to function.	1	Set	90,000.00	90,000.00	5,000.00	5,000.00
17.02.00	Supplying, laying, connecting and commissioning 75 KV 36 mm dia special copper cable(only meant for these applications) in G I pipe for protection of the cable with necessary accessories as required.	140	Mtrs	325.00	45,500.00	50.00	7,000.00
17.03.00	Supplying, providing and connecting Eath Gel in the Earth Electrode with necessary accessories. As required by the system	3	Sets	13,500.00	40,500.00	2,000.00	6,000.00
17.04.00	Supplying, erecting, connecting and commissioning a Lightning Event Counter of digital type in weather proof enclosure with necessary accessories	1	Set	20,000.00	20,000.00	1,000.00	1,000.00
17.000	Tesing and commissioning of the System (Lumpsum)	1	Set			5,000.00	5,000.00
18.00.00	AUTO POWER FACTOR CAPACITOR BANK		Set		-	3,000.00	3,000.00
	Supplying, erecting and commissioning of 60 KVAR APFC in the enclosed MS Enclosure with all interconnections of Capacitor Bank for 12 Step Relay APFC shall be incorporated to maintainpower factor suitable to accommodate thefollowing capacitor bank with all interconnections 10 KVAR - 3 Nos						
	5 KVAR - 3 Nos 3 KVAR - 3 Nos						
	2 KVAR - 2 Nos						
	1 KVAR - 1 Nos 1 No. Class 1.0 96 Sq.mm Digital Power Factor Meter.	2	Sets	75,000.00	150,000.00	1,500.00	3,000.00
19,00.00	SAFETY EQUIPMENTS						-

chile For Kenin Electricals Pvt. Ltd.

OF ICN +CO

Managing Director

PAGE 13 OF 14

DIRECTOR CHENNAL

of 2 core speaker cable in trunking and conduit of 20 core speaker cable in trunking and conduit of 4 core speaker cable in trunking and conduit of 4 core speaker cable in trunking and conduit of 5 quantity of 4 core speaker cable in trunking and conduit of 6 quantity of 4 conduit and input module box wall and proper civil finishing box will be ed by cilent of 6 quantity of 5 quantity of 6 quantity of 6 quantity of 7 quantity of 7 quantity of 8 quantity of 9 q	500 500 20	Mts Mts Nos		-	12.00 25.00 15.00	7,500.00
ng, flush mounted output and input module box wall and proper civil finishing box will be ed by cilent ng, flush mounted of connector terminal and suitable for 4module powder coated ms base box e terminal.plate and terminal will be supplied by Y PVC CONDUITS ying, laying of Heavy duty PVC conduit laid in concealed in wall / partitions with accessories,	500	Mts Nos		-	15.00	
ng, flush mounted output and input module box wall and proper civil finishing box will be ed by cilent ng, flush mounted of connector terminal and suitable for 4module powder coated ms base box e terminal.plate and terminal will be supplied by Y PVC CONDUITS ying, laying of Heavy duty PVC conduit laid in concealed in wall / partitions with accessories,	20	Nos		-		7,500.00 3,000.00
wall and proper civil finishing box will be ed by cilent ng, flush mounted of connector terminal and suitable for 4module powder coated ms base box e terminal.plate and terminal will be supplied by Y PVC CONDUITS ying, laying of Heavy duty PVC conduit laid in concealed in wall / partitions with accessories,				-	150.00	3,000.00
suitable for 4module powder coated ms base box e terminal.plate and terminal will be supplied by Y PVC CONDUITS ying, laying of Heavy duty PVC conduit laid in concealed in wall / partitions with accessories,	20	Nos	,			
ring, laying of Heavy duty PVC conduit laid in concealed in wall / partitions with accessories,			1		75.00	1,500.00
concealed in wall / partitions with accessories,						
n. dia PVC Conduits	200	Mts	30.00	6,000.00	8.00	1,600.00
n. dia PVC Conduits	300	Mts	40.00	12,000.00	10.00	3,000.00
n. dia PVC Conduits	50	Mts	58.00	2,900.00	15.00	750.00
n. dia PVC Conduits	100	Mts	75.00	7,500.00	20.00	2,000.00
IG OF LIGHT FITTINGS (INTERNAL - 10N AREA)						
, connecting and commissioning Ceiling light / ilier / wall light Fitting with necessary accessories ed for the iob.	100	Nos		-	75.00	7,500.00
ring, fixing of Ceiling fan with necessary down lamps, screws etc.	20	Nos	1,450.00	29,000.00	150.00	3,000.00
ring, fixing of Exhaust fan with louvres, brackets ecessary clamps, screws etc.	10	Nos	1,100.00	11,000.00	150.00	1,500.00
connecting and commissioning of 2 x18 W PL LIGHT FITTING RECESSED DOWN LIGHTER, of PS MAKE FBS/145/218L with Horizontal lamp on (or) equivalent	50	Nos		-	90.00	4,500.00
connecting and commissioning of 1x 40W PATTI FITTING PHILIPS MAKE TMC55/136HF fixing in iling with all necessary accessories.	50	Nos		-	40.00	2,000.00
connecting and commissioning of 2 x36 W CFL SED PHILIPS MAKE FBS470/236 AGHFPS P5 236 quivalent with Electronic Ballast complete fixing false ceiling with all necessary accessories.		Nos			175.00	5,250.00
FIXTURES (EXTERNAL)		A STATE OF THE PARTY OF THE PAR				
: Only Light Fitting and Lamp will be ied by Client. All other accessories like os, screws etc., shall be included in the	18 4.C.	WHEN,	SV EARC			
iii iiii	S MAKE FBS/145/218L with Horizontal lamp (or) equivalent connecting and commissioning of 1x 40W PATTI ITTING PHILIPS MAKE TMC55/136HF fixing in ling with all necessary accessories. connecting and commissioning of 2 x36 W CFL SED PHILIPS MAKE FBS470/236 AGHFPS P5 236 uivalent with Electronic Ballast complete fixing alse ceiling with all necessary accessories. FIXTURES (EXTERNAL) Only Light Fitting and Lamp will be ed by Client. All other accessories like	S MAKE FBS/145/218L with Horizontal lamp in (or) equivalent connecting and commissioning of 1x 40W PATTI ITTING PHILIPS MAKE TMC55/136HF fixing in ling with all necessary accessories. connecting and commissioning of 2 x36 W CFL SED PHILIPS MAKE FBS470/236 AGHFPS P5 236 uivalent with Electronic Ballast complete fixing false ceiling with all necessary accessories. 30 FIXTURES (EXTERNAL) Only Light Fitting and Lamp will be ed by Client. All other accessories like s, screws etc., shall be included in the	S MAKE FBS/145/218L with Horizontal lamp In (or) equivalent Connecting and commissioning of 1x 40W PATTI ITTING PHILIPS MAKE TMC55/136HF fixing in ling with all necessary accessories. Connecting and commissioning of 2 x36 W CFL SED PHILIPS MAKE FBS470/236 AGHFPS P5 236 uivalent with Electronic Ballast complete fixing ralse ceiling with all necessary accessories. 30 Nos FIXTURES (EXTERNAL) Only Light Fitting and Lamp will be ed by Client. All other accessories like s, screws etc., shall be included in the	S MAKE FBS/145/218L with Horizontal lamp In (or) equivalent connecting and commissioning of 1x 40W PATTI ITTING PHILIPS MAKE TMC55/136HF fixing in ling with all necessary accessories. connecting and commissioning of 2 x36 W CFL SED PHILIPS MAKE FBS470/236 AGHFPS P5 236 uivalent with Electronic Ballast complete fixing alse ceiling with all necessary accessories. 70 Nos FIXTURES (EXTERNAL) Only Light Fitting and Lamp will be ed by Client. All other accessories like s, screws etc., shall be included in the	S MAKE FBS/145/218L with Horizontal lamp In (or) equivalent connecting and commissioning of 1x 40W PATTI ITTING PHILIPS MAKE TMC55/136HF fixing in ling with all necessary accessories. connecting and commissioning of 2 x36 W CFL SED PHILIPS MAKE FBS470/236 AGHFPS P5 236 uivalent with Electronic Ballast complete fixing false ceiling with all necessary accessories. 30 Nos FIXTURES (EXTERNAL) Only Light Fitting and Lamp will be ed by Client. All other accessories like s, screws etc., shall be included in the	S MAKE FBS/145/218L with Horizontal lamp (or) equivalent Connecting and commissioning of 1x 40W PATTI ITTING PHILIPS MAKE TMC55/136HF fixing in ling with all necessary accessories. Connecting and commissioning of 2 x36 W CFL SED PHILIPS MAKE FBS470/236 AGHFPS P5 236 uivalent with Electronic Ballast complete fixing alse ceiling with all necessary accessories. 30 Nos FIXTURES (EXTERNAL) Only Light Fitting and Lamp will be ed by Client. All other accessories like s, screws etc., shall be included in the

For Kevin Electricals Pvt. Ltd.

Managing Director

PAGE 12 OF 14

DIRECTOR

DIRECTOR

CHENNIAL

10.01.00	Supplying, fabricating, erecting, connecting & commissioning of the Powder coated Cable Trays with necessary Angle irons for cable supports and other allied fabrication works. Fixing to concrete surfaces shall be done with the help of expandable type anchor fastners capable of bearing a weight of 500 Kgs. Fixing to brick walls shall be done with grouting. The distance between two supports shall be 600mm. The materials and labour for grouting, cable supports and other allied fabrication work shall supplied by the Contractor at no extra cost.	1000	Kgs	60.00	60,000.00	15.00	15,000.00
10.02.00	Supplying, fabricating, erecting, connecting & commissioning of the Perforated type GI Cable Trays with necessary Angle irons for cable supports and other allied fabrication works. Fixing to concrete surfaces shall be done with the help of expandable type anchor fastners capable of bearing a weight of 500 Kgs. Fixing to brick walls shall be done with grouting. The distance between two supports shall be 2000mm. Thematerials and labour for grouting, cable supportsand Provision for fixing allied fabrication work shall supplied by the contractor with provision for fixing Gi flats Throughout with connection point once every mtrs. on both sides all supports shall be with threaded rods once every 1500mm.						
	600 mm (w) x 50 mm (H)	75	Mtrs	760.00	57,000.00	125.00	9,375.00
	450 mm (w) x 50 mm (H)	75	Mtrs	650.00	48,750.00	110.00	8,250.00
	300 mm (w) x 50 mm (H)	100	Mtrs	550.00	55,000.00	100.00	10,000.00
	Supplying, erecting, connecting & commissioning of the 6 mm thread rod with slotted channel supports and welded in the stress supports for the GI trunking and related to all accessories etc.	300	Mtrs	160.00	48,000.00	50.00	15,000.00
11.00.00	G I TRUNKING						
	Supplying, rabricating, laying and connecting the following GI TRUNKING with cover of 1.6 mm. Thick embedded in the floor (or) open in ceiling / laid in below false flooring with thread rod and rail supports including of L shape,T shape and necessary support,clamps screws and all accessories etc.				·		
	100 x 45 mm	200	MTS	350.00	70,000.00	60.00	12,000.00
	150 x 45 mm	100	MTS	425.00	42,500.00	75.00	7,500.00
	200 x 45 mm.	50	MTS	475.00	23,750.00	90.00	4,500.00
12.00.00	ERECTING OF SPEAKER EQUIPMENT.						
12.01.00	Erecting of wall mounted speaker with anchor fasterner for 10 kgs weight with supports and clamp will be supplied by cilent	100	Nos		-	150.00	15,000.00
12.02.00	Erecting of ceiling hung speaker with rope support upto 50 kgs weight for sub hopper with supports and clamp will be supplied by cilent	4	Set	3	_	750.00	3,000.00

TECTURAL Kevin Electricals Pvt. Ltd.

Managing Director

PAGE 11 OF 14

DIRECTOR THUVANMIYUR, CHENNA

10.00.00	CABLE TRAY						
	Supplying, laying and connecting 25 Sq.mm.PVC Insulated copper conductor wires in PVC Conduits laid open fashion with necessary clamps, screws, interlinks etc.	100	Mtrs	190.00	19,000.00	25.00	2,500.00
09.09.00	Supplying, laying and connecting 500mm long 12 x 3 mm. Copper flat with SMC Insulator in open fashion with necessary clamps, screws,etc. as earth link for Data Earthing	10	Sets	250.00	2,500.00	100.00	1,000.00
09.08.00	Supplying, laying & connecting 500mm. long 25x6mm.Copper flat with SMC Insulator in open fashion with necessary clamps, screws,etc. as earth link for UPS	3	Sets	650.00	1,950.00	150.00	450.00
09.07.00	Supplying, laying, connecting and commissioning 8 SWG bare enamelled copper wire enclosed in PVC Conduits with necessary clamps, screws etc. for earthing AC Equipments / motors etc.	150	Mtrs	75.00	11,250.00	15.00	2,250.00
09.06.00	Supplying, laying & connecting 500mm. long 25 x 6 mm.GI flat with SMC Insulator in open fashion with necessary clamps, screws,etc. as earth link	4	Sets	350.00	1,400.00	100.00	400.00
09.05.00	Supplying, laying and connecting 25 x 6mm. CU Flat laid in open fashion with necessary clamps, screws,interlinks etc. for earthing the Panels / Stabilizer / DG netural	100	Mtrs	810.00	81,000.00	30.00	3,000.00
09.04.00	Supplying, laying and connecting 25 x 6mm. G.I Flat laid in open fashion with necessary clamps, screws,interlinks etc. for earthing the Panels / Stabilizer / DG body earthing etc.	300	Mtrs	100.00	30,000.00	20.00	6,000.00
09.03.00	Supplying, laying and connecting 50x6mm. G.I.Tape wound in half lapped fashion with bituminious tape painted at a depth of 600mm. in ground to interconnect the earth electrodes. The tape shall not come into contact with any unnecessary metal parts (or) cables along with its route	100	Mtrs	200.00	20,000.00	30.00	3,000.00
09.02.00	Supplying, installing and connecting a Copper plate of size 600mm.x 600 mm.x 3 mm. at a depth of 3000 mm. in an earth pit of 700 x 700 x 3500 mm. filled with salt and charcoal mixed with sand in alternate layers 150 mm. each upto a height of 3000 mm. from bottom. Two copper flats of 25 x 6mm. shall be braced to this copper plate throughout the overlaping length with the copper plate and brought to the surface of the earthpit. This copper flat shall have provision for connecting wires of flats as the case may be. A suitable size of 40 mm. dia GI Pipe shall be provided uptil the bottom of the earth pit. This GI Pipe shall have provision for watering through a funnel. A masonary strucutre shall be constructed to a depth of 450mm. and a heavy duty CI Cover shall be used to cover the pit. The cost of digging and back filling shall also be included . Sand, salt and charcoal are in the Contractor's scope.	6	Sets	12,000.00	72,000.00	2,500.00	15,000.00

MADRAS ELECTRICAL CONSULTANTS

(VELACHERY)

CHENNALAZ

For Kevin Electricals Pvt. Ltd.

Managing Director

PAGE 10 OF 14

DIRECTOR DIRECTOR

08.01.00	Supplying, wiring, connecting and commissioning the				T		
00.01.00	light points with 3 Runs of 1.5 Sq. mm. PVC insulated						
	multistranded Copper Conductor wires (One each for						
	Phase, Neutral and Earth) in Heavy duty PVC Conduits						
	concealed in wall / ceiling or open above false ceiling						
	with necessary clamps screws etc. including supplying	_					
	and fixing 6 Amps. Switch in manufacturers mounting						
	box fixed flush with the wall.						
08.01.01	One Light Controlled by one Switch	100	Pts.	550.00	55,000.00	90.00	9,000.00
08.01.02	Same as above item with additional light point.	70	Pts.	420.00	20 400 00	60.00	4 200 00
00.01.02	Same as above tern with additional light point.	70	PIS.	420.00	29,400.00	60.00	4,200.00
08.02.00	Same as the Item No. 08.01.00 but for 6 Amps.						
	Independant switched socket combined including	1.0	Dt-	1 150 00	44 500 00	200.00	
	supplying and fixing 6Amps Switched Socket.	10	Pts.	1,150.00	11,500.00	200.00	2,000.00
08.03.00	Same as the Item No. 08.01.00 but for Ceiling Fan						
	points including supplying, and fixing concealed type	20	DI-	1 200 00		150.00	
	fan hook box and electronic regulator.	20	Pts.	1,200.00	24,000.00	150.00	3,000.00
08.04.00	Same as Item No. 08.01.01 but for TWO WAY LIGHT						
	POINTS with 2Nos. 6 Amps Switches.	10	Pts.	850.00	8,500.00	150.00	1,500.00
08. 0	Same as Item No.08.01.00 but for TWO WAY Fan						
	POINTS with 2 Nos. 6 Amps. Switches.	5	Pts.	1,350.00	6,750.00	200.00	1,000.00
08.06.00	Same as the Item No. 08.01.00 but for Exhaust Fan						
	points.	10	Pts.	600.00	6,000.00	100.00	1,000.00
08.07.00	Same as the Item No. 08.01.00 but for Wall Mounted						
	Fan points.	2	Pts.	650.00	1,300.00	125.00	250.00
	Note:-						
	The cost of Supplying, Laying and Pulling for Circuit						
	Mains with 3 Runs of 1.5 Sq.mm. PVC Insulated						
	Multistranded Copper condutor wires in PVC Conduits						
	concealed in wall / ceiling or open above false ceiling (1	
	The average length shall be 7Mts from switch board to						
	light point and 10 mtr from DB to switch board) shall					1	
	be included in the Point rate for Light, Fan, Exhaust						
09 00 00	EARTHING						
09.	Supplying, installing and connecting a 2.5Mtr. long						
-	40mm. dia G.I.Pipe with holes drilled diametrically						
	opposite to each other once every 150mm. in an earth						
	pit of 380x380x3500mm. filled with salt and charcoal						
	mixed with sand in alternate layers 150mm.each upto				-		
	a height of 3000mm. from bottom. The pipe shall have						
	provision for watering through a funnel.It shall also					1 2	
	have provision for connecting 50x6mm.G.I. Flat on two						
	sides. A masonary strucutre shall be onstructed to a						
	depth of 450mm. and a Medium duty CI Cover shall be						
	used to cover the pit. The cost of digging and back						
	filling shall also be included. Sand,salt and charcoal are						
	in the Contractor's scope.	8	Sets	2,500.00	20,000.00	2,000.00	16,000.00

For Kevin Electricals Pvt. Ltd.

Managing Director

PAGE 9 OF 14

DIRECTOR PRUVANMIYUR, CHENNE

07.04.00	Supplying, laying, connecting & commissioning 2 Runs of 6 Sq.mm. with 1 Runs of 2.5 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for						
	continuous earthing in in PVC Conduits open above false ceiling or concealed in wall / ceiling with	450	Mts.	130.00	58,500.00	25.00	11,250.00
	necessary lamns screws etc	430	ITILS.	130.00	38,300.00	23.00	11,250.00
07.05.00	Supplying, fixing, connecting & commissioning 32 Amps SPN Metal clad socket combined with 32Amps DP as control in Manufacturer's mounting box fixed flush with the wall.	5	Nos.	1,100.00	5,500.00	150.00	750.00
07.06.00	Supplying and fixing 6 Amps Switched Socket in Manufacturer's mounting box fixed flush with the wall.	20	N	275.00	0.250.00	40.00	1 200 00
07.07.00	Supplying, laying, connecting & commissioning 3 Runs of 2.5 Sq.mm.PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in already laid PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to Power Points.	30	Nos.	275.00	8,250.00	40.00	1,200.00
	Sciews etc from DB to Fower Forms.	800	Mts.	55.00	44,000.00	10.00	8,000.00
07.00 30	Supplying, laying, connecting & commissioning 3 core 2.5 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) open in ceiling or concealed in wall / ceiling with necessary lamps,						
	screws etc from DB to stage focus light point.	1200	Mts.	68.00	81,600.00	10.00	12,000.00
07.09.00	Supplying, laying, connecting & commissioning 3 core 4 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) GI tray open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	2800	Mts.	85.00	238,000.00	12.00	33,600.00
07.10.00	Supplying, laying, connecting & commissioning 3 core 6 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) GI tray open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	300	Mts.	135.00	40,500.00	15.00	4,500.00
07.11.00	Supplying, fixing, connecting and commissioning of 16 AMPS SPN MENNEKES make schuko model of 2 pin and type plug and socket in Manufacturer's mounting box fixed flush with the wall. For music equipment.(german make)	40	Nos.	1,050.00	42,000.00	125.00	5,000.00
07.12.00	Supplying, fixing, connecting and commissioning of 10- 16 AMPS SPN MENNEKES make 3 pin and type plug and socket in Manufacturer's mounting box fixed flush with the wall. For music equipment (indian model)	200	Nos.	900.00	180,000.00	100.00	20,000.00
07.13.00	Supplying and laying of 25mm. Dia Heavy duty PVC Conduits concealed / open in wall / ceiling etc. with necessary clamps, screws etc. with 1 Run of 16 SWG G.I. Fish wire.		Mtrs	30.00	18,000.00	10.00	6,000.00
07.14.00	Supplying and laying of 32 mm. Dia Heavy duty PVC Conduits concealed / open in wall / ceiling etc. with necessary clamps, screws etc. with 1 Run of 16 SWG G.I. Fish wire.	1200	Mtrs	38.00	45,600.00	12.00	14,400.00
	1						

CTURAL Por Kevin Electricals Pvt. Ltd.

CHENNA

Managing Director

PAGE 8 OF 14

DIRECTOR

07.03.00	Supplying, fixing, connecting & commissioning 20Amps Metal clad socket combined with 20Amps DP MCB as control in Manufacturer's mounting box fixed flush with						
07.02.00	Supplying and fixing 6/16Amps Switched Socket in Manufacturer's mounting box fixed flush with the wall.	25	Nos.	340.00	8,500.00	50.00	1,250.00
07.01.00	Supplying, laying, connecting & commissioning 2 Runs of 4 Sq.mm. with 1 Run of 2.5 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in already laid PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to Power Points.	1500	Mts.	75.00	112,500.00	10.00	15,000.00
07.00.00	RAW /UPS POWER WIRING						
06.04.00	Supplying, laying, connecting & commissioning 4 Runs of 6 Sq.mm. with 2 Runs of 2.5 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps. screws etc.	30	Mtrs.	360.00	10,800.00	60.00	1,800.00
06.03.00	Supplying, laying, connecting & commissioning 4 Runs of 10 Sq.mm. with 2 Runs of 4 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps. screws etc.	30	Mtrs.	425.00	12,750.00	75.00	2,250.00
06.02.00	Supplying, laying, connecting & commissioning 5 Runs of 25 Sq.mm. with 2 Runs of 16 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc.for ups DB.	125	Mtrs.	110.00	13,750.00	150.00	18,750.00
06.01.00	Supplying, laying, connecting & commissioning 4 Runs of 25 Sq.mm. with 2 Runs of 16 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc.for ups input	30	Mtrs.	950.00	28,500.00	125.00	3,750.00
06.00.00	MAINS WIRING						
	4C x 2.5 Sq.mm. Cu.	10	Nos	175.00	1,750.00	60.00	600.00
	3C x 2.5 Sq.mm. Cu.	16	Nos	150.00	2,400.00	50.00	800.00
	4C x 10 Sq.mm. Al.	8	Nos	450.00	3,600.00	100.00	800.00
	4C x 16 Sq.mm. Al.	10	Nos	500.00	5,000.00	100.00	1,000.00
-	3 1/2 x 25 Sq.mm. Al.	8	Nos	500.00	4,000.00	100.00	800.00
	3 1/2 x 35 Sq.mm. Al.	10	Nos	500.00	5,000.00	125.00	1,250.00
	3 1/2 × 50 Sq.mm. Al.	2	Nos	600.00	1,200.00	125.00	250.00
	3 1/2 x 150 Sq.mm. Al.	16	Nos	800.00	12,800.00	150.00	2,400.00

MADRAS ELECTRICAL CONSULTANTS

VELACHERY
CHENNAL 42.

Kevin Electricals Pvt. Ltd.

Managing Director

PAGE 7 OF 14

LEELA SAMSON DIRECTOR

DIRECTOR

JANUANMIYUR, CHENNALA

	Supplying, erecting, connecting & commissioning PVC weather proof type enclosure and with 100 AMPS 4P MCCB with 25 KA rating on an angle Iron frame with necessary interconnections, cable box, brackets, screws, bolts, nuts, etc.	1	Set	8,500.00	8,500.00	400.00	400.00
04.07.00	Supplying, erecting, connecting & commissioning PVC weather proof type enclosure and with 32 AMPS TPN metal clad socket with 4P MCB on an angle Iron frame with necessary interconnections, cable box, brackets, screws holts nuts etc.	10	Set	3,750.00	37,500.00	300.00	3,000.00
05.00.00	CABLES/TERMINATIONS						
	Supplying,laying,connecting & commissioning the following 1.1 KV Grade AYFY/AYWY (or)YWY /YFY Under ground cables with XLPE Insulation with necessary clamps,screws, etc. in the following methods:-						
05.01.00	BURIED UNDERGROUND / LAID IN TRENCH (Inclusive of digging, back filling, bricks sand etc.)						
	3 1/2 x 240 Sq.mm. Al.	100	MTRS.	650.00	65,000.00	200.00	20,000.00
	3 1/2 x 150 Sq.mm. Al.	400	MTRS.	415.00	166,000.00	170.00	68,000.00
	3C x 2.5 Sq.mm. Cu.	400	MTRS.	90.00	36,000.00	120.00	48,000.00
	4C x 2.5 Sq.mm. Cu.	250	MTRS.	110.00	27,500.00	120.00	30,000.00
	4C x 16 Sq.mm. Al.	100	MTRS.	115.00	11,500.00	145.00	14,500.00
05.02.00	CLAMPED ALONG WALL/CEILING NOTE: Supply of Anchor Fastners and necessary 1.5 mm. thick GI Flat, clamps shall be included in the cost.						
	3 1/2 x 185 Sq.mm. Al.	175	MTRS.	525.00	91,875.00	40.00	7,000.00
~	3 1/2 x 150 Sq.mm. Al.	100	MTRS.	415.00	41,500.00	40.00	4,000.00
	3 1/2 x 50 Sq.mm. Al.	100	MTRS.	210.00	21,000.00	35.00	3,500.00
	3 1/2 x 35 Sq.mm. Al.	300	MTRS.	165.00	49,500.00	30.00	9,000.00
	3 1/2 x 25 Sq.mm. Al.	200	MTRS.	130.00	26,000.00	30.00	6,000.00
	4C x 16 Sq.mm. Al.	400	MTRS.	115.00	46,000.00	30.00	12,000.00
	4C x 10 Sq.mm. Al.	100	MTRS.	90.00	9,000.00	25.00	2,500.00
	3C x 2.5 Sq.mm. Cu.	100	MTRS.	90.00	9,000.00	15.00	1,500.00
05.03.00	TERMINATION						
	Supplying,terminating,connecting and commissioning the above Underground cables with Double compression type glands. The cost of earthing gland with copper strips/ wires shall also be included. The cables shall be terminated with Al / copper lugs after crimning.						
	3 1/2 x 240 Sq.mm. Al.	10	Nos	1,000.00	10,000.00	200.00	2,000.00
	3 1/2 x 185 Sq.mm. Al.	2	Nos	850.00	1,700.00	200.00	400.00

MADRAS ELECTRICAL CONSULTANTS

VELACHERY
CHENNAI-42.

Kevin Electricals Pvt. Ltd.

CHENNA

Managing Director

PAGE 6 OF 14

LEELA SAMSON Z DIRECTOR

	Toursey 22 American FLMCB 20mA 1 No						
	Incomer: 32 Amps 4P ELMCB,30mA 1 No.	RO	Sets	7,400.00		700.00	
	Outgoing: 6 - 16 Amps SP MCB 18 Nos.	RO	Sets	7,400.00		700.00	
03.03.00	PDB						30 8 To 2 18 THE WAY TO SHOW THE
	8 Way TPN MCB DB						
	Incomer: 63 Amps 4P ELMCB,30mA 1 No.						
-	Outgoing: 6-16 Amps SP MCB 24 Nos.	2	Sets	8,000.00	16,000.00	700.00	1,400.00
03.04.00	External LDB				2		
	8 Way TPN MCB DB						
	Incomer: 63 Amps 4P ELMCB,100mA 1 No.						
	Outgoing: 6 - 16 Amps SP MCB 24 Nos.	1	Set	8,000.00	8,000.00	700.00	700.00
03.05.00	AHU Vertical DB						
	8 Way TPN VERTICAL MCB DB						
	Incomer: 125 Amps 4P MCCB with 25 Ka Ics with						
	standing capacity 1 No.	ļ					
	Outgoing: 63 Amps TP MCB 1 No.	-		-			
	Outgoing: 32 Amps TP MCB 7 Nos.	1	Set	16,500.00	16,500.00	900.00	900.00
03.06.00	UPS Main Vertical DB						
	8 Way TPN VERTICAL MCB DB						
	Incomer: 63 Amps TP2N MCB 1 No.						
	Outgoing: 10-32 Amps SP MCB 18 Nos	2	Sets	8,500.00	17,000.00	700.00	1,400.00
04.00.00	FSU/ MCCB / STARTERS						
,							
04.01.00	Supplying, erecting, connecting & commissioning 32Amps.4P MCB with DOL Starter for a maximum of						
	5HP 3 PHASE MOTOR with interconnections and suitably mounted on the wall.	10	Sets	4,000.00	40,000.00	250.00	2,500.00
04.()0	Supplying, erecting, connecting & commissioning						
	63Amps 4P MCB on an angle Iron frame with necessary interconnections, cable box, brackets,						
	screws, bolts, nuts, etc.	5	Sets	1,450.00	7,250.00	150.00	750.00
04.03.00	Supplying, erecting, connecting & commissioning 10						
	Amps SP MCB in weather proof enclosure with necessary interconnections, brackets, screws, bolts,			5			
	nuts, etc. for external lighting	7	Sets	650.00	4,550.00	100.00	700.00
04.04.00	Supplying, erecting, connecting & commissioning 63						
	Amps 4P MCB in weather proof enclosure with necessary interconnections, brackets, screws, bolts,			2.750.00	42.750.00	150.00	750.00
	nuts. etc. for Ac control		Sets	2,750.00	13,750.00	150.00	750.00
04.05.00	Supplying, erecting, connecting & commissioning 32 Amps 4P MCB on an angle Iron frame with necessary						
_	interconnections, cable box, brackets, screws, bolts,						600.00

in fari

TUR For Kevin Electricals Pvt. Ltd.

Managing Director

PAGE 5 OF 14

LEELA SAMSON DIRECTOR

	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional						20
	meter (0 - 200 & 315 A) with Inbuilt Selector Switch.						
	iii) RYB LED Cluster type Indicating Lamps and			-			
	Control fuses shall be provided.	1		265,000.00	265,000.00	5,000.00	5,000.00
02.04.00	AC PANEL (OUTDOOR TYPE)						
-	CABLE ENTRY: BOTTOM						
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated AC PANEL (outdoor type). The Board shall be incorporated with the following:-						
	INCOMER: 250 AMPS 4P MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.						
	OUTGOING: 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relavs2 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relavs3 Nos. 32 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relavs5 Nos.						
	BUSBAR : ALUMINIUM					307	
	RATING: 250 AMPS						
	The Phase Bus bar shall be 40 x 10 mm. and the Neutral bar shall be 25 x 6 mm. The Earth Bus bar shall be 2 Runs of 25 x 3 mm.						
	There shall be ONE set of Metering Compartment incorporated with the following:-						- 15
,	i) CTs of ratio 250 /5A and Class 0.5 for metering and burden 10 VA.						
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 250 A) with Inbuilt Selector Switch.						
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.	1		138,000.00	138,000.00	4,000.00	4,000.00
03.00.00	MCB DBs						
	Supplying, fixing, connecting & commisioning the following MCB DISTRIBUTION BOARDS fixed flush with the wall. All DBs shall have Double door. Lighting and Power DB - C curve and UPS DB - D curve				LALAKS	EEL SAMS	DAFFO
03.01.00	LDB				(the		anson
	8 Way TPN MCB DB				TOVAN	MIYUR, CHE	NAIM
	Incomer: 63 Amps 4P ELMCB,30mA 1 No.						
	Outgoing: 6-16 Amps SP MCB 24 Nos.	2	Sets	8,000.00	16,000.00	700.00	1,400.00

MADRAS ELECTRICAL CONSULTANTS

VELACHERY
CHENNAI-42.

CTUR For Kevin Electricals Pvt. Ltd.

PAGE 4 OF 14

100 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable/Fixed rerload and Fixed short circuit relavs3 Nos. USBAR: ALUMINIUM ATING: 250 AMPS The Phase Bus bar shall be 40 x 10 mm. and the				,		
USBAR: ALUMINIUM ATING: 250 AMPS						
JSBAR : ALUMINIUM ATING : 250 AMPS						
ATING: 250 AMPS						
ne Phase Bus bar shall be 40 x 10 mm, and the						
eutral bar shall be 25 x 6 mm. The Earth Bus bar all be 2 Runs of 25 x 3 mm.						
nere shall be TWO set of Metering Compartment corporated with the following:-						
CTs of ratio 200/5A and Class 0.5 for etering and burden 10 VA.	,					
1 No. Class 0.5, 96 Sq.mm. Digital multifuntional eter (0 - 200 A) with Inbuilt Selector Switch.				5		
RYB LED Cluster type Indicating Lamps and entrol fuses shall be provided.	1		230,000.00	230,000.00	5,000.00	5,000.00
G PANEL						
ABLE ENTRY : TOP / BOTTOM						
opplying, Erecting, Testing & commissioning FLOOR DUNTED CUBICLE TYPE 14 SWG thick CRCA sheet mpartmentalised modular type with powder coated G PANEL. The Board shall be incorporated with e following:-						
G INCOMER 1 : 250 AMPS 4P motorized MCCB th 25 KA Withstanding Capacity Adjustable overload d short circuit relays 1 No.						
G INCOMER 2: 315 AMPS 4P motorized MCCB th 25 KA Withstanding Capacity Adjustable overload d short circuit relavs 1 No.						
JS COUPLER: 315 AMPS 4P MCCB th 25 KA Withstanding Capacity Adjustable overload d short circuit relavs 1 No.						
te: All the incomer and Buscoupler are electrical and echanical interlock with auto/manual selector switch.						
JTGOING: 250 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable overload d short circuit relavs4 Nos.					THETRA FO	AA.
SBAR : ALUMINIUM				ALAK	1	TOAT
TING: 315 AMPS					THE W	201
e Phase Bus bar shall be 50×10 mm. and the utral bar shall be 25×06 mm. The Earth Bus bar all be 2 Runs of 25×6 mm.				OVA	NMIYUR, CH	NNA
ere shall be TWO set of Metering Compartment corporated with the following:-			MECT	BALA		
CTs of ratio 250 & 315 /5A and Class 0.5 for etering and burden 10 VA.			12 M			
e e o i G to	CTS of ratio 200 /5A and Class 0.5 for etering and burden 10 VA. 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional eter (0 - 200 A) with Inbuilt Selector Switch. RYB LED Cluster type Indicating Lamps and introl fuses shall be provided. BLE ENTRY: TOP / BOTTOM PPIVING, Erecting, Testing & commissioning FLOOR DUNTED CUBICLE TYPE 14 SWG thick CRCA sheet in partmentalised modular type with powder coated in PANEL. The Board shall be incorporated with perfollowing: INCOMER 1: 250 AMPS 4P motorized MCCB in 25 KA Withstanding Capacity Adjustable overloaded dishort circuit relavs 1 No. INCOMER 2: 315 AMPS 4P motorized MCCB in 25 KA Withstanding Capacity Adjustable overloaded short circuit relavs 1 No. SCOUPLER: 315 AMPS 4P MCCB in 25 KA Withstanding Capacity Adjustable overloaded short circuit relavs 1 No. SCOUPLER: 315 AMPS 4P MCCB in 25 KA Withstanding Capacity Adjustable overloaded short circuit relavs 1 No. SCOUPLER: 315 AMPS 4P MCCB in 25 KA Withstanding Capacity Adjustable overloaded short circuit relavs 1 No. SCOUPLER: 315 AMPS 4P MCCB with auto/manual selector switch. SCOUPLER: 315 AMPS 4P MCCB with Scoupler are electrical and chanical interlock with auto/manual selector switch. SCOUPLER: 315 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable overloaded short circuit relavs 4 Nos. SEBAR: ALUMINIUM TING: 315 AMPS Phase Bus bar shall be 50 x 10 mm. and the putral bar shall be 25 x 06 mm. The Earth Bus bar all be 2 Runs of 25 x 6 mm. Per shall be TWO set of Metering Compartment or porated with the following: CTS of ratio 250 & 315 /5A and Class 0.5 for	CTS of ratio 200 /5A and Class 0.5 for electring and burden 10 VA. 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional electr (0 - 200 A) with Inbuilt Selector Switch. RYB LED Cluster type Indicating Lamps and introl fuses shall be provided. 1 PANEL BLE ENTRY: TOP / BOTTOM PPIVING, Frecting, Testing & commissioning FLOOR DUNTED CUBICLE TYPE 14 SWG thick CRCA sheet in PANEL. The Board shall be incorporated with electrophysical electrophysic	CTS of ratio 200 /5A and Class 0.5 for elering and burden 10 VA. 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional electr (0 - 200 A) with Inbuilt Selector Switch. RYB LED Cluster type Indicating Lamps and introl fuses shall be provided. 1 DEBLE ENTRY: TOP / BOTTOM BIBLE ENTRY: TOP / BOTTOM Polying, Erecting, Testing & commissioning FLOOR BUNTED CUBICLE TYPE 14 SWG thick CRCA sheet inpartmentalised modular type with powder coated in PANEL. The Board shall be incorporated with a following: INCOMER 1: 250 AMPS 4P motorized MCCB that 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. INCOMER 2: 315 AMPS 4P motorized MCCB that 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. SCOUPLER: 315 AMPS 4P MCCB that 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. SCOUPLER: 315 AMPS 4P MCCB that 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. SCOUPLER: 315 AMPS 4P MCCB that 35 AMPS 4P MCCB that 36 AMPS 4P MCCB with 48 AMPS	CTs of ratio 200 /5A and Class 0.5 for etering and burden 10 VA. 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional eter (0 - 200 A) with Inbuilt Selector Switch. RYB LED Cluster type Indicating Lamps and not for fuses shall be provided. 1 230,000.00 1 PANEL BLE ENTRY: TOP / BOTTOM Poplying, Erecting, Testing & commissioning FLOOR pulying, Erecting, Testing & commissioning FLOOR pulying, Erecting, Testing & commissioning FLOOR pulying the Entry 1: 4 SWG thick CRCA sheet inpartmentalised modular type with powder coated in PANEL. The Board shall be incorporated with infollowing: 1 NOOMER 1: 250 AMPS 4P motorized MCCB the 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. 1 NOOMER 2: 315 AMPS 4P motorized MCCB the 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. 1 SCOUPLER: 315 AMPS 4P MCCB the 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. 1 SCOUPLER: 315 AMPS 4P MCCB the 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. 1 SCOUPLER: 315 AMPS 4P MCCB the circuit relavs 1 No. 1 SCOUPLER: 315 AMPS 4P MCCB the circuit relavs 1 No. 1 SCOUPLER: 315 AMPS 4P MCCB the circuit relavs 4 No. 1 SCOUPLER: 315 AMPS 4P MCCB with KA (Ics) Withstanding Capacity Adjustable overload dishort circuit relavs 4 Nos. 1 SSAR: ALUMINIUM 2 SSAR: ALUMINIUM 3 SSAR: ALUMINIUM 3 SSAR: ALUMINIUM 3 SSAR: ALUMINIUM 4 SSAR: ALUMINIUM 5 SSAR: ALUMIN	CTs of ratio 200 /SA and Class 0.5 for eterina and burden 10 VA. I No. Class 0.5, 96 Sq.mm. Digital multifuntional ter (0 - 200 A) with Inbulit Selector Switch. RYB LED Cluster type Indicating Lamps and ntrol fuses shall be provided. I PANEL BLE ETRY: TOP / BOTTOM Diplying, Erecting, Testing & commissioning FLOOR DIVITED CUBICLE TYPE 14 SWG thick CRCA sheet enpartmentalised modular type with powder coated PANEL. The Board shall be incorporated with following: INCOMER 1: 250 AMPS 4P motorized MCCB the 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. INCOMER 2: 315 AMPS 4P motorized MCCB the 25 KA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. SCOUPLER: 315 AMPS 4P MCCB the SKA Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. SCOUPLER: 315 AMPS 4P MCCB the incorporated with circuit relavs 1 No. THE ALL HIS TORDING CAPACITY ADJUSTABLE OVER THE ALL HIS TORD	CTs of ratio 200 /5A and Class 0.5 for teterina and burden 10 VA. 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional ster (0 - 200 A) with Inbuilt Selector Switch. RYB LED Cluster type Indicating Lamps and ntrol fuses shall be provided. 1 PANEL BLE ENTRY: TOP / BOTTOM PUNITED CUBICLE TYPE 14 SWG thick CRCA sheet mpartmentalised modular type with powder coated in Panel. The Board shall be incorporated with infollowing: 1 INCOMER 1: 250 AMPS 4P motorized MCCB thick St. St. All Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. 1 INCOMER 2: 315 AMPS 4P motorized MCCB thick St. All Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. 1 SCOUPLER: 315 AMPS 4P MCCB thick CRCA sheet with a standard capacity Adjustable overload dishort circuit relavs 1 No. 1 SCOUPLER: 315 AMPS 4P MCCB thick CRCA sheet with a standard capacity Adjustable overload dishort circuit relavs 1 No. 1 SCOUPLER: 315 AMPS 4P MCCB thick CRCA sheet with auto/manual selector switch. 1 STORING: 250 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable overload dishort circuit relavs 1 No. 1 SCOUPLER: 315 AMPS 4P MCCB with KA (Ics) Withstanding Capacity Adjustable overload dishort circuit relavs 4 No. 1 SCOUPLER: 315 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable overload dishort circuit relavs 4 No. 1 SCOUPLER: 315 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable overload dishort circuit relavs 4 No. 1 SCOUPLER: 315 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable overload dishort circuit relavs 4 No. 1 SCOUPLER: 315 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable overload dishort circuit relavs 4 No. 1 SCOUPLER: 315 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable overload dishort circuit relavs 4 No. 1 SCOUPLER: 315 AMPS TPN MCCB with KA (Ics) Withstanding Capacity Adjustable overload dishort circuit relavs 4 No. 1 SCOUPLER: 315 AMPS TPN MCCB with KA (Ics) Withstanding Capacity

MADRAS ELECTRICAL CONSULTANTS

(VELACHERY CHENNAI 42.)

For Kevin Electricals Pvt. Ltd.

PAGE 3 OF 14

	,						
	CABLE ENTRY: TOP / BOTTOM						
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated						
	MAIN PANEL -1. The Board shall be incorporated with the following:-	·				-	
	EB & DG INCOMER : 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos.			·			
	OUTGOING: 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relavs1 No. 100 AMPS TPN MCCB with						
	25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays1 No. 63 AMPS TPN MCCB with						
	25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relavs3 Nos. 32 AMPS TPN MCCB with						
	25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relavs4 Nos.						
	BUSBAR : ALUMINIUM						
	DATING - 250 AMPC						
	RATING: 250 AMPS						
	The Phase Bus bar shall be 40×10 mm. and the Neutral bar shall be 25×6 mm. The Earth Bus bar shall be 2 Runs of 25×3 mm.						
	There shall be TWO set of Metering Compartment incorporated with the following:-						
	i) CTs of ratio 200 /5A and Class 0.5 for metering and burden 10 VA.						
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch.						
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.	1	Set	216,000.00	216,000.00	5,000.00	5,000.00
.02.00	MAIN PANEL - 2						
	CONTRACTOR / POTTOM						
	CABLE ENTRY : TOP / BOTTOM						
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated MAIN PANEL -2. The Board shall be incorporated with the following:-				JUAN	LEEDA SAMS	Now Sou
	EB & DG INCOMER : 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos.			61	URAL	ANMIYUR, CH	ENNALA
	OUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relavs1 No. 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relavs3 Nos.			CHI CHI	NNA A	,	

For Kevin Electricals Pvt. Ltd.

PAGE 2 OF 14

01.09.2010 BILL OF QUANTITIES / SCHEDULE OF WORKS FOR ELECTRICAL INSTALLATION TO BE CARRIED OUT FOR PROPOSED FOR M/S. KALAKSHETRA AT CHENNAI SUPPLY ITEM NO DESCRIPTION **ERECTION** QTY. **AMOUNT** RATE AMOUNT RATE RS. RS. RS. RS. 01.00.00 METER BOARD /ACCESSORIES 01.01.00 CT METER BOARD Supplying, erecting, connecting & commissioning a floor mounting Angle Iron all metal Meter Board with the following:-3Nos. 300Amps. TP cutouts & 1No. 300 Amps neutral link fixed on a MS Sheet mounted on angle iron Space for fixing 1 No.CT operated Meter on sheet steel / angle iron frame. 1 No. 200 Amps Triple Pole and neutral front operated Fuse Switch Unit of AC 23 utilisation category . 1 Set of interconnection between Meter and cutout shall be made with solid copper conductor. This shall also be made between Fuse Switch Units and Meter. Supplying and fixing 3 Nos 200/5 A CT as required by 2,000.00 2 Sets 29,500.00 59,000.00 1,000.00 EB on copper bus bars. Note: Before manfacturing the metering panel get approval from TNFB. 01.01.00 METER BOARD Supplying, erecting, connecting & commissioning a floor mounting Angle Iron all metal Meter Board with the followina:-3Nos. 300Amps. TP cutouts & 1No. 300 Amps neutral link fixed on a MS Sheet mounted on angle iron frames. Space for fixing 1 Nos. 100 Amps Meter on sheet steel / angle iron frame. 1 No. 125 Amps TP cutout and neutral link fixed on a MS sheet. 1 No. 125 Amps Triple Pole and neutral front operated Fuse Switch Unit of AC 23 utilisation category . 1 Set of interconnection between Meter and cutout shall be made with solid copper conductor. This shall 1,000.00 RO 22,500.00 also be made between Fuse Switch Units and Meter. Note: Before manfacturing the metering panel get approval from TNEB. 02.00.00 LT PANEL 02.01.00 MAIN PANEL - 1

MADRAS ELECTRICAL CONSULTANTS

For Kevin Electricals Pvt. Ltd.

PAGE 1 OF 14



Kevin Electricals Pvt. Ltd., ob

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020.

REF: KE/TA/100/2010/402

The Director, M/s. Kalakshetra Foundations, Chennai.

14/9/10.

02.09.2010

Dear Sir,

SUB: - Electrical Installation to be carried out for M/s. Kalakshetra at Chennai -Submission of offer - Reg.

REF: - Your Mail Dt.01.09.2010

We thank you very much for your kind enquiry and we are pleased to submit our competitive offer for the above project.

Taxes & Duties: - Our offer is inclusive of all taxes & duties etc.

<u>Validity</u>: - Our offer is valid for the period of 30 days from the date of this letter.

Guarantee: - The supplied materials and workmanship are guaranteed for the Period of 6 Months from the date of completion of work.

Completion Period: - The entire work will be completed within stipulated period from the date of receipt of the work order.

Payment: - We request you to kindly arrange to make the payment as follows:

Ø 30% as an advance along with your valuable order.

Ø 60% against supply of materials at site.

Ø 10% after completion of work

We hope that we have given best competitive offer and expecting your valuable order.

Thanking you,

Your's faithfully,

for Kevin Electricals Pvt Ltd,

L.Wilson Susai Raj (Managing Director)

Encl:

2010. for Rs. 50,000

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

Please note that deduction towards, income tax, VAT as applicable and 5% retention amount of bill value, which will be refunded after liability period one year subject to the performance of the work.

Kindly provide your company PAN, TIN and service tax Nos in writing, for remitting the tax deductions amount to the concerned departments

Please note that any non-tendered items for the work should be allowed after going through the rate analysis and approval of Consulting Architect Sri.Ravi Niilakantan and approval of works committee.

During the period of execution of work, if the work of the contractor is found to be not satisfactory and specification / details or if there is considerable delay in progress, the contract is liable to be terminated without notice and also without assigning any reason.

The receipt of this letter may please be acknowledged for having agreed for the terms and returned.

Before commencing the work, a formal agreement may be entered, incorporating the terms and conditions given in the tender schedule.

Thanking you,

Yours faithfully,

Leela Samson DIRECTOR.

Copy to

M/s.CARD Sri.Ravi Nilakantan Consulting Architect.

Draft for apportal please,

2

3.15110

CAO

Olal 1/10
DIRECTOR 1/10

C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\ Electricl installation work.doc

September 28, 2010

M/s.Kevin Electricals Pvt Ltd, Engineers and Government Licensed A grade Contractors, No.7, (Old No. 1- B) Arunachalapuam, IInd Street, Adyar, Chennai 600 020.

Sir/s,

Sub: Koothambalam – Electrical Installation work in Kalakshetra Foundation – Award of work – Reg.

Ref: i) Your tender dated 14.04.2010
ii)Revised tender offer letter dated 17.09.2010.

Based on recommendation of works committee, The Director, Kalakshetra Foundation is pleased to accept in principle award the work of Electrical Installation work at Koothambalam in Kalakshetra Foundation to you at a total cost of Rs. 49,08,773.27/-(Rupees Forty Nine lakh eight thousand seven hundred seventy three and paise twenty seven only) agreed item rate contract with the specifications and as per the description of work enclosed herewith. This amount is included of VAT, Income tax and Service tax. This is a firm price and No escalation will be accepted on any account, where any particular work is decided to be withdrawn from the contract by us, there the contract value will also get reduced correspondingly.

The work may be executed in consultation with Architect Sri. Ravi Niilakantan and his associates (Electrical consultant). The work should be executed by you under the supervision of a competent site Engineer /Technical persons as per the terms and conditions given by the consultant Architect

Time is the essence of the contract and the work should be completed in all respects on or before 30th November 2010 in all respects as per the schedule of completion given in the bid documents. Any delay in the completion of the work beyond prescribed date will result in levy of liquidated damages or penalty clause will be applied as per the agreement terms. No extension of time will be considered.

The claim and payment will be admitted on completion of work as per the actual execution of work, based on the measurement recorded/entered and checked, and certification by the consultant Architect.Sri.Ravi Niilakantan and his associates.

As per the terms, the upto 15 y.
Mobil is sation advance, will be paid against submission of equivalent value
Of Bankquarantee . Ofter configuration Consulting Architect. The same
amount will be deducted on PRO-RATA basis of bill value submitment.





Works kalakshetra <works@kalakshetra.in>

Electrical installation work - award of letter - reg.

Works kalakshetra <works@kalakshetra.in> To: ravi <card@vsnl.com>

Fri, Oct 1, 2010 at 4:00 PM

Sir,

The award of work for the electrical installation work for the Koothambalam is ready. By the by the M/s.Kevin electricals was contacted over the phone and wanted to send the work order by post. Accordingly, the award of contract is being despatched to M/s. Kevin Electricals pvt ltd, and copy to M/s.CARD and M/s.Madras electrical consultants.

For information please.

warm regards

V.srinivasan kalakshetra



The claim and payment will be admitted on completion of work as per the actual execution of work, based on the measurement recorded/entered and checked, and certification by the consultant Architect.Sri.Ravi Niilakantan and his associates (Electrical consultant).

Please note that deduction towards, income tax, VAT as applicable and 5% retention amount of bill value, which will be refunded after liability period one year subject to the performance of the work.

Kindly provide your company PAN, TIN and service tax Nos in writing, for remitting the tax deductions amount to the concerned departments

Please note that any Non-tendered items for the work should be allowed after going through the rate analysis and approval of Consulting Architect Sri.Ravi Niilakantan and approval of works committee.

During the period of execution of work, if the work of the contractor is found to be not satisfactory and specification / details or if there is considerable delay in progress, the contract is liable to be terminated without notice and also without assigning any reason.

The receipt of this letter may please be acknowledged for having agreed for the terms and returned.

Before commencing the work, a formal agreement may be entered, incorporating the terms and conditions given in the tender schedule.

Thanking you,

Yours faithfully,

Leela Samson DIRECTOR.

Copy to

M/s.CARD Sri.Ravi Nilakantan Consulting Architect.

M/s.Madras Electrical Consultants, No.6, Park Avenue 1st cross street, Velachery, Chennai 600 042. Sean South Reported South Reported South Liver Cleaning Part 140

(97)

0/1

C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\	September 28,
Electricl installation work.doc	2010

M/s.Kevin Electricals Pvt Ltd, Engineers and Government Licensed A grade Contractors, No.7, (Old No. 1- B) Arunachalapuam, IInd Street, Adyar, Chennai 600 020.

Sir/s,

Sub: Koothambalam – Electrical Installation work in Kalakshetra Foundation – Award of work – Reg.


Ref: i) Your Tender No. KF/TA/100/2010/402 dated 02.09.2010 ii)Revised tender offer letter dated 17.09.2010.


Based on recommendation of works committee, The Director, Kalakshetra Foundation is pleased to accept in principle award the work of Electrical Installation work at Koothambalam in Kalakshetra Foundation to you at a total cost of Rs. 49,08,773.27/-(Rupees Forty Nine lakh eight thousand seven hundred seventy three and paise twenty seven only) agreed item rate contract with the specifications and as per the description of work enclosed herewith. This amount is included of VAT, Income tax, and Service tax. This is a firm price and No escalation will be accepted on any account, where any particular work is decided to be withdrawn from the contract by us, there the contract value will also get reduced correspondingly.

The work may be executed in consultation with Architect Sri. Ravi Niilakantan and his associates (Electrical consultant). The work should be executed by you under the supervision of a competent site Engineer /Technical persons as per the terms and conditions given by the consultant Architect

Time is the essence of the contract and the work should be completed in all respects on or before 30th November 2010 in all respects as per the schedule of completion given in the bid documents. Any delay in the completion of the work beyond prescribed date will result in levy of liquidated damages or penalty clause will be applied as per the agreement terms. No extension of time will be considered.

As per terms, the mobilization advance up to 15% of the total value of work awarded will be paid against producing the equivalent value of Bank guarantee after certifying the consulting Architect. The deduction of the mobilization advance will be made on PRO-RATA basis of the bills value submitted for payment.





CENTRE FOR ARCHITECTURAL RESEARCH & DESIGN

ARCHITECTURE O LANDSCAPE O INTERIORS

04th October 2010.

To Smt.Leela Samson, Director. Kalakshetra foundation, Chennai -6000041.

Dear Smt Leela Samson, Please find three sets of drawings listed below for construction. Two sets may be handed over to M/s. Kevin electricals

Sub: Sheet No. 1 2.	"Koothambalam" Sheet Name Diagram Main schematic electrical drawing Sound equipment and Stage lighting, Cable tray at FF Lvl.	Issued date 04.10.'10 04.10.'10	Count 3Sets. 3Sets.
		Reco	and 6 days.
Thanking you, With best regard	ards,	A woom	7/2010

Encl. As above.

The claim and payment will be admitted on completion of work as per the actual execution of work, based on the measurement recorded/entered and checked, and certification by the consultant Architect.Sri.Ravi Niilakantan and his associates (Electrical consultant).

Please note that deduction towards, income tax, VAT as applicable and 5% retention amount of bill value, which will be refunded after liability period one year subject to the performance of the work.

Kindly provide your company PAN, TIN and service tax Nos in writing, for remitting the tax deductions amount to the concerned departments

Please note that any Non-tendered items for the work should be allowed after going through the rate analysis and approval of Consulting Architect Sri.Ravi Niilakantan and approval of works committee.

During the period of execution of work, if the work of the contractor is found to be not satisfactory and specification / details or if there is considerable delay in progress, the contract is liable to be terminated without notice and also without assigning any reason.

The receipt of this letter may please be acknowledged for having agreed for the terms and returned.

Before commencing the work, a formal agreement may be entered, incorporating the terms and conditions given in the tender schedule.

Thanking you,

Yours faithfully,

Leela Samson

DIRECTOR.

Copy to

M/s.CARD Sri.Ravi Nilakantan Consulting Architect.

M/s.Madras Electrical Consultants, No.6, Park Avenue 1st cross street, Velachery, Chennai 600 042.

Accepted

For KEVIN ELECTRICALS PVT. LTD.,

Managing-Director

(10)



			_
	C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\	September 28,	
1	Electricl installation work.doc	2010	

M/s.Kevin Electricals Pvt Ltd, Engineers and Government Licensed A grade Contractors, No.7, (Old No. 1- B) Arunachalapuam, IInd Street, Adyar, Chennai 600 020.

Sir/s,

Sub: Koothambalam – Electrical Installation work in Kalakshetra Foundation – Award of work – Reg.

Ref: i) Your Tender No. KF/TA/100/2010/402 dated 02.09.2010 ii)Revised tender offer letter dated 17.09.2010.

Based on recommendation of works committee, The Director, Kalakshetra Foundation is pleased to accept in principle award the work of Electrical Installation work at Koothambalam in Kalakshetra Foundation to you at a total cost of Rs. 49,08,773.27/-(Rupees Forty Nine lakh eight thousand seven hundred seventy three and paise twenty seven only) agreed item rate contract with the specifications and as per the description of work enclosed herewith. This amount is included of VAT, Income tax, and Service tax. This is a firm price and No escalation will be accepted on any account, where any particular work is decided to be withdrawn from the contract by us, there the contract value will also get reduced correspondingly.

The work may be executed in consultation with Architect Sri. Ravi Niilakantan and his associates (Electrical consultant). The work should be executed by you under the supervision of a competent site Engineer /Technical persons as per the terms and conditions given by the consultant Architect

Time is the essence of the contract and the work should be completed in all respects on or before 30th November 2010 in all respects as per the schedule of completion given in the bid documents. Any delay in the completion of the work beyond prescribed date will result in levy of liquidated damages or penalty clause will be applied as per the agreement terms. No extension of time will be considered.

As per terms, the mobilization advance up to 15% of the total value of work awarded will be paid against producing the equivalent value of Bank guarantee after certifying the consulting Architect. The deduction of the mobilization advance will be made on PRO-RATA basis of the bills value submitted for payment.

For KEVIN ELECTRICALS PVT. LTD.,

Managing Drector

Founder: Smt. Rukmini Devi Chairman: Justice Sri S. Mohan

Director and Secretary: Ms. Leela Samson

- 66

Ba



Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors

12 10 10 10 10 10 10 10 05

05.10.2010

REF: KE/KF/644/2010/483

To

The Director, Kalashetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation work for M/s. Kalashetra Foundation at Chennai - Work order Acceptance - Reg.

REF: - Your Order Dt.28.09.2010

We hereby accepted and acknowledged the above work order and thank you very much for the same.

Thanking you,

Yours faithfully, for Kevin Electricals Pvt Ltd,

L.Wilson Susai Raj (Managing Director)

105

Branch Office:


Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in





Engineers and Government Licenced 'A' Grade Contractors
No. 7, (O. No. 1-B) Arunachalapuram, lind Street, Adyar,
Chennai. 600 020. ©: 24466938, 24468401. Fax: 24912704
E-mail: kevinelectrical@yahoo.co.in

The Director, Kalashedore Franklion, Thim vanioniy co,

Chennai boo off.



Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors

0)/2/10

REF: KE/KF/644/2010/502

09.10.2010

To

The Director, Kalashetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation to be carried out for M/s. Kalashetra at Chennai - Authorization - Reg.

REF: - Order Dt.28.09.2010

We hereby authorized Mr.P.Saravana Kumar who is our Site Engineer to attend the project on behalf of our company.

His specimen signature is affixed herewith.

Thanking you,

Yours faithfully,

For Kevin Electricals Pvt Ltd,

L.Wilson Susai Raj (Managing Director) Specimen Signature

P. Saravana Kumar

(105)

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank) Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

प्रेषक डाकघर की नाम मोहर Name stamp of office of posting

(ALAKSHETRA FOUNDATION Date-Stamp Hजने वाले का पता Sender's Address

(पन/PIN MGIPCBE—DTP—53 PSD/CBE/08—26-9-08/10,00,000 Pads.

* एक पत्र/पोस्टकाड/पेकट/पासल प्राप्त हुआ

* Received a Registered Insured Ins

The real section of the section of t



U7



Works kalakshetra <works@kalakshetra.in>

Electrical installation work koothambalam - reg.

Works kalakshetra <works@kalakshetra.in>

Tue, Oct 19, 2010 at 4:56 PM

To: ravi <card@vsnl.com>

Sir,

The work order for the above, was issued to the contractor.

The entering into agreement for the work has not been made sofar. I have been asking them to enter into agreement format available in the tender schedule.

is there any provision in this contract for security deposit to be made with the Kalakshetra Foundation as same as followed by the civil contract work.

Kindly asked them to do the needful at the earliest please.

warm regards

V.Srinivasan kalakshetra







Works kalakshetra <works@kalakshetra.in>

Electrical installation work - Agreement - reg.

Works kalakshetra <works@kalakshetra.in>

Tue, Oct 26, 2010 at 11:43 AM

To: "j.ra.jayakumar jayaramanradhabai" <jrajayakumar27@gmail.com>

Dear J.Ra.J.

Please refer earlier email dated oct 19, 2010, the entering the agreement into the foundation has not been done sofar by the contractor M/s.Kevin electricals

You sent the email that you have discussed but No response sofar.

Kindly remain and excute the agreement at the earliest please.

Kalakshetra



प्रथक डाकघर की नाम मोहर
Name stamp of office of posting

Wish airch
का पता
Sender's
Address

GALAKSHETRA FOUNDATION
Date-Stamp
THIRUVANMIYUR,
CHENNAI-600 04

GHAPPIN

MGIPCBF—DTP—53 PSD/CBE/08—26-9-08/10,00,000 Pads

*Received a Registered Insured Letter/Postcard/Packet/Parcel M/S. Madras Llectrical Consultants,

Unit aim an intermed No.6, Park Avenue 1st Cross Street,

Addressed to (Name) Velacherry, Chennai-600 042.

+Insured for Rupees

श्रितरण की तारीख/Date of delivery

- अनावश्यक को काट दिया जाए।
- * Score out the matter not required.
- † केवल बीमा वस्तुओं के लिए।
- + For Insured articles only.

(8)

पाने वाले के देखा अ Signature of addressee

3

ouii	dations at Chennai.	/s.Kalashetra	
S.No	/ Item	Total Length in Mtrs.	Qty
I	Ground Floor		
1	12 Core Balanced Audio Cable	270	
2	8 Core Blanced Audio Cable	120	
3	6 Sq. mm. Speaker Cable	260	
4	1 Core Blanced Audio Cable	400	
5	4 Sq. mm Speaker Cable	430	
6	Binary 434 DMX512	210	
	Ground Floor	1690	1690
II	First Floor		
1	12 Core Balanced Audio Cable		
2	8 Core Blanced Audio Cable		
3	6 Sq. mm. Speaker Cable		
4	1 Core Blanced Audio Cable	110	
5	4 Sq. mm Speaker Cable	380	1
6	Binary 434 DMX512	15	
	First Floor	505	50
I	Ground Floor - Qty	1690	
II	First Floor - Qty	505	



121



Works kalakshetra <works@kalakshetra.in>

1744 - NRN - 13 - Kalakshetra - Audio Cable Running Meters

M S Ramesh <msramesh@mec-india.com>

Sat, Oct 30, 2010 at 11:42 AM

To: works@kalakshetra.in Cc: mecramesh@eth.net

Dear Sir,

I am attaching the Audio Cable Running Meters for Ground Floor & First Floor for your reference.

Regards,

N.R.Nagarajan

Madras Electrical Consultants, #6 First Cross Street, Velachery, Chennai 600 042. Phone (044) 2972 8201 / 03,Mobile: 99414 91263,Email: nrnagarajan@mec-india.com;mecramesh@eth.net

Audio Cable Running Meters.xls



- 4. The event of their ceasing to be the Architect for the purpose of this contract, such other person as shall be nominated by the Owner not being a person to whom the contractor shall object for reasons considered to be sufficient by the Owner mentioned in the said conditions provided always that no person subsequently appointed to be Architect under this contract shall be entitled to disregard or overrule any previous decision or approval or direction given or expressed by the Architect and confirmed by Owner for the time being.
- 5. The Owner through the Architect reserves to him the right of altering the drawings, the nature of the work or having portions of the same carried out by the Owner or otherwise and such alteration, variations shall be carried out without prejudice to this contract.
- 6. The said contract comprises the work above mentioned and all subsidiary works connected therewith within the same site as may be ordered to be done from time to time by the said Architect even through such works may not be shown on the drawings or described in the said specifications or the Priced Schedule of Quantities.
- 7. The said conditions and Appendix thereto shall be read and construed as forming part of this Agreement, and the parties hereto shall respectively abide by, submit themselves to the conditions and perform the agreements on their part respectively in such conditions.

We have seen all the terms and conditions as well as the specifications for the work and agreed to abide by them.

As witness our hand this 1st day of November 2010.

OWNER

FOR KEVIN ELECTRICALS I

CONTRACTOR

(In The Presence of)

(In The Presence of)

signed on or behalf of at the rates therein set forth amounting to the sum of Rs.49,08,773.27/- (Rupees Forty Nine Lakhs Eight Thousand Seven Hundred and Seventy Three Only) (hereinafter referred to as the said "Contract Amount") Inclusive of all taxes but excluding service tax.

AND WHEREAS the Owner accepted of the contractor for the above mentioned work and conveyed vide letter No. C: \ 2009-2010 \ V.Admin \ 2.Engineering \ i.Plan \ Koothambakkam \ Electrical installation work.doc Dt.28.09.2010 at the rates stated in the Schedule of Quantities for the work and accepted by the Owner upon the terms and subject to the conditions of the contract.

AND WHEREAS the Contractor has deposited with the Owner the sum of Rs.50,000/-(Rupees Fifty Thousand Only) as interest-free security deposit to be retained until the expiry of the Defects Liability Period for the due observance and performance of the contract.

NOW IT IS HEREBY AGREED AS FOLLOWS:

- 1. In consideration of the payment to be made to the contractor for the work to be executed by him as referred in clause XV of the tender documents, the contractor hereby covenant with the owner that the Contractor shall and will duly provide, execute, complete and maintain the said work and shall do and perform all other acts and things in the Contract mentioned or described or which are to be implied there from or may be reasonable necessary for the completion of the said works and at the said lines and in the manner and subject to the terms and conditions or stipulations mentioned in the contract.
- 2. In consideration of the due provision execution, completion and maintenance of the said work the Owner does hereby agree with the contractor that the Owner will pay to contractor the respective amounts for the work actually done by him and approved by the Owner at the Schedule of Rate and such other sum payable to the contractor under provision of Contract, such payment to be made at such time in such manner (as prescribed for in the contract).
- 3. It is specifically and distinctly understood and agreed between the Owner and the Contractor that the Contractor shall have no right, title or interest in the site made available by the Owner for execution of the works or in the building structure or works executed on the said site by the Contractor or in the goods, articles, materials etc. brought on the said site (unless the same specifically belongs to the Contractor) and the Contractor shall not have or deemed to have any lien whatsoever change for unpaid bills will not be entitled to assume or retain possession or control of the site or structures and the Owner shall have an absolute and unfettered right to take full possession of site and to remove the Contractor, their servants, agents and materials belonging to the Contractor and lying on the site.

nan

FOR KEVIN ELECTRICALS PVT. LTD.,

Managing Director

AL DELA SAMSON
LEELA SAMSON
LEELA SAMSON
LEELA SAMSON
LEELA SAMSON

(114)





Name (CN) 1 Electricals Child

S.P. VASANTHA
STAMP VENDOR
L.No. C4/22702/81 dt. 27-1-82
15. Røbertson Lang,
Mandavellpakkam, R.A. Puram
Cherinai - 600 028, Ph : 24939524

ARTICLES OF AGREEMENT

ARTICLES OF AGREEMENT made this 29th day of October 2010 between M/s.Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041 represented by the Director (hereinafter called the "owner") of the one part and M/s. Kevin Electricals Pvt Ltd represented by Sri. L.Wilson Susai Raj, Managing Director, aged 44 years, whose registered office is situated at No.7 (old.No.1B), Arunachallapuram, IInd Street, Adyar, Chennai - 600 020 (hereinafter called the "Contractor") of the other part.

WHEREAS the owner is desirous for Electrical Installation Works for the Koothambalam at Kalakshetra Foundation (hereinafter called "the work") and has caused drawings, specifications and schedule of Quantities describing the works to be done and prepared by M/s. Centre for Architectural Research & Design, Architects, represented be Sri. Ravi Niilakantan and WHEREAS the said drawings as issued from time to time, the Notice of Tender, General Instructions to Contractors, the Specifications and/or the schedule of Quantities have been

LEELA SALOR DIRECTOR DIRECTOR LA CHEMINARY CHE

your

For KEVIN ELECTRICALS PVT. LTD.,

Managing Director



Kevin Electricals Pvt. Ltd., 24

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/KF/644/2010/565

03.11.2010

To

The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation to be carried out for M/s. Kalashetra at Chennai - Submission of Articles of Agreement - Reg.

REF: - Your Order Dt.28.09.2010.

With reference to the above, we are herewith submitting the original Agreement for the above project.

Thanking you, Your's faithfully, for **Keyin Electricals Pvt Ltd**,

L.Wilson Susai Raj (Managing Director)



Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank) Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

- 11. Subject to clause 3 hereof, Guarantee shall remain in force until the date of issue of Virtual Completion Certificate under the Contract.
- 12. Any notice by way of request, demand or otherwise hereunder may be sent by post to the Bank, addressed as aforesaid, and if sent by post, it shall be deemed to have been given at the time when it would be delivered in due course of post, and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate of posting from postal Authorities / Agencies, to the effect that the envelope was so posted shall be conclusive.
- 13 These presents shall be governed by and construed in accordance with Indian Law.
- 14 The Bank hereby declares that it has the power to issue this Guarantee and the undersigned has full power to do so.

Notwithstanding anything contained hereinabove our liability under this guarantee is restricted to Rs. 7,36,316/- (Rupees Seven Lakhs Thirty Six Thousand Three Hundred and Sixteen Only). This guarantee is valid up to 17.02.2011. Any claim arising out of the quarantee must be lodged with the bank at its office at No.30, Mandaveli Street, Mandaveli, Chennai - 600 028. on or before 17.02.2011, after which the liability of the bank would be extinguished.

In witness thereof the Bank has executed these present the day and year first above written.

Signed and delivered for and on behalf of the above named.

Manager Mondorcii, Chennai - 28

BG NO: 28277 DATED: 18/11/10 AMOUNT: 7,26,3161-DUE ON: 17/2/2011

VALID UPTO: 17/2/2011


Mandavell, Chesinavernoran Manager



- 03. The CLIENT may, without affecting Bank's liabilities and obligations hereunder and without reference to the Bank grant time or other indulgence to or compound with the Contractor or enter into any agreement or agree to forbear to enforce any of the terms and conditions of the Contract.
- 04. This Guarantee shall not be affected by any change in the Constitution of the Bank of the CLIENT or by absorption / merger of the CLIENT with any other body or corporation or otherwise and this Guarantee will be available to or enforceable by such body or corporation.
- 05. All composition and payments received by the CLIENT from or on behalf of the Contractor shall be regarded as payments in gross and in the event of the contractor being wound-up, the CLIENT will be entitled to prove against the properties of the Contractor in respect of the whole of the contractor's indebtedness to the CLIENT without any right on the part of the Bank to stand in the Client's place in respect of or to claim the benefits of such composition and payment or any security held by the CLIENT until the CLIENT shall have received the full amount of the claims against the contractor.
- 06 In order to give effect to this Guarantee the CLIENT will be entitled to act as if the Bank were the principal debtor and the Bank hereby waives all and any of its rights of surety ship.
- 07 THE GUARANTEE HEREIN CONTAINED is unconditional and not revocable by notice during its currency and will remain in full force until full payment has been made to the Client by BANK on the Client having lodged a claim under the Bank Guarantee within its validity i.e. 17.02.2011 (Due Date) and if no claim is lodged by the Client then the Guarantee would expire within the period specified in this Guarantee. The Bank's liability under this Guarantee is restricted to Rs. 7,36,316/- (Rupees Seven Lakhs Thirty Six Thousand Three Hundred and Sixteen Only) The CLIENT may claim the full or part of the amount under the Guarantee entirely at its sole discretion and make this claim at one or more times before the expiry (including the claim period) of this guarantee. The total amount of claims is restricted to the Bank's liability under the Guarantee. The Bank is required to make a payment immediately on receipt of the claim in the enclosed format.
- 08 THIS GUARANTEE shall continue to be in force notwithstanding the discharge of Contractor by operation of law and shall cease only on payment of the full amount by BANK to Client of the amount hereby secured and on the claim of Client against Contractor in respect of Contract being satisfied.
- 09 This Guarantee shall be in addition to and not in substitution for any other guarantee or security for the Contractor given or to be given to the CLIENT in respect of the Contract by the Bank whether alone or jointly with others.
- 10. IN THE EVENT OF force majeure, according to the Contract the validity of the present guarantee shall be extended for a period to be mutually agreed upon by the Client and the Contractor.

For CITY UNION BANK LTD.

K. Rochester Manager



FOR CITY UNION BANK LTD.

Manager AVEENDRAM Mandavell, Chennal 2861 AND WHEREAS one of the conditions of Contract entered into, with Contractor is that Client should make an advance payment of **Rs. 7,36,316/-** being **15%** (Fifteen percent) of Contract value against an indemnity in the form of a bank guarantee from a bank and in a form acceptable to the Client.

AND WHEREAS THE Contractor has requested BANK to issue one guarantee of Rs.7,36,316/-

NOW THIS GUARANTEE WITNESSETH that.

01. In consideration of Client, at the request of the Contractor, advancing a sum of Rs. 7,36,316/-, to the Contractor as and by way of Mobilization advance, the Bank hereby unconditionally and irrevocably guarantees to the Client for due performance of the Contractor's obligations under the contract and indemnifies the client in respect of the amount of the mobilization advance. BANK hereby undertakes without recourse to Contractor, to pay the Client, on mere demand in the enclosed format up to and not exceeding altogether a sum of Rs. 7,36,316/- (Rupees Seven Lakhs Thirty Six Thousand Three Hundred and Sixteen Only) being the amount of the 100% (One hundred percent) of the mobilization advance payment or such other unadjusted amount of the said mobilization advance. If the Client notifies to the Bank that the Contractor has failed to observe, perform and fulfill the terms of the said Contract then the Bank shall immediately pay to the CLIENT, on Client's mere demand in the enclosed format, such sum or sums of money to the extent of Rs. 7,36,316/- being 15% of the value of the Contract as may be claimed by the CLIENT by reason of non-fulfillment by the Contractor of his obligations under the Contract as aforesaid / and shall also indemnify the CLIENT against all losses and damages which may be suffered by the CLIENT as aforesaid and against all costs, charges, expenses which may be incurred by the CLIENT in connection herewith. The Bank shall pay the said amount without demur or protest or without recourse to the Contractor. Any such demand placed in the enclosed format on the Bank shall be conclusive with respect to the amount due and payable by the Bank under this Guarantee. The decision of Client as to whether the terms and conditions of this Guarantee or Contract have been observed or not shall be final and binding on BANK and the BANK will not have the discretion to withhold payment to the if letter in enclosed format is delivered by the CLIENT to the BANK on or before 17.02.2011 (Tenure of Contract including extension period, if any or the complete recovery of mobilization advance which ever is later)

02. This Guarantee is a continuing Guarantee and not revocable except with the previous written consent of the CLIENT and as aforesaid, it will continue in force until the Contractor has maintained the schedule of delivery of the said work under the Contract and observed and fulfilled the terms and conditions of the Contract. The CLIENT has an irrevocable & unconditional right to claim under the Guarantee in case the Guarantee required to be extended in its opinion is not extended by the CONTRACTOR or the BANK within the time frames and for the time frames stipulated by the CLIENT.

K. AMDARANK LTD.

Manager

Manager

Manager

Chennal - 28.

BG NO: 28277DATED: 18/11/20 AMOUNT: 7,86,316/-DUE ON: 17/2/2011 VALID UPTO: 17/2/2011

FOR CITY UNION BANK LTD.

Managers, RAVEENDRY Mandavell, Chennai 608 - 501



abh तिमलनाडु TAMILNADU SL. No 10531 Dala 27-10-2010 Name Kelin Electricals P. D. Value Rs. 100/

L.No. C4/22702/81 dt. 15. Robertson Lang. Mandave pakkam, R.A. Puram Chennai - 600 028, Ph : 24939524

Bank Guarantee For Mobilization Advance Payment

THIS GUARANTEE made this 18th day November 2010 BETWEEN M/s.City Union Bank Ltd, Mandaveli Branch, Mandaveli, Chennai - 600 028.(hereinafter called BANK) which expression shall, unless repugnant to the context or contrary to the meaning thereof, include its successors and assigns on the one part and M/s. Kalashetra Foundation having its office at Tiruvanmiyur, Chennai - 600 041 (hereinafter called Client) which expression shall, unless repugnant to the context or contrary to the meaning thereof, include its successors and assigns, of the other part.

WHEREAS Client has entered into a contract C: \ 2009-2010 \ V.Admin \ 2.Engineering \ i.Plan \ Koothambakkam \ Electrical installation work.doc (hereinafter called Contract) at a total value of Rs.49,08,773.27 with M/s.Kevin Electricals Pvt Ltd, 7, Arunachalapuram IInd Street, Adyar, Chennai - 600 020. (hereinafter called Contractor) which expression shall, unless repugnant to the context or contrary to the meaning thereof, includes its successors and assigns.

608-53

FOR CITY UNION BANK LTD.

Manager Mandarell, Chennai - 28. BG NO: 28277 DATED: 18/11/10 AMOUNT: 7,86,816/-DUE ON: 17/2/2011

VALID UPTO: 17/2/2011

FOR CITY UNION BANK LTD.

Manage RAVEENDRAN Mandavell, Chennage 8. 501

K, Seethalakshmi 608-538



Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020.

REF: KE/KF/644/2010/605

18.11.2010

To

The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation work for M/s. Kalakshetra Foundation at Chennai - Submission of Bank Guarantee - Reg.

REF: - Your Order Dt.28.09.2010

With reference to the above, we are herewith submitting the original Bank Guarantee (No:28277 Dt.18.11.2010 for Rs. 7,36,316/-) for mobilization advance.

We request you to kindly arrange to release the mobilization advance & oblige.

Thanking you,

Yours faithfully, for Kevin Electricals Pvt Ltd,

L.Wilson Susai Raj (Managing Director)

Branch Office:

: # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road, Bangalore

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank) Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in



Works kalakshetra <works@kalakshetra.in>

Wed, Nov 24, 2010 at 9:38 AM

Security deposit - Electrical installation work at Koothambalam- reg.

Works kalakshetra <works@kalakshetra.in>
To: card@vsnl.com, jrajayakumar27@gmail.com
Cc: ao@kalakshetra.in, cao@kalakshetra.in

Dear sir,,

M/s.Kelvin electricals submitted the bank guarantee for relase of moblisation advance for the electrical work at koothambalam.

They are asked to submit the 1.5 % of the total awarded value as security deposit in addition to the EMD. The same was discussed during the saturday meeting.

They did not come to submitt the above amount as security deposit.

Please guide me,

may I proceed to relase the bank guarantee to M/s.Kelvin electricals without considering the security deposit.

warm regards

V.Srinivasan.

A TERRITOR

4.00 m

2 A A W 5 C

(22)

Rosum: Hed Pleano

- 1) As per SI. No I on Abstract of Frical terms in 16 Pender Canditain, (P84/c) uph 15 1. 7 18 Contact Value of wall again BG to be adjusted again payment of the Contracta's Muning Will
- 1) BG is Ventey on in in order plear 1 PIDAL Liton; N pe

CAD PIOLINA

GAU

COC

to availability of fueds. Dr. May le appel subject-

Sub pl.

Kuhun 13/12

DIR. 16/12

Resulanited Pleans

Further to 15 note almo, it is stated that

As pur Para 2.09 of the combact of Agreement, MIS CARD Keprun to invite, roceive and analyse tendens; advise chieut on worlds Committee File-1 appointment of Contractors

Accordingly this contract to Etechnical mistallate has Page 22/c Koofrentelm' was drahad & 4/5 CARD aw the same in indrated to m;

As put to Tender Dommens of this was (P6827) Electrical | Works END @ 17. 8 14 Contract vane new 11 to deposited by 14 Documni. tenden; (350,000/-) Page 105/c placed below

Sumperty on por R mail Kept at P 134/c, Se wii by Puge 134/c deposit of 1.5 %. By the Contract value was also collected ly 1/1 (AR) (1 73650/-)

BOB & END an S. D wer towarded be an en chegines an too to the thegues was realised in Canara Bane Plan schomer, on 21.9.2010 aw 4.12.20 to respectives under

It is now subsonith Molihaha amout paid leg to Contractor may pleas be refeased, on the BG again this a mar is how given by the Can hack

Entron: And for approved 101:

andblisalin partof Pl. renly & link Kindly comprise of the B. a is in order tehneally.

Tender page 84/6

puge 135/e

P129/C

C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\ Electricl installation work.doc

November 30, 2010

Sub: Koothambalam – Electrical Installation work in Kalakshetra Foundation – Release of Mobilization advance - Reg.

Ref: Clarification sent to M/s.CARD by email dated Nov 24, 2010.

- Page 130

Based on recommendation by the consulting Architect M/s.CARD and his associates M/s. Madras electrical Consultants, after approved by the works committee, the work of Electrical installation at Koothambalam in Kalakshtra Foundation was awarded to M/s.Kevin Electricals Pvt Ltd, Engineers and Government Licensed A grade Contractors, Adyar, Chennai 600 020, at a total cost of Rs.49,08,773.29/-(Rupees forty nine lakh eight thousand 107% 108 seven hundred seventy three and paise twenty nine only)

The contractor M/s.Kevin Electricals submitted the EMD amount along with tender puge 5 submission for Rs.50, 000/- as per the terms.

As per M/s.CARD terms, the security deposit at rate of 2.5% of awarded the contract value has to be remitted with the client before entering into agreement. The issue was discussed with M/s.CARD and his associates during the Saturday meeting. The arrangement to remit 1.5% of awarded contract value will be submitted by the contractor after considering the EMD already submitted the contractor at rate of 1%, which was communicated to M/s.CARD and still pending.

Meanwhile, the contractor requested to release the mobilization advance, as per the terms for Rs. Rs.7, 36,316/-against the bank guarantee value of Rs. Rs.7, 36,316/- vide city union bank / Mandavelli branch.

Submitted for information please.

Manchario Mario

CAÓ

A Actai to fivation of to be d'are upently,

As fair Molidia chá advano netears the

Jame may be d'are offer Lilvy 16 B.G with un (PASIC)

May be approved please.

Deputy Director

A MIS. CARD has now clamined that EMD to 14 and seum

DD

Director

page 133 for 13. 50,000 form funts a lime of the onstrict 2010 E134 (Et. ST.) Envals seeming Deposit, News. 125)

0000000

All amech

Lagran (PTO)

DIRECTO



Kevin Electricals Pvt. Ltd., 22

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/KF/644/2010/667

16.12.2010

To

The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation to be carried out for M/s. Kalashetra at Chennai - Submission of Statutory Details- Reg.

REF: - Your Order No: C:\2009-2010\V.Admin\2.Engineering\ i.Plan \ Koothambalam \ Electrical Installation work.doc Dt.28.09.2010.

With reference to the above, we are herewith submitting the details for your kind reference.

1) TIN.No

33680862581

2) PAN No

AACCK2913P

3) Service Tax Reg.No

CAI/Chennai - IV/115/STC

4) ESI No

51-85288-101

5) PF No

TN/51955

Thanking you,

Yours faithfully,

for Kevin Eleçtricals Pvt Ltd,

Wilson Susai Raj naging Director)

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

က 4 9 2 œ या उनके आदेश पर / OR ORDER SECTIVED SECTIVED For GITY UNION BANK LIMITED 🕒 कृते सिटी यूनियन बैंक लिमिटेड 73,650,00 ı ال 0.0005400013 00100711 73,650.00 रुपये RUPEES Seventy Three Thousand Six Hundred Fifty ONLY KALAKSHETRA FOUNDATION * दला Mal 2 (121) - 795355 NOT OVER Re. 项 OT MANDAVELI (CHENNAI) BRANCH (036) CITY UNION BANK LIMITED III 795355III सिटी यूनियन बैंक लिमिटेड SERVICE BRANCH CHENNAL अदाकर्ता शाख का नाम NAME OF DRAWEE BRANCH ON DEMAND PAY मांग्ने पर ई प्रके कर्त निव्रम : रू के छोगात कि निष्ट प्रसी ग्रिष्ट eussi to eate ent mont antnom xis not blisk

CITY UNION BANK LIMITED

(3/2)



Kevin Electricals Pvt. Ltd., 1936

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020.

REF: KE/KF/644/2010/629

01.12.2010

To

The Director, Kalakshetra Foundation. Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation to be carried out for M/s. Kalashetra at Chennai - Submission of Security Deposit - Reg.

REF: - Your Order No: C:\2009-2010\V.Admin\2.Engineering\ i.Plan \ Koothambalam \ Electrical Installation work.doc Dt.28.09.2010.

With reference to the above, we are herewith submitting the DD for Rs.73,650/-(Rupees Seventy Three Thousand Six Hundred and Fifty Only) (Demand Draft No: 795355 Dt.01.12.2010) towards security deposit of 1.5% apart from the EMD amount of Rs. 50,000/- which was already given along with the tender.

Thanking you,

Your's faithfully, for Kevin Electricals Pvt Ltd,

L.Wilson Susai Raj (Managing Director)

Chaque removed and Depositudin Boulc on 3-12, 2010.

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

by eash subject to realisation on account of Cheque No. 9 9 5355 A. 1.12, 2 cto city Union Beale, go Archemis Rupees Seventy three thousand ser hunched out filts RECEIVED with thanks from only Kevin Electricals Put. Lieli Date: 3 . 12 . 2010 Adyon, chemia - 600 020 198

A LANGER BAR STEEL BAR STE

Chief Accounts Officer





AO Kalakshetra <ao@kalakshetra.in>

regarding EMD&Security deposit for HVAC work

Ravi Nilakantan < card@vsnl.com>
To: AO Kalakshetra < ao@kalakshetra.in>

Wed, Dec 8, 2010 at 1:41 PM

Sri. Ramachandran,

EMD is 1% Security is 1.5% of the contract value.



Regards,

Ravi

From: AO Kalakshetra [mailto:ao@kalakshetra.in] Sent: Tuesday, December 07, 2010 10:59 AM

To: card@vsnl.com

Cc: jrajayakumar27@gmail.com

Subject: regarding EMD&Security deposit for HVAC work

Sir,

We received 2.95 lakh by cheque from M/s Unimech Engineers towards HVAC works at Koothambalam as recommend by you as mentioned Security Deposit.

Kindly clarify the following at the earliest,

The percentage charges for the EMD & Security Deposits and the actual amounts as per tender / quotation conditions may be indicated clearly by email.)

warm regards,

08 12 2010

By 50,,000 f. Cof um Balc

D.D.w. 682551 21.9.2010

By 23,600 (DD) - 3.12.2000

Ex DD 795355 City um Balc -4.12.10

MCW 2649101001749

(b)

133

केनरा बैंक 🗘 Canara Bank

तिरुवनमियूर, चेन्नई - 600041 Thiruvanmiyur, Chennai - 600041

CBS BRANCH ब बें SB

दिनांक Date 1,81122010

Pay M/s. Kevin Electricals Put. Ltd.

या धारक को or Bearer

रूपये Rupees Seven lach Size thousand Eight hundred and Surly four on अदा करें

₹5. 7, 06 ,864 =

SWEEP IN / SWEEP OUT

FACILITY A/C

खार्स. A/CNO. NO 2 6 4 9 1 0 1 0 0 1 7 1 9 1

2010 MSHAO IFSC : CNRB0002649

FOR KALAKSHETRA FOUNDATION

Authorised Signatories

"346765" 600015078:

10





Works kalakshetra <works@kalakshetra.in>

layout and orientation of HVAC plant - reg.

Works kalakshetra <works@kalakshetra.in>

Tue, Dec 28, 2010 at 2:09 PM

To: ravi <card@vsnl.com>

Cc: ao@kalakshetra.in, CAO Kalakshetra <cao@kalakshetra.in>

Dear sir,

As decided that the shifting of EB pillar box near the koothambalam through the Electricity people is being organised. The location of shifting the pillar box is identified by the Director, and shown to the Mr.J.Ra.J and my self.

Meanwhile, the exact location and orientation of HVAC plant, Diesel Generator room and proposed transformer area layout may be furnished to office for approval before shifting the EB pillar box.

Kindly do the needful.

warm regards v.srinivasan



		Sten.	pse163
0 0		by Cash subject to realisation on account of FMD for Fle Lluces Cheque of the Hallollon of Solver of Solve	Chief Accounts Officer
		3 3	ounts C
Date: 20	F. M. Seven Tabusand out	THE S	f Acco
ate :	0	77	Chie
D Z	1/2	D on	
No. 121 Date:	F. M. Geven Minimand out	7 D	
(3	4	25 57000 - 57000 - 58663 / 16.9.10
Z.	2 E	of C)	0
		count	3
7	3	on a Z	9
	4	sation OC	25
ks fron		realis	1
than	A A	ect to	000 L
1 C	(_	o single	5 8
		Cash S Cheque	(X) \$ > > > > > > > > > > > > > > > > > >
No.		ī â (

Date: 20 9 10	Los Logadole	Chief Accounts Officer of 100 100 100 100 100 100 100 100 100 10
No. 122 Date: $2c$ 9 10 RECEIVED with thanks from ReV^{10} $ELLLLLLLLL$	Rupees F. L. Ly The would owly Exclusive at Finatellal by Oash subject to realisation on account of EMD. Av. L. Upafadallal	CUB 11-d DD Mo: 68 2551/13 9 10
No.	Rupa Oy Og Che	KS.

RECEIVED with thanks from S. S. Electricals Rupees S. M. Hy Cash Habita Count of Charles School Styles Cheque Anothall alicen 10 paradalam of Sound Styles Rs. 68000 Rs. 68	No. 124 BECEIVED with thanks from S.S. Fleeth. Call.	Rupees Slate Can the the cond of the Cash by Cash subject to realisation on account of EMD the Cash Electrical Sustainant of Short Cash Cheque of Short Cash Chegue of Short Cash Cash Cash Cash Cash Cash Cash Cash	
--	---	--	--

Date: 20 (D	n hundrad and dolly for Electrical Sound system	Chief Accounts Officer & S1219 \ 20 9 10 5
No. 123 Date: 20 7	Rupees Staty that Another Seven hundred and John Bupees Stathy that Another And And Cash subject to realisation on account of EMD An Electrices Cheque Exacted to the Markan Construction of Sound System.	(S. 140) The Chim 431219 20 9 10 9

Fo, The Director DD/ Ao Kalakhetna Foundatus

Redpected modam | Sin,

our Kootkambalam is under menovation. So wehave to Shift the Elever Allan Box (Power Supply) from exitating Place to other place (mean Generally opp)

I recount you kindly Intom Am Electricity Board obtice recons peting

1493 from the existing Pillar 1496

Dem House 202-27-95 (Service)

3) College Cottagy 202-27-198 "

@ Prenter Hall & 20x-27-198

above mentin Places will be

Distrubed during the Shitim of ER Pil



Works kalakshetra <works@kalakshetra.in>

M/s. Kalakshetra - Eb application & covering letter for shifting - Reg

Kevin Electricals Pvt Ltd., <kevinelectrical@yahoo.co.in>

Mon, Dec 27, 2010 at 1:57 PM

To: Works@kalakshetra.in

Cc: card@vsnl.com, jra jayakumar <jrajayakumar27@gmail.com>, MSRamesh <msramesh@mec-india.com>, loganayaki mec <gloganayaki@mec-india.com>

Dear Sir,

Kindly let us have following documents & details for apply for EB connection.

1) Copy of existing meter card for new enhancement.

2) ownership documents for new CT meter connection.

Covering letter for shifting of Existing feeder pillar box(Draft letter is Enclosed herewith)

4) Necessary deposit amount (As soon as receipt of advice for TNEB)

Kindly do the needful & oblige.

Thanks & Regards

L.Wilson Susai Raj,

Managing Director
Kevin Electricals Pvt Ltd.,

No.7 (Old No.1B) Arunachalapuram 2nd Street, Adyar, Chennai - 600 020.

Tel.No. 044-2446 6938, Telefax 044-2491 2704.

Draft Letter.doc



DRAFT Sent by MIS. kerin Electricals.

To

The Assitant Engineer,
Tamilnadu Electricity Board, Tawi well have here to a 2's muse aposte.

Thirwanmiyur,

Chennai - 41.

Dear Sir,

SUB: - Shifting of pillar box - Requested- Reg.

REF: - Feeder Pillar No.P149B to 149C.

We request the authority to kind arrange to shift the pillar box (Ref.No:P149B to 149C) which is presently installed near by koothambalam since we are proposed to provide the new road for vehicle movement propose to devotop to law o caps.

The necessary amount for shifting will be paid on hearing from your end.

Kindly do the needful & oblige.

Thanking you,

Yours faithfully, For

(Managing Director)

Encl: (i) Lyng of existy EA service metar Card

(ii) Kalahaha Ferdahi Ach 1993 - detailing 16 aree of an mentip.

(40)



Works kalakshetra <works@kalakshetra.in>

layout and orientation of HVAC plant - reg.

Works kalakshetra <works@kalakshetra.in>

Tue, Dec 28, 2010 at 2:09 PM

To: ravi <card@vsnl.com>

Cc: ao@kalakshetra.in, CAO Kalakshetra <cao@kalakshetra.in>

Dear sir,

As decided that the shifting of EB pillar box near the koothambalam through the Electricity people is being organised. The location of shifting the pillar box is identified by the Director, and shown to the Mr.J.Ra.J and my self.

Meanwhile, the exact location and orientation of HVAC plant, Diesel Generator room and proposed transformer area layout may be furnished to office for approval before shifting the EB pillar box.

Kindly do the needful.

warm regards v.srinivasan



502° 90 1/2010 /20

(10)

மி் கட்டணப் பட்டியல்					CURRENT CONSUMPTION CHARGES -TABLE			
மின் அளவு குறிக்கப்பட்ட நாள் Date of Reading	கறிக்கப்பட்ட மின் அளவு அளவு நாள் Reading Consumption		மின் கட்டணம் CC Charges மு. Rs.			கணக்காளரின் சுருக்கொப்பம் (Initials)	மின் கட்டணம் செலுத்திய விவரம் P.R. No. & Date	குறிப்பு Remarks
5310	6710	620	2904	1	CHS 2021	M Q	369/16	4.
2,1510	5710	ηП.	lho'	_	200	1950	19/61	
8/h	5840	130	820	CF	S 202 LA	9 1890	/3187	7
Male	صده	200	1048		my	۹ 728	ist.	
121210	buro	370	1905					
10 1	Ü		-					
		3.	# 1500 Fine					
		4 7 14	The state of the s					
			1000	alam-				
1111								
\overline{C}								
The state of the s					No. 3.	3		
			n 4	ica icas				-
			100		நீங்களும் இலாப	200		

(102)

த்.நா.மி.வா. அச்சகம், சென்னை – 38. 2008–2009

வசூல் நேரம்

முற்பகல் 8.30 மணிமுதல் பிற்பகல் 12.30 மணி வரை பிற்பகல் 1.30 மணிமுதல் பிற்பகல் 2.30 மணி வரை மின் நுகர்வோர்களின் குறைகள் சம்பக்தப்பட்ட அலுவலகப் பணியாளர் களால் தீர்க்கப்படாமல் இருந்தால் அவர்கள் மின் நுகர்வோர் குறை தீர்க்கும் மன்றத்தை அணுகலாம்.

விதிமுறைகள்

 மின் கட்டண அட்டை, கணக்கீட்டாளர் பார்வையில் படுமாறு வைக்கப்பட வேண்டும்.

2. அட்டையைக் கொடுக்க இயலாத மின் நுகாவோருக்கு கட்டண தொகையைக் கணக்கீட்டு ஒரு சீட்டு கொடுக்கப் படும். அட்டை தொலைந்துவிட்டாலோ (அ) சிதைந்து உப்யோகீக்க இயலாத நிலையில் இருந்தாலோ மின் நுகாவோருக்கு புதிய அட்டை கொடுக்க ரூ. 5/– (ரூபாய் ஐந்து) வசூலிக்கப்படும்.

3. கதவு பூட்டப்பட்டிருப்பின் முந்தைய கணக்கீட்டின்படி உள்ள கட்டணமே வசூலிக்கப்படும். அடுத்த மின் கணக்கீட்டின் போதும் பூட்டப்பட்டிருப்பின் 24 மணி நேர அறிவிப்பு தரப்படும். 24 மணி நேர அறிவிப்பு பெறப்பட்ட பிறகும் பூட்டப்பட்டிருப்பின் மின் இணைப்பு துண்டிக்கப்படும்.

4. செலுத்தப்படும் மின் கட்டணங்களுக்கு நிலையான ரசீது களைப் பெற வேண்டும். ரசீதுகளில்லாமல் செலுத்தப் படும் தொகைகளுக்கு மின்சார வாரியம் பொறுப்பாகாது.

5. மின் கப்டணத்தை பணமாகவோ, காசோலை / வணுவோலை அல்லது பண அஞ்சல் (எம்.ஓ) மூலமாகவோ செலுத்தலாம். பணமாக செலுத்துவதானால், வகுல் மையத்தில் மட்டுமே செலுத்துதல் வேண்டும். காசோலையாக செலுத்துவதானால் கணக்கீட்டாளா் மின் அளவு குறிக்க வரும்போது அல்லது தபால் மூலம் அல்லது வகுல் மையத்தில் செலுத்தலாம் காசோலை/ வரைவோலை மேற்பாாவை பொறியாளா் /

என்று எழுதப்பட்டு "Account Payee" என்று குறுக்கு கோடிப்பட்டிருத்தல் வேண்டும்.

6.பண அஞ்சல் அல்லது காசோலையை தபாலில் அனுப்பும் பொழுது மின் இணைப்பு எண், எந்த மாத மின் கட்டணம் போன்ற விவரங்கள் குறித்து, பிரிவு அலுவலருக்கு அனுப்புதல் வேண்டும்.

7. மின்சார வாரியம் அவ்வப்போது அறிவிக்கும் விதிமுறைகள் அனைத்தும் மின் நுகாவோருக்கு பொருந்தும். horas The ass

மின் பயனீட்டுக் கட்டண் அட்டை CURRENT CONSUMPTION CHARGES ARD

பிரிவு அலுவலகம் : (Section Office)

பகிர்மானம் : (Distribution)

மின் இணைப்பு எண்ற

-027-95

பெயர் (Name) :

முகவரி (Address) :

ஒருமுனை/மும்முனை இணைப்பு

மின் அளவியின் எண் (Meter No.) :

7008292

திறன் (Capacity) :

வைப்பு நிதி (CCD) :

கட்டண வீதப்பட்டியல் எண் : (Tariff)

கட்டண விகிதம் (Tariff Rates) :

மின் கட்டணம் செலுத்தும் இடம்: (Cash Counter)

மின் கட்டணம் செலுத்த கடைசி நாள்:

பயனீட்டு மின் அளவு (மீட்டர் ரீழுங்) சனவரி, மார்ச், மே, கூலை, சைப்டம்பர், நவம்பர் பிப்ரவரி, ஏப்ரல், கூன், ஆகஸ்டு, அக்டோபர், டிசம்பர்

மாதங்களில் 16ம் தேதி முதல் எடுக்கப்படும்

மின் கட்டணம் செலுத்த குறிப்பிடப்பட்டுள்ள கன நாளிலிருந்து 7 நாட்களுக்குள் மின் கட்டணம் செலுத்தப் படவில்லையெனில், மறு அறிவிப்பின்றி மின் இணைப்பு துண்டிக்கப்படும். மேற்குறிப்பிட்ட 7 நாட்களையும் சேர்த்து மின் கட்டணம் செலுத்தி மின் துண்டிப்பைத் தவிர்க்க இறுதி நாள் 15ம் தேதி.

இறுத் நாள் விடுமுறையாக இருப்பின் அதற்கு அடுத்த பணிநாளில் கட்டணம் செலுத்தலாம். அப்படியும் செலுத்தத் தவறினால் மின் இணைப்பு துண்டிக்கப்படும்.

A.

நுகர்வோர் கையொப்பம்



229 202 27 198

	Tiolog						
மின் அளவு	மின்	ப்ரின் ம	மின் கட்டல	Temp in in its i		செலுத்திய	ട്രുവരു പോർഗ്ര
குறிக்கப்பட்ட நாள்	(ரூர்) அளவு	அளவு (கன்சம்ஷன்)	%	பை.	் கண்க்காளின் கையொட்பம்	0 '	astigent partigent
1/18	9110	1355	6300	C.S.	- 1	ORS COLTY	10 seef
alila	f0770	1660	7709		/	Cesa 94	e glalg
319	12600	1830	8495			CUS017	73 5/7/9
29/5/09	14000	1400	6500	-		08012	72 12/6/9
-719	15000	1000	4660			21310	1470g
24 59	15000	Allo	5584	_		chee1490	1866
11/04	16000	(1000 12v	5584			Cly219An	979 14 lobs
ella,	16500	P7 (200	558L	-		ch 2996/	e 1721/2 (
263-10	17000	04/200	5584	/	•	HS 202 TEST C2	88/15W/to
3000	18630	1630	7571	_	l o	Zoulot 2AT	Supplies mer
_ &(10	20630	2000.	9801	C	HS 202	1897	SAGEO IN
Thale	22360	MZs	8759		2	ong Tellis	தாப்லம் இரும்வத்தில்
12-12-0	24000	1640	8306	in (co			(อีเมากุดีเมาเลา เมลิกันดูเราะสา
						eli .	म् क्षीट १८७१ । १ कि.म. १८०४ ।
		to the section				गुराह	் புப்பட்டும் வரப்பட்டுக்
						A STATE	o luraisigi elitasialiale

மின்சாரத்தை சிக்கனமாகப் பயன்படுத்தி, நாட்டுத்கு உதவுங்கள் நீங்களும் இலாபம் பெறுந்தள்.



மின் தடங்கலுக்கு 1912 தொடர்பு கொள்ளவும்.

வசூல் நேரம்

முற்பகல் பிற்பகல்

8–30 மணி முதல் 12-30 மணி வரை

பிற்பகல்

1430 மணி முதல்

பிற்பகல்

2-30 மணி வரை

விதிமுறைகள்

மின்கட்டண் அட்டை, கணக்காளர் பார்வையில் படுமா று வைக்கப்பட வேண்டும்.

2 அட்டையைக் கொடுக்க இயலாத மின் நுகர்வோருக்கு கட்டண தொகையைக் கணக்கிட்டு ஒரு சீட்டு கொடுக்கப்படும். அடுத்த கணக்கீட்டின் பேரதும் அட்டையை கொடுக்க இயலாத மின் நுகர்வோருக்கு புதிய அட்டை கொடுக்க ரூ. 5/- (ரூபாய் ஐந்து) வசூலிக்கப்படும்.

கதவு பூட்டப்பட்டிருப்பின் முந்தைய கணக்கீட்டுபடி உள்ள கட்டணமே வகுலிக்கப்படும். தொடர்ந்து பூட்டப்பட்டிருப்பின் மின்.இணைப்பு துண்டிக்கப்படும்.

செலுத்தப்படும் மின் கட்டணங்களுக்கு நிலையான ரசீதுகளைப் பெற வேண்டும். ரசீதுகளில்லாமல் செலுத்தப்படும் தொகைகளுக்கு மின்சார வாரியம் பொறுப்பாகர்து.

மின் கட்டணத்தை பணமாகவோ, காசோலை அல்லது பண் அஞ்சல்(ஆஎம்.ஓ.இ)முல்மாசவோ செலுத்தலாம். பணமாக செலுத்துவதானால் வசூல் மையத்தில் மட்டுமே செலுத்துதல் வேண்டும். கரசோலையாக செலுத்துவதானால், கணக்காளர் மின் அளவு குறிக்க வரும்போது அல்லது தபால் மூலம் அல்லது வகுல் மையத்தில் செலுத்தலாம் காசோலைகள் மேற்பார்வை பொறியாளர்/ ... பகிர்மான வட்டம் என்று எழுதப்பட்டு Account Payee "என்று சோடி டப்பட்டிருத்தல் வேண்டும்.

பண அஞ்ச்ல் அல்லது காசோலையை தபாலில் அனுப்பும் பொழுது மின் இணைப்பு எண். எந்த மாத மின் கட்டண்ம் போன்ற விவரங்கள் குறித்து, பிரிவு அலுவலருக்கு அனுப்புதல் வேண்டும்.

மின்சார வாரியம் அவ்வப்போது அறிவிக்கும் விதிமுறைகள் அனைத்தும் மின் நுதர்வோருக்கு பொருத்தும் படுப்படு முத்துகள் நெரியில்ல அக்கியில் இது இந்தியில்ல **நாகர்கோர் சைமெழ்ப்படி**ந்தில்

fump bouse

ALON மின் **6001**

பிரிவு ஆலுவலகம் : பகிர்மானம் (ஊர்) :

மின் இணைப்பு எண் பெயர் :

ஒருமுனை/மும்முனை இணைப்பு பின் அளவியின் எண் :

ுறன்:

முகவரி:

வேப்பு நிதி:

1தப்பட்டி எண் (டே்ரிப் எண்)

மின் கட்டண விகிதம் :

மின் க்ட் டணம் செலுத்தும் இடம் : மின் கட்டணம் கட்ட கடைசி நாள் :

சனவரி, மார்ச், மே, சூலை, செப்டம்பர், நவம்பர் பிப்ரவரி, ஏப்ரல், சூன், ஆகஸ்டு, அக்டோபர், டிசம்பர் மாதங்களில் 16ம் தேதி முதல் But विष्युः । எடுக்கப்படும்.

1910 ஆம் ஆண்டின் இந்திய மின்சார சட்டம் பிரிவு 24 உட்பிரிவு (1)ன் படி மின் நுகர்வோர்க்கு கொடுக்கப்படும் 7 நாள் அறிவிப்பு

மின் கட்டணம் கட்டக் குறிப்பிடப்பட்டுள்ள கடைசி நாளிலிருந்து 7 நாட்களுக்குள் மின் கட்டணம் செலுத்தப்படவில்லையெனில், மறு அநிவிப்பின்றி மின் இணைப்பு துண்டிக்கப்படும்.

மேற்குறிப்பிட்ட 7. நாட்களையும் சேர்த்து மின் கட்டணம் செலுத்தி மின் துண்டிப்பைத் தவிர்க்க இறுதி நாள் 15ம் தேதி

இறுதிநாள் விடுமுறையாக இருப்பின் அதற்கு அடுத்த பணிநாளில் கட்டணம் சட்டலாம். அப்படியும் கட்டத் தவுறினால் மின் இணைப்பு துண்டிக்கப்படும்.

மின் துண்டிப்பு நாள் 16ம் தேதி அவ்லது அதன் பின்பு.

*



	JMPTION CHARGES மின் கட்டணம்		பெரு வெருத்தம்			ாட் டியல்	்டணப் ட	மிர் கட
க்றிப்பு Remarks	្រាល VEEssard ទេស្វាត់ទី៧ សាលារបំ P.R. No. & Date	கணக்காளரின் சுஞக்கொப்பம் (Initials)	Total மு. Rs.	மின் வரி (Electy. Tax) மு. Rs.	றின் கட்டணம் CC Charges மு. Rs.	பயனீட்டு அளவு Consumption	மின் அளவு Reading	மின் அளவு குறிக்கப்பட்ட நாள் Date of Reading
17	369154	4 9	HS 202 14	/(3736	800	46070	7310
	1914	Q 58	Just	~ L	1888	400	46470	dia
	3/86	1889/	202 101 0	CHS	4634	340	47413	8(12
	1186	1270	2		5382	اعلها	48470	alcalo
					3467	680	49150	Mio
	-111-2						71.50	
						17.	Signature of the state of the s	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
							a constant the	
			AND THE ST					
						in Ma		
	3,000							
				5	MENCOLUE III		17.7	(c)
					The second second	E May	<u>1</u>	10 01 025 035 10 025 4 034 035 1 025 4 035 035
	*							

மின் திருட்டு பற்றிய தகவல்களைத் தெரிவிக்க என்ற தொலைபேசியில் தொடர்பு கொள்ளவும்

த.நா.மி.வா. அச்சகம், சென்னை – 38. 2008–2009

·

வசூல் நேரம்

முற்பகல் 8.30 மணிமுதல் பிற்பகல் 12.30 மணி வரை பிற்பகல் 1.30 மணிமுதல் பிற்பகல் 2.30 மணி வரை மின் நுகர்வோர்களின் குறைகள் சம்பந்தப்பட்ட அலுவலகப் பணியாளர் களால் தீர்க்கப்படாமல் இருந்தால் அவர்கள் மின் நுகர்வோர் குறை தீர்க்கும் மன்றத்தை அணுகலாம்.

விதிமுறைகள்

- மின் கட்டண அட்டை, கணக்கீட்டாளர் பார்வையில் படுமாறு வைக்கப்பட வேண்டும்.
- 2. அட்டையைக் கொடுக்க இயலாத மின் நுகாவோருக்கு கட்டண தொகையைக் கணக்கீட்டு ஒரு சீட்டு கொடுக்கப் படும். அட்டை தொலைந்துவிட்டாலோ (அ) சிதைந்து உபயோக்க்க இயலாத நிலையில் இருந்தாலோ மின் நுகாவோருக்கு புதிய அட்டை கொடுக்க ரூ. 5/- (ருபாய் ஐந்து) வகுலிக்கப்படும்.
- 3. கதவு பூடப்பட்டிருப்பின் முந்தைய கணக்கீட்டின்படி உள்ள கட்டணமே வகுலிக்கப்படும். அடுத்த மின் கணக்கீட்டின் போதும் பூட்டப்பட்டிருப்பின் 24 மணி நேர அறிவிப்பு தரப்படும். 24 மணி நேர அறிவிப்பு பெறப்பட்ட பிறகும் பூட்டப்பட்டிருப்பின் மின் இணைப்பு துண்டிக்கப்படும்.
- 4. செலுத்தப்படும் மின் கட்டணங்களுக்கு நிலையான ரசீது களைப் பெற வேண்டும். ரசீதுகளில்லாமல் செலுத்தப் படும் தொகைகளுக்கு மின்சார வாரியம் பொறுப்பாகாது.
- 5.மின் கப்பணத்தை பணமாகவோ, காசோலை / வரைவோலை அல்லது பண அஞ்சல் (எம்.ஓ.) மூலமாகவோ செலுத்தலாம். பணமாக செலுத்துவதானால், வசூல் மையத்தில் மட்டுமே செலுத்துதல் வேண்டும். காசோலையாக செலுத்துவதானால் கணக்கீட்டாளர் மின் அளவு குறிக்க வரும்போது அல்லது தபால் மூலம் அல்லது வசூல் மையத்தில் செலுத்தலாம். காசோலை/ வரைவோலை மேற்பார்வை பொறியாளர் / மின்பகிர்மான வட்டம் என்று எழுதப்பட்டு "Account Payee" என்று குறுக்கு கோடிப்பட்டிருத்தல் வேண்டும்.

Kan ..

No.

- 6.பண அஞ்சல் அல்லது காசோலையை தபாலில் அனுப்பும் பொமுது மின் இணைப்பு எண, எந்த மாத மின் கப்டணம் போன்ற விவரங்கள் குறித்து, பிரிவு அலுவலருக்கு அனுப்புதல் வேண்டும்.
- மின்சார வாரியம் அவ்வப்போது அறிவிக்கும் விதீமுறைகள் அனைத்தும் மின் நுகர்வோருக்கு பொருந்தும்.

Hombe collap



மின் பயனீட்டுக் கட்டண அட்ெ CURRENT CONSUMPTION CHARGES CARD

பிரிவு அலுவலகம் : ABA SWR (Section Office)

பகிர்மானம் : (Distribution)

மின் இணைப்பு எண் 202 – 02 7 – 71 (SC No.)

வெயர் (Name): Se செய்வ

ஒருமுனை/மும்முனை இணைப்பு :

மின் அளவியின் எண் (Meter No.) :

திறன் (Capacity) :

வைப்பு நிதி (CCD) :

கட்டண வீதப்பட்டியல் எண் : (Tanff)

கட்டண விகிதம் (Tariff Rates) :

மின் கட்டணம் செலுத்தும் இடம்: (Cash Counter)

மின் கட்டணம் செலுத்த கடைசி நாள்:

பயனீட்டு சனவரி, மார்ச், மே, கூலை, செப்டம்பர், நவம்பர் பிப்ரவரி, ஏப்ரல், குன், ஆகஸ்டு, அக்டோபர், டிசம்பர்

மாதங்களில் 16ம் தேதீ முதல் எடுக்கப்படும்

மின் கட்டணம் செலுத்த குறிப்பிடப்பட்டுள்ள கடைசி நாளிலிருந்து 7 நாட்களுக்குள் மின் கட்டணம் செலுத்தப் படவில்லையெனில், மறு அறிவிப்பின்றி மின் இணைப்பு துண்டிக்கப்படும். மேற்குறிப்பிட்ட 7 நாட்களையும் சேர்த்து மின் கட்டணம் செலுத்தி மின் துண்டிப்பைத் தவிர்க்க இறுதி நாள் 15ம் தேதி.

இறுத் நாள் விடுமுறையாக இருப்பின் அதற்கு அடுத்த பணிநாளில் கட்டணம் செலுத்தலாம். அப்படியும் செலுத்தத் தவறினால் மின் இணைப்பு துண்டிக்கப்படும்.

நுகர்வோர் கையொப்பம்



SI. Docu No. N	nent Year	Village	Taluk	District	Survey No.	Paimash No.	Extent
25. 227	5 194	7 Thiruvanmi- yur	Saidapet	Chinglepe	t O.S. No. 267		0-5-12
				£	269 270	0-0-12	0-15-6 3-10-2 0-0-12
	* *				270 <i>A</i> 271 278	À	2-4-0 1-4-0 1-4-0 1-4-0
10 1.			;	<u>.</u>	279		1-0-0 4-15-0 1-0-0 0-3-0
		<i>\</i>			e e e e e e e e e e e e e e e e e e e	1226, 1226A, 1226B, 967, 968A, 968C, 970B, 970D,	0-1-12 0-5-13 2-1-10 0-5-9 2-9-0 0-0-6 0-2-0
5. 3776	1947	Do.	Diagram at the state of the sta			971B, 976A, 532D, 533, 579A.	1-10-4 2-4-0 0-5-10 2-0-8
۷.۱۹۰		Б0.	Do	Do.	••	1214A, 1217A, 1218A, 1218B, 1212, 1213, 1215	3-9-6 Cawnies
. 3777	1947	Do.	Do.	Do.		1216, 1221 1212, 1213, 1215,	
						1216, 1214A, 1217, 1218A, 1219B,	6-6-10 Cawnies 3-9-6 Cawnies
		Sowcarpet, Re District of Ma	egistration dras	Do.	(O.S. No. 695, 742) 10168/2 and	House No. 2/500 Mint Street,	1,397 Sq. ft.
		North Madras	3.6.1		10170	P.T. Ms.	
1606	1950		e se	Do.	(O.S. No. 2506) R.S. No. 3376	House No. 117, Lingi Chetty St., G.T. Ms.	1,331 Sq. ft.
909		Thiruvanmiyur		Do.		1214, 1217, 1218, 1219B	2-9-0 Cawnies
203	1961	Do.	Do	Do.	, ' .	500	0-8-0 Cawnies 3 Grounds

All the buildings on the above lands, institutions, and all the assets whatsoever including Bank balances and cash of the Kalakshetra and Besant Centenary Trust/Hostel in the City of Madras.

K. L. MOHANPURIA, Secy. to the Govt. of India.



		1 (2)			PART	В			
Sl. No.	Document No.	Year	Village	Taluk	District	Survey No.	Paimash No.	Extent	
1.	448	1881	Thiruvanmi- yur	Saidapet	Chinglepet		977, 1212, 1213, 1214, 1215, 1216, 1217, 1218, 1219 and 1221		Cawnies
2.	1224	1908	Do.	Do.	Do.		968C	2-0-8	Cawnies
3.	2382	. 1913	Do.	Do.	Do.		967, 968C	2-0-8	Cawnies
4.	2559	1913	Do.	Do.	Do.		967, 968	2-0-8	Cawnies
5.	4544	1919	Do.	Do.	Do.		532D, 533, 534	3-7-8	Cawnies
6.	2642	1920	Do.	Do.	Do.		967, 968, 968C	4-1-0	Ca wnies/
7.	1325	1927	Do.	Do.	Do.	**	533, 534, 532	3-7-8	Cawnies .
8.	1966 -	1940	Do.	Do.	Do.		976A, 971B	2-2-0	Cawnies
9.	2056	1941	Do.	Do.	Do.		984	0-4-6	Cawnies
10.	2194	1941	Do.	Do.	Do.		984	0-4-6	Cawnies
11.	532	1943	Do.	Do.	Do.		976A, 971B	2-2-0	Cawnies
12.	1471	1943	Do.	Do.	Do.		976A, 971B	6-2-0	Cawnies
13.	1380	1937	Do.	Do.	Do.		191	1-4-0	Cawnies
14.	1381	1937	Do.	Do.	Do.		191	1-4-0	Cawnies
15.	1032	1945	Do.	Do.	Doj		532, 534	3-7-8	Cawnies
16.	1744	1929	es es e						
				* · ·					
	(Parent docum	nent of I	tem 15)		3	-			4
17.	1134	1945	Do.	Do.	Do.		984, 984	0-4-6 0-4-6	Cawnies Cawnies
18.	1224	1945	Do.	Do.	Do.	, · · ·	971 B , 976A	6-2-0	Cawnies
19.	1268	1945	Do.	Do.	Do.		970B, 970D	2-8-0	Cawnies
20.	1598	1945	Do.	Do.	Do.	••	967, 968, 968C	4-1-0	Cawnies
21.	1941	1945	Do.	Do.	Do.	••	1226A/1 1226B/1	0-5-15	Cawnies
22.	1942	1945	Do.	Do.	Do.		1226B/2	0-15-13	Cawnies
23.	1988	1945	Do.	Do.	Do.		976B, 979A	2-6-0	Cawnies
24.	353	1947	Do.	Do.	Do.	••	976A/1	3-0-0	Cawnies
					/			//	

199

No.	Document No.	Date	Village	Taluk	District	Survey No	o. Paimash No.	Extent
13.	1865	2-9-52	Thiruvan- miyur	Saidapet	Chinglep	et	1228	0-3-8
				*				1-8-4
14.	621	27-3-59	Do.	Do.	Do.	••	973-В 972	-1 acre 98 cents 0-7-0 5-7-0
			*			e v	961-C/1 961-L 964	0-3-4 0-9-10 2-5-2
15.	769	12-5-54	Do.	D-				9-0-0 Cawnie -12 acres
6.	2053	24-8-56		Do.	Lo.	••	1219 1224	50 Cents
17.			Do.	Do.	Do.		979-C	1-11-14 Cawnies
8	2151	3-9-56	Do.	Do.	Do.		974/A	2-0-0 Cawnies -2 acres 66 cents
0	863	April, 1960	Do.	Do.	Do.	158/1	882-B 882-D 886-D	
							957-A 958-A 963-A	
						8 9	964 886-C 964 Part	
						170/1	964 Part 975 C Part	21 acres 6 cents
			*			170/3	975J 973A 973A 1	
		a :#4			•		973A 2	
			e gi			eas a	975G 975H 975-I 975M 975G	
						9	975G 975H 2 975K	
•	291	6-2-63 ·	Do.	Do.	Do.	166/2	957-B 962 963-B	22 acres approximately
		•				24.	966 968-C	7 20 77
	754 2	2-3-63	Do.	Do.	Do.	161/2	857 882-C (Part)	27 acres 74 cents approximately
							877-A 940 941 942	
							955-A 965 961H	
1	481 A	pril, 1968	Do.	Do.	Do.	178/3 (Part) 178/8	1212 1214 1184	4 grounds 1988 Sq. ft.
	403					8	1185 1220	e-
. 1	482 A	pril, 1968	Do.	Do.	Do.	178/3 178/8	Do.	8 grounds 96 Sq. ft.

All the buildings on the above lands, institutions, all assets whatsoever including Bank balances and cash of the Kalakshetra

THE FIRST SCHEDULE

[See clause (d) of section 3]

- 1. Kalakshetra College of Fine Arts.
- 2. Craft Education and Research Centre consisting of-
 - (i) a Weaving Department, and
 - (ii) a Kalamkari unit.
- 3. Besant Arundale Theosophical Senior Secondary School.
- 4. Besant Theosophical High School.
- 5. Besant Cultural Centre Hostel.

THE SECOND SCHEDULE

(See section 4)

PART A

Sl. D No.	No.	Date	Village	Taluk	District	Survey No.	Paimash No.	Extent	-
1.	1541	16-8-49	Thiruvan- miyur	Saidapet	Chinglepet	•	1225/A 1228	0-3-8 1-8-4	-
								1-11-12	Cawnies
2,	1542	16-8-49	Do.	Do.	Do.		1227/E	0-9-0 0-75	Cawnies Cents
3.	1543	16-8-49	Do.	Do.	Do.	•••		0-3-12 0-6-2	
4.	768	12-5-54	Do.	Do.	Do.		1219 1224	0 3-12 0 -6-2	
	(In recti	fication of Sl.	, :			•		•	
5.		16-8-49	Do.	Do.	Do.	Y	947-C 1226-C 1226-D	0-11-0 0-6-0 0-12-0	*
			÷	(4)				1-13-0	
6.	1605	25-8-49	Do.	Do.	Do.	, "	1228 B 1226 A 1226 C/1	0-6-10 0-55	Cawnies Cents
7.	1960	13-10-49	Do.	Do.	Do.		1227/D	0-3-12	Cawnies
8.	1984	15-10-49	Do.	Do.	Do.		1227/F	0-5-8	Cawnies
9.	1324	26-11-49	Do.	Do.	Do.	O.S. No. 327 R.S. No. 528	House and Groun No. 18, Andiappa Gramani Street, Royapuram-13.		q. ft.
10.	1324	26-11-49	Do.	Do.	Do.	,	1229/C	0-10-0 -1 acre	Cawnies 14 Cents
11.	2752	11-12-50	Do.	Do,	Do.		1219/A-3 1224/D	0-3-12 55	Cawnies Cents
12.	2759	21-12-50	Do.	Do.	Do.	1	1219	0-3-12 -50	Cawnies Cents

- (e) the maintenance of accounts, registers and other records of the Foundation.
- (3) No regulation made by the Foundation shall have effect until it has been approved by the Central Government and published in the Official Gazette, and the Central Government, in approving the regulation, may make changes therein which appear to it to be necessary.

Rules and regulations to be laid before Parliament. 33. Every rule and every regulation made under this Act shall be laid, as soon as may be after it is made, before each House of Parliament, while it is in session for a total period of thirty days which may be comprised in one session or in two or more successive sessions, and if, before the expiry of the session immediately following the session or the successive sessions aforesaid, both Houses agree in making any modification in the rule or regulation, or both Houses agree that the rule or regulation, should not be made, the rule or regulation shall thereafter have effect only in such modified form or be of no effect, as the case may be; so, however, that any such modification or annulment shall be without prejudice to the validity of anything previously done under that rule or regulation.

Power to remove difficultits. 34. (1) If any difficulty arises in giving effect to the provisions of this Act, the Central Government may, by order, not inconsistent with the provisions of this Act, remove the difficulty:

Provided that no such order shall be made after the expiry of a period of two years from the commencement of this Act.

(2) Every order made under this section shall be laid as soon as may be after it is made, before each House of Parliament.

Repeal and saving. 35. (1) The Kalakshetra Foundation Ordinance, 1993 is hereby repealed.

Ord. 30 of 1993.

(2) Notwithstanding such repeal, anything done or any action taken under the Ordinance so repealed, shall be deemed to have been done or taken under the corresponding provisions of this Act.



30. Every Member of the Governing Board, Academic Committee and the Finance Committee and the Director of the Foundation shall be indemnified by the Foundation against all losses and expenses incurred by them in relation to the discharge of their duties, except such as are caused by their wilful act or default.

Indemnity.

31. (1) The Central Government may, by notification, make rules for carrying out the provisions of this Act.

Power to make rules.

- (2) In particular, and without prejudice to the generality of the foregoing power, such rules may provide for all or any of the following matters, namely:—
 - (a) the allowances to the Members under sub-section (5) of section 12;
 - (b) the powers which the Governing Board shall exercise and the functions which it shall discharge under sub-section (2) of section 14;
 - (c) functions to be performed by the Finance Committee, under clause (iv) of section 18;
 - (d) the salary and allowances and other terms and conditions of service of the Director under sub-section (3) of section 19;
 - (e) the form and the manner in which the budget is to be prepared by the Governing Board under section 23;
 - (f) the form and the manner in which, and the time at which, the returns, statements and the annual report shall be prepared under section 25;
 - (g) any other matter which has to be, or may be, prescribed.
- 32. (1) The Foundation may make regulations, not inconsistent with this Act and the rules made thereunder, for enabling it to discharge its functions under this Act.

Power to make regulations.

- (2) Without prejudice to the generality of the foregoing power, such regulations may provide for all or any of the following matters, namely:—
 - (a) the management of the properties and funds, affairs and works of the Foundation;
 - (b) the procedure in regard to transaction of business of the Governing Board and the Academic Committee (including quorum at their meetings) and the transaction of business of the Finance Committee under sub-section (3) of section 13, sub-section (3) of section 15 and sub-section (2) of section 17;
 - (c) creation or abolition of posts and the procedure for appointment of the professional, administrative and ministerial staff;
 - (d) the tenure of office and other terms and conditions of the members of the Academic Committee under sub-section (2) of section 15; and

CHAPTER V

MISCELLANEOUS

Prior approval of the Central Government for alienation of property.

26. The Foundation shall not, except with the previous approval of the Central Government, sell or otherwise dispose of any property vested in the Foundation.

Power of Central Government to give directions to the Foundation.

- 27. (1) The Central Government may, if it is satisfied that it is necessary so to do in the public interest, issue, for reasons to be recorded and communicated to the Foundation, such directions as it thinks fit.
- (2) Without prejudice to the generality of the foregoing powers, such directions may include directions requiring the Foundation—
 - (a) to make or amend any regulation within such period as may be specified in the direction; and
 - (b) to give priority to the work undertaken or to be undertaken by the Foundation in such manner as the Central Government may think fit to specify in this behalf.
- (3) Any direction issued under this section shall have effect notwithstanding anything contained in any law for the time being in force or in the memorandum or regulations of the Kalakshetra Society.

Dissolution of the Foundation. 28. (1) The Central Government may, by notification and for reasons to be specified therein, dissolve, the Foundation from such date and for such period as may be specified in the notification:

Provided that before issuing any such notification, the Central Government shall give a reasonable opportunity to the Foundation to make representation against the proposed dissolution.

- (2) When the Foundation is dissolved under sub-section (1),-
- (a) all members of the Governing Board, Academic Committee and the Finance Committee, notwithstanding that the terms of their office had not expired, shall, from the date of dissolution, vacate their offices as such members;
- (b) all powers and duties of the Governing Board, Academic Committee and the Finance Committee shall, during the period of dissolution, be exercised and performed by such person or persons as the Central Government may appoint in this behalf;
- (c) all properties and assets vested in the Foundation shall, during the period of dissolution, vest in the Central Government; and
- (d) as soon as the period of dissolution expires, the Foundation shall be reconstituted in accordance with the provisions of this Act.

Protection of action taken in good faith.

29. No suit prosecution or other legal proceeding shall lie against the Central Government or any officer of that Government or the Foundation or Member or Director or any officer of the Foundation for anything which is in good faith done or intended to be done under this Act.

- (3) The Foundation may spend such sums as it may think fit for performing its functions under this Act, and such sums shall be treated as expenditure payable out of the Fund of the Foundation.
- 23. The Foundation shall prepare, in such form and at such time each year, as may be prescribed, the budget in respect of the financial year next ensuing showing the estimated receipts and expenditure, and copies thereof shall be forwarded to the Central Government.

Budget.

24. (1) The Foundation shall maintain proper accounts and other relevant records and prepare an annual statement of accounts including the balance sheet in such form as may be approved by the Comptroller and Auditor-General of India.

Accounts and audit of the Foundation

- (2) The accounts of the Foundation shall be audited by the Comptroller and Auditor-General of India and any expenditure incurred by him in connection with such audit shall be payable by the Foundation to the Comptroller and Auditor-General of India.
- (3) The Comptroller and Auditor-General of India and any person appointed by him in connection with the audit of the accounts of the Foundation shall have the same rights, privileges and authority in connection with such audit as the Comptroller and Auditor-General of India has in connection with the audit of the Government accounts, and, in particular, shall have the right to demand the production of books, accounts, connected vouchers and other documents and papers and to inspect the office of the Foundation.
- (4) The accounts of the Foundation as certified by the Comptroller and Auditor-General of India or any person appointed by him in this behalf together with the audit report thereon shall be forwarded annually to the Central Government and that Government shall cause the same to be laid before each House of Parliament.
- 25. (1) The Foundation shall furnish to the Central Government at such time and in such form and in such manner, as may be prescribed, or as the Central Government may direct, such returns and statements and such particulars in regard to any proposed or existing programme for the promotion and development of the objects of the Foundation, as the Central Government may, from time to time, direct.

Duty to furnish returns, annual reports, etc.

- (2) Without prejudice to the provisions of sub-section (1), the Foundation shall, as soon as possible after the end of each financial year, submit to the Central Government an annual report in such form and before such date as may be prescribed, giving a true and full account of its activities and programmes during the previous year.
- (3) A copy of the report received under sub-section (2) shall be laid, as soon as may be, after it is received, before each House of Parliament,

- (iii) review the financial position of the Foundation from time to time and have an internal audit conducted; and
 - (iv) perform such other functions as may be prescribed.

Appointment and duties of Director.

- 19. (1) The Central Government shall, by notification, appoint a Director who shall be the principal executive officer of the Foundation and who shall be responsible for the proper administration of the affairs of the Foundation and its day-to-day management and shall exercise such other powers and perform such other duties as may be assigned to him by the Governing Board.
- (2) The Director shall prepare the annual statement of accounts and budget estimates of the Foundation for scrutiny by the Finance Committee.
- (3) The Director shall be a whole time employee of the Foundation and shall be entitled to such salary and allowances out of the Fund and shall be subject to such conditions of service in respect of leave, pension, provident fund and other matters, as may be prescribed.

Transfer of service of exising employees. 20. On and from the appointed day, every officer or other employee, employed immediately before the appointed day in connection with the affairs of Kalakshetra shall become an officer or other employee of the Foundation and shall hold office by the same tenure and remuneration and on the same terms and conditions as to pension, gratuity and other matters as he would have held under the Board of Trustees or any other body, in whatever, capacity, if this Act had not been passed and shall continue to do so, unless and until his employment in the Foundation is terminated or until his tenure, remuneration and other terms and conditions are duly altered by the Foundation:

Provided that the tenure, remuneration and other terms and conditions of service of any such officer or employee shall not be altered to his disadvantage without the previous approval of the Central Government.

CHAPTER IV

FINANCE, ACCOUNTS AND AUDIT

Grants by Central Government to the Foundation.

21. For the purpose of enabling the Foundation to discharge its functions efficiently under this Act, the Central Government may, after due appropriation made by Parliament by law in this behalf, pay to the Foundation in each financial year, such sums of money, on such terms and conditions as that Government may determine, by way of grant, loan or otherwise.

Fund of the Foundation.

- 22. (1) The Foundation shall have its own Fund; and all sums which may, from time to time, be paid to it by the Central Government and all receipts of the Foundation (including any sum which the State Government or any other authority or person may pay to the Foundation) shall be credited to the Fund and all payments by the Foundation shall be made therefrom.
- (2) All moneys belonging to the Fund shall be deposited in such banks or invested in such manner as may, subject to the approval of the Central Government, be decided by the Governing Board.

- 14. (1) The Governing Board shall be the supreme authority of the Foundation and the general superintendence, direction and management of the affairs of the Foundation shall vest in the Governing Board.
- (2) The Governing Board shall exercise such powers and discharge such functions as may be prescribed.
 - 15. (1) The Academic Committee shall consist of-
 - (a) the Director;
 - (b) the Heads of the constituent units;
 - (c) three distinguished persons in the field of art and culture including dance, music, folk arts and crafts, to be nominated by the Central Government; and
 - (d) one person to be nominated by the State Government, representing the Department of Education of that Government.
- (2) The tenure of office and other terms and conditions of the members of the Academic Committee shall be such as may be specified by regulations.
- (3) The Academic Committee shall observe such procedure in regard to the transaction of its business at its meetings (including the quorum at the meetings) as may be specified by regulations.
- 16. The Academic Committee shall be responsible for the maintenance of standards of education, training and examination conducted by the constituent units and shall exercise such other powers and perform such other functions as may be assigned to it, from time to time, by the Governing Board.
 - 17. (1) The Finance Committee shall consist of-
 - (a) the Financial Adviser to the Government of India or his nominee in the Ministry of the Central Government dealing with culture:
 - (b) an officer of the Central Government, not below the rank of a Deputy Secretary, to be nominated by that Government;
 - (c) an officer of the State Government not below the rank of a Deputy Secretary, to be nominated by that Government, representing the Department of Finance of that Government; and
 - (d) the Director.
- (2) The Finance Committee shall observe such procedure in regard to the transaction of the business at its meetings as may be specified by regulations.
 - 18. The Finance Committee shall—
 - (i) scrutinise the annual statement of accounts and budget estimates of the Foundation prepared by the Director and make recommendations to the Governing Board;
 - (ii) prescribe the limits of the recurring and non-recurring expenditure of the Foundation for each financial year;

Governing Board to be the supreme authority of Foundation.

Academic Committee.

Powers and functions of Academic Committee.

Finance Committee.

Powers and functions of Finance Committee.



- (c) two persons, possessing one or more of the qualifications referred to in sub-clauses (i) to (iv) of clause (b), to be nominated by the State Government;
- (d) two officers of the Central Government, not below the rank of a Deputy Secretary, to be nominated by that Government, to represent the Ministry of the Central Government dealing with culture, ex officio;
- (e) one officer of the State Government, not below the rank of Joint Secretary, to be nominated by that Government, to represent the Department of Education of that Government, ex-officio; and
 - (f) the Director, ex officio.

Term of office of Members.

- 12. (1) The term of office of the Members shall be five years from the date of constitution of the Governing Board.
- (2) If a casual vacancy occurs in the office of a Member nominated under clause (b) or clause (c) of section 11, whether by reason of his death, resignation or inability to discharge his functions owing to illness or other incapacity, such vacancy shall be filled by making fresh nomination and the Member so nominated shall hold office for the remainder of the term of office of the Member in whose place he is so nominated.
 - (3) An outgoing Member shall be eligible for re-nomination.
- (4) A Member may resign his office by writing under his hand addressed to the Central Government but shall continue in office until his resignation is accepted by that Government.
- (5) The Members nominated under clauses (b) and (c) of section 11, shall be entitled to such allowances as may be prescribed.

Meetings of Governing Board.

- 13. (1) The Governing Board shall meet at least twice in a year at Madras at such time as may be fixed by the Chairperson of the Governing Board.
- (2) All decisions at the meeting of the Governing Board shall be taken by majority of the Members present and voting:

Provided that in the case of equality of votes the Chairperson of the Governing Board shall have a casting vote.

- (3) The Governing Board shall observe such procedure in regard to the transaction of its business at its meetings (including the quorum at its meetings) as may be specified by regulations.
- (4) No act or proceeding of the Governing Board shall be invalid merely by reason of—
 - (a) any vacancy in, or any defect in the constitution of, the Governing Board; or
 - (b) any defect in the nomination of a person acting as a Member of the Governing Board; or
 - (c) any irregularity in the procedure of the Governing Board not affecting the merits of the case.

CHAPTER III

KALAKSHETRA FOUNDATION

- 8. (1) With effect from such date as the Central Government may, by notification, appoint in this behalf there shall be established a Foundation to be called the Kalakshetra Foundation.
- (2) The Foundation shall be a body corporate by the name aforesaid, having perpetual succession and a common seal, with power to acquire, hold and dispose of property, both movable and immovable, and to contract and shall by the said name sue and be sued.
- (3) The office of the Foundation shall be located at Thiruvanmiyur, Madras.
 - 9. The objects of the Foundation shall be,-
 - (i) to emphasise the essential unity of all true arts;
 - (ii) to work for the recognition of the arts as vital to the individual, national and international growth;
 - (iii) to maintain the highest traditions of art and culture their pristine purity and in conformity with traditions;
 - (iv) to arrange for the training, research, study, teaching and development of art and science, music, dance-drama, fine arts and Bharat-Natyam; and
 - (v) to ensure that the principles of "education without fear" and "art without vulgarity" are adhered to in the activities of the Foundation and not to permit any deviation from these high ideals.
- 10. (1) The Foundation shall consist of the following authorities, namely:-
 - (a) the Governing Board;
 - (b) the Academic Committee; and
 - (c) the Finance Committee.
- (2) In the discharge of functions and exercise of powers under this Act, the authorities referred to in sub-section (1) shall be guided by the objects specified in section 9.
 - 11. The Governing Board shall consist of-
 - (a) a Chairperson, who shall be a person of high eminence in public life, to be appointed by the Central Government;
 - (b) not more than twelve Members to be nominated by the Central Government from amongst persons who-
 - (i) have rendered valuable service to Kalakshetra;
 - (ii) have been connected with, or have knowledge of art, culture, folk arts and crafts;
 - (iii) are eminent artistes; and
 - (iv) are patrons of art and culture;

Establishment and incorporation of Foundation.

The obejct of foundation.

Authorities of the Founda-

The Governing



(4) If, on the commencement of this Act, any suit, appeal or other proceeding of whatever nature in relation to any assets or properties which have vested in the Central Government under section 4, instituted or preferred by the Board of Trustees is pending, the same shall not abate, be discontinued or be, in any way, prejudicially affected by reason of such transfer and vesting, or of anything contained in this Act, but the suit, appeal or other proceeding may be continued, prosecuted or enforced, by the Central Government or where the right, title and interest in relation to such assets and properties are directed under section 6 to vest in the Foundation, by the Foundation.

Central
Government to
direct
vesting
of assets
and properties in
the Foundation.

- 6. (1) Notwithstanding anything contained in sections 4 and 5, the Central Government shall direct, by notification, that the right, title and interest in relation to the assets and properties of Kalakshetra, which had vested in it under section 4, shall vest in the Foundation on such date, not being a date earlier than the date of commencement of this Act, as may be specified in the notification.
- (2) On and from the date of vesting of the right, title and interest in relation to the assets and properties of Kalakshetra in the Foundation under sub-section (1),—
 - (a) the Foundation shall be deemed to have become the owner of the assets and properties; and
 - (b) the rights and liabilities of the Central Government, in relation to such assets and properties shall be deemed to have become the rights and liabilities respectively of the Foundation.

Duty of persons to deliver and to account for assets, properties, etc. /

- 7. (1) On the vesting in the Central Government of the assets and properties of Kalakshetra, all persons in charge of the management of the said assets and properties immediately before the date of such vesting, shall be bound to deliver to the Central Government or to the Foundation or to such person or body of persons as the Central Government or the Foundation may specify in this behalf, all assets, properties, books of account, registers or other documents in their custody relating to the assets and properties of Kalakshetra.
- (2) Every person who has, in his possession or control any assets, properties, books, documents or other papers relating to Kalakshetra which have vested in the Central Government or the Foundation under this Act, and which belong to Kalakshetra or would have so belonged if Kalakshetra had not vested in the Central Government or the Foundation, shall be liable to account for the said assets, properties, books, documents and other papers to the Central Government or the Foundation, as the case may be, and shall deliver them up to the Central Government or the Foundation or to such person or body of persons as the Central Government or the Foundation may specify in this behalf.
- (3) The Central Government shall take or cause to be taken all necessary steps for securing possession of assets and properties of Kalakshetra which have vested in it under section 4.

CHAPTER II

ACQUISITION AND TRANSFER OF THE ASSETS AND PROPERTIES OF KALAKSHETRA

4. On the commencement of this Act, the right, title and interest in relation to the assets and properties of Kalakshetra specified in the Second Schedule and vested in the Board of Trustees or any other body, in whatever capacity, shall stand transferred to, and vest in, the Central Government.

Transfer to, and vesting in, the Central Government of the assets and properties of Kalakshetra.

General effect of vesting

- 5. (1) The right, title and interest vested in the Central Government under section 4 shall be deemed to include all the assets, rights, leaseholds, powers, authorities, licences and privileges; all property (movable and immovable) including lands and buildings; musical instruments; equipments used in teaching, training and staging of performing arts; tools and facilities used in arts and crafts; costumes and decorative items; books; stationery, furniture and other equipments used in libraries and laboratories; works of art and artefacts; stores, automobiles and other vehicles; workshops; cash balances, funds including reserve funds, investments and all other rights and interests arising out of such assets and properties as were immediately before the commencement of this Act the possession, ownership, power or control of the Board of Trustees or any other body, in whatever capacity, and all books of account, registers, maps, plans and all other documents of whatever nature relating thereto.
- (2) All assets and properties as aforesaid which have vested in the Central Government under section 4 shall, by force of such vesting, be freed and discharged from any trust, obligation, mortgage, charge, lien and all other encumbrances affecting them or of any attachment, injunction, decree or order of any court or other authority restricting the use of such assets or properties in any manner, or appointing any receiver in respect of the whole or any part of such assets and properties shall be deemed to have been withdrawn.
- (3) Any licence, permission, authority, concession, facility, privilege, affiliation or any other instrument of similar nature granted to the Board of Trustees or any other body, in whatever capacity, in relation to the assets and properties of Kalakshetra or any of its constituent units which has vested in the Central Government under section 4, at any time before the commencement of this in force immediately before Act and such commencement, shall continue to be in force on and after such commencement in accordance with its tenor in relation to, and for purposes of, such assets and properties, or where the direction under section 6 has been issued, the Foundation shall be deemed to be substituted in such licence, permission, authority, concession, facility, privilege, affiliation or other instrument, as if it had been granted to the Foundation and the Foundation shall hold it for the remainder of the period for which the Board of Trustees or any other body, in whatever capacity, would have held it under the terms thereof.

Declaration of Kalakshetra as an institution of national importance. 2. Whereas the objects of the institution known as Kalakshetra at Adyar, Madras in the State of Tamil Nadu, founded by the late Thirumathi Rukmini Devi Arundale, are such as to make the institution one of national importance, it is hereby declared that the institution known as Kalakshetra is an institution of national importance.

Definitions.

- 3. In this Act, unless the context otherwise requires,-
- (a) "Academic Committee" means the Academic Committee constituted under section 15;
- (b) "appointed day" means the date on which the Foundation is established under sub-section (1) of section 8;
- (c) "Board of Trustees" means the Board of Trustees managing the affairs of Kalakshetra under the 'scheme writ' approved by the Madras High Court in petition No. 716 of 1985;
- (d) "constituent units" means the units of Kalakshetra specified in the First Schedule;
- (e) "Director" means the Director appointed under sub-section (1) of section 19;
- (f) "Finance Committee" means the Finance Committee constituted under sub-section (1) of section 17;
- (g) "Foundation" means the Kallakshetra Foundation established under sub-section (1) of section 8;
- (h) "Fund" means the Fund of the Foundation referred to in section 22;
- (i) "Governing Board" means the Governing Board constituted under section 11;
- (j) "Kalakshetra" means the institution known as Kalakshetra founded by the late Thirumathi Rukmini Devi Arundale, situated at Adyar, Madras, and includes its constituent units;
- (k) "notification" means a notification published in the Official Gazette;
- (l) "Member" means a Member of the Governing Board and includes the Chairperson thereof;
- (m) "prescribed" means prescribed by rules made under this Act;
 - (n) "regulations" means regulations made under section 32;
 - (0) "Schedule" means a Schedule annexed to this Act;
 - (p) "State Government" means the Government of Tamil Nadu.





असाधारण EXTRAORDINARY

भाग II—खण्ड 1 PART II—Section 1

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं॰ 6] नई दिल्ली, मंग्लवार, जनवरी 4, 1994/पौष 14, 1915 No. 6] NEW DELHI, TUESDAY, JANUARY 4, 1994/PAUSA 14, 1915

इस भाग में भिन्न पृष्ठ संख्या दी जाती है जिससे कि यह प्रलग संकलन के रूप में रखा जा सके । Separate paging is given to this Part in order that it may be filed as a separate compilation

MINISTRY OF LAW, JUSTICE AND COMPANY AFFAIRS

(Legislative Department)

New Delhi, the 4th January, 1994/Pausa 14, 1915 (Saka)

The following Act of Parliament received the assent of the President on the 4th January, 1994, and is hereby published for general information:—

THE KALAKSHETRA FOUNDATION ACT, 1993

No. 6 of 1994

[4th January, 1994.]

An Act to declare Kalakshetra of Madras to be an institution of national importance, to provide for the establishment and incorporation of a Foundation for its administration, to make provisions for further development of Kalakshetra in accordance with the aims and objects for which Kalakshetra was founded and for matters connected therewith or incide tal thereto.

BE it enacted by Parliament in the Forty-fourth Year of the Republic of India as follows:—

CHAPTER I

PRELIMINARY

- 1. (1) This Act may be called the Kalakshetra Foundation Act, 1993.
- (2) It shall be deemed to have come into force on the 29th day of September, 1993.

Short title and commencement.

163

DRAFT FOR APPROVAL PLEASE

To,

The Assistant Engineer,

Tamil Nadu Generation and Distribution Corporation,

Shastri Nagar,

Adyar,

Chennai- 600 041.

Sir,

Sub: Shifting of pillar box- requested.

Ref: Feeder Pillar no P 149 B to P149c.

We request you to kindly arrange to shift pillar box 149 B to P149 C which is presently located near Koothambalam, as we propose to develop the landscaping area in and around Koothambalam to facilitate public movement.

The necessary amount for shifting will be paid on hearing from you.

Yours faithfully,

Leela Samson,

Director.

Encl: i. Copy of existing EB service meter card, ___ P139 - P141) c

ii. Kalakshetra Foundation Act, 1993 detailing area of ownership. - P149/c (P142-P1431c)



- Copy of the existing EB service meter card for new enhancement P = 139,140,141
- Ownership documents for New CT meter connection. Kalakshetra Foundation Act 1993
 P – 142 - 149
- Covering letter for shifting of Existing feeder pillar box (Draft letter is enclosed herewith)

 P 150
- A necessary implementation charge (As soon as receipt of advice for TNEB) has to be paid by the Kalakshetra Foundation.

The job for shifting the DB pillar and disconnection of above said electrical supply, restoration of all the electrical supply would take 3 to 7 days. The alternate source of electrical supply will be arranged above said locations except Rukmini arangam/Koothambalam by our electrician with the available connection with back feeding.

As a first step, the application for shifting the DB pillar box and connected service connections to the Electricity board may be submitted with the required documents for this work. The draft letter along with enclosure required is submitted for approval.

p150/c

J. Rame Solners

CAÓ

The dright letter to approve theore.

TNGDE MOY PING

Deputy Director

3/1/11

Director

Culal 3/1 29/710

(165)



C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Kootha	mbalam\ December 28, 2010
Electricl installation work.doc	

Sub: Koothambalam – Electrical Installation work in Kalakshetra Foundation – Shifting of Distribution Pillar Electrical box – Expenditure and Approval of – reg.

Ref: Email from M/s.Kevin Electricals pvt ltd dated Dec 27, 2010.

P - 136

The work of Electrical installation at Koothambalam in Kalakshtra Foundation was awarded to M/s.Kevin Electricals Pvt Ltd, Engineers and Government Licensed A grade Contractors, Adyar, Chennai 600 020, at a total cost of Rs.49,08,773.29/-(Rupees forty nine lakh eight thousand seven hundred seventy three and paise twenty nine only)

page 107 €108

The following electrical service connections have been connected from the koothambalam distribution pillar box No. 149 C/ TNEB and details are

Sl.No	Service area	EB Service No.
1	To Pump house (for koothambalam well motor)	202-27-95
2	To Koothambalam, Rukmini arangam and Tagore hall	202-27-94
3	To Four room cottage, all class rooms in CFA	202-27-198

Page 139 Page 141 Page 140

It is proposed to undertake the development work for landscaping work from koothambalam structure profile about 30 metre distance. With in this area the present toilet block, hexagonal block and above said TNEB distribution box (much nearer the Koothambalam area) is falling in the location. Hence the proposal of the shifting of TNEB distribution pillar box from Koothambalam area into appropriate location (close to the RR masonry wall as shown by the Director) in the campus is submitted.

Meanwhile, the exact location and orientation of HVAC plant area; Diesel Generator and Electrical room for the koothambalam and proposed transformer location layout was requested to furnish the drawing with the Consulting Architect M/s.CARD /Ravi Niilakantan and his associates' Electrical consultant (M/s.Madras Electrical Consultants). The reply is awaited from them.

Pupe 138

In this connection, the contractor M/s.Kevin Electricals who is the electrical contractor for the Koothambalam work, has sent the email and requested to give the copy of the following for proceeding the job with TNEB office / Sastri Nagar / Adyar.

Pige 136

.....2





To,

03 January 2011

The Assistant Engineer,

Tamil Nadu Generation and Distribution Corporation,

Shastri Nagar,

Adyar,

Chennai- 600 041.

Sir,

Sub: Shifting of pillar box- requested.

Ref: Feeder Pillar no P 149 B to P149 C.

We request you to kindly arrange to shift pillar box 149 B to P149 C which is presently located near Koothambalam, as we propose to develop the landscaping area in and around Koothambalam to facilitate public movement.

The necessary amount for shifting will be paid on hearing from you.

Yours faithfully,


Leela Samson,

Director.

Encl: i. Copy of existing EB service meter card,

ii. Kalakshetra Foundation Act, 1993 detailing area of ownership.





Kalakshetra Foundation

755

To,

03 January 2011

The Assistant Engineer,

Tamil Nadu Generation and Distribution Corporation,

Shastri Nagar,

Adyar,

Chennai- 600 041.

Sir,

Sub: Shifting of pillar box-requested.

Ref: Feeder Pillar no P 149 B to P149 C.

We request you to kindly arrange to shift pillar box 149 B to P149 C which is presently located near Koothambalam, as we propose to develop the landscaping area in and around Koothambalam to facilitate public movement.

The necessary amount for shifting will be paid on hearing from you.

Yours faithfully,

Leela Samson,

Director.

Encl: i. Copy of existing EB service meter card,

ii. Kalakshetra Foundation Act, 1993 detailing area of ownership.

P. SARAVARALY

Founder: Smt Rukmini Devi Chairman: Justice Sri S. Mohan Director & Secretary: Ms. Leela Samson



E-mail: admin@kalakshetra.in Phone: +91-(0)44-24520836/4057/1844 Fax: +91-(0)44-24524359





layout and orientation of HVAC plant - reg.

Works kalakshetra <works@kalakshetra.in>

Tue, Jan 11, 2011 at 10:38 AM

To: ravi <card@vsnl.com>

Cc: "j.ra.jayakumar jayaramanradhabai" <jrajayakumar27@gmail.com>, mecramesh@eth.net

Dear sir.

The application for shifting of EB pillar box near the Koothambalam was submitted by the M/s.Kevin electricals after all paper required and obtained from the Kalakshetra.

the exact location and orientation of HVAC plant, Diesel Generator room and proposed transformer area layout may be furnished to office for approval before shifting the EB pillar box.

warm regards . V.Srinivasan

[Quoted text hidden]



157



Works kalakshetra <works@kalakshetra.in>

layout and orientation of HVAC plant - reg.

Works kalakshetra <works@kalakshetra.in>

Tue, Dec 28, 2010 at 2:09 PM

To: ravi <card@vsnl.com>

Cc: ao@kalakshetra.in, CAO Kalakshetra <cao@kalakshetra.in>

Dear sir,

As decided that the shifting of EB pillar box near the koothambalam through the Electricity people is being organised. The location of shifting the pillar box is identified by the Director, and shown to the Mr.J.Ra.J and my self.

Meanwhile, the exact location and orientation of HVAC plant, Diesel Generator room and proposed transformer area layout may be furnished to office for approval before shifting the EB pillar box.

Kindly do the needful.

warm regards v.srinivasan





C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\ Electricl installation work.doc

Tuesday, February 01, 2011

Sub: Koothambalam electrical installation work - contract paper - signature of electrical consultant and Consulting Architect - Submission - Reg.

As per the instructions given by the Consulting Architect / M/s.CARD-Shri.Ravi Niilakanatan, the original tender document paper (page indicated 6, 7,8 and 29 to 105) was handed over to Shri.J.RA.Jayakumar /clerk of works for obtaining the signature from the electrical consultant - M/s. Madras Electrical Consultant and M/s.CARD/Shri.Ravi Niilakanatan with seal.

It is assured that the all the original with signature will be returned by tomorrow at the earliest.

Shri.J.Ra.Jayakumar Clerk of Works. Clerk of Works.





C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\
Electricl installation work.doc

Tuesday, February

O/ 01, 2011

Sub: Koothambalam electrical installation work – contract paper – signature of electrical consultant and Consulting Architect – Submission – Reg.

As per the instructions given by the Consulting Architect / M/s.CARD-Shri.Ravi Niilakanatan, the original tender document paper (page indicated 6, 7,8 and 29 to 105) was handed over to Shri.J.RA.Jayakumar /clerk of works for obtaining the signature from the electrical consultant – M/s. Madras Electrical Consultant and M/s.CARD/Shri.Ravi Niilakanatan with seal.

It is assured that the all the original with signature will be returned by tomorrow at the earliest.

Shri.J.Ra.Jayakumar Clerk of Works.

Swomford for approval preave

30)

11241

Document of 2/10





light fitting works - Koothamablam

Works kalakshetra <works@kalakshetra.in>
To: ravi <card@vsnl.com>

Tue, Feb 8, 2011 at 5:51 PM

o. ravi <card@\

Sir,

Kindly arrange to provide the light fitting layout drawings and estimation copy of the the work through electrical consultant at the earliest please.

the email or letter for refund of the EmD to the unsuccessful tender for the electrical work may be sent for further action please.

UPS tender paper with details for the koothambalam may be forwarded this office please.

warm regards

Kalakshetra Foundation



161



Works kalakshetra <works@kalakshetra.in>

Refund of EMD - reg.

Works kalakshetra <works@kalakshetra.in>

Thu, Feb 17, 2011 at 2:17 PM

To: ravi <card@vsnl.com>

Sir,

Please give your approval for refund the EMD for the following unsuccessful tenders for the Electrical installation work at Koothambalam.

1. M/s.K.K.Singh electricals

Rs. 57,000

2. M/s. Polar electricals

Rs.63,740

3. M/s.S.S.Electricals

Rs.68,000

Kalakshetra





IFSC Code - Reg

K.K.Singh Electricals < kksinghelectricals@gmail.com>

Wed, Feb 16, 2011 at 10:24 AM

To: works@kalakshetra.in

Dear Sir,

I hereby mentioned our IFSC details for your reference.

1 Name of Beneficiary K.K.SINGH ELECTRICALS

2 Address of Beneficiary # 3, NEW MARKET, WEST TAMBARAM

CHENNAI 600 045.

3 Name of Beneficiary's Bank The Karur Vysya Bank Limited,

Address of Beneficiary Bank Tambaram Branch,

West Tambaram,

Chennai - 600 045.

5 Beneficiary Bank's IFSC Code KVBL0001190

(mandatory 11 characters)

Account No. of Beneficiary

119011500005385


Thanking you,

Regards
G.Hari Kumar
K.K.Singh Electricals
Grade - A - Electrical Contractor
No. 3, New Market
West Tambaram
Chennai - 600 045.

Ph: 2226 6663, 2226 0939 Fax: 91 - 44 - 2226 4551. Mobile: 9884176667

E Mail: kksinghelectricals@gmail.com

kksinghele@gmail.com







IFSC code requested reg.

Works kalakshetra <works@kalakshetra.in>
To: sse078@hotmail.com, sse078@gmail.com

Thu, Feb 17, 2011 at 1:58 PM

Sir,

Kindly provide your banker details for transfer the EMD refund amount for the work of electrical installation work at Koothambalam in Kalakshetra Founation.

Name of the bank branch Account No. IFSC code no.

warm regards Kalakshetra

To SS elevisions







Refund of EMD - details requested -reg.

Works kalakshetra <works@kalakshetra.in>
To: sivapolarelectricals@gmail.com

Thu, Feb 17, 2011 at 3:09 PM

Sir,

Kindly provide your banker details for transfer the EMD refund amount for the work of electrical installation work at Koothambalam in Kalakshetra Founation.

Name of the bank branch Account No. IFSC code no.

warm regards Kalakshetra

To polar elamos



ELECTRICAL SERVICES

)1 Street, 15th Sector, K.K. Nagar, Chennai - 78.

044-43

Fax : 044-24 Mobile: 98408

: 98408

E-mail: sse078

18/01/2

5.S.ELECTRICALS SERVICES: -

PAN NO: - ABBFS0436L

SERVICE TAX NO: - ABBFS0436LST001

3ANK DETAILS: -

NAME OF THE BANK & BRANCH: - CORPORATION BANK, ASHOK NAGAR BRANCH.

TYPE OF ACCOUNT: - C.A

BANK ACCOUNT NAME: - S.S.ELECTRICAL SERVICES

BANK ACCOUNT NUMBER: -CA01000 257

SWIFT CODE: - CORP IN BB 122

IFSC CODE FOR RTGS TRANSFER: - CORPO00000578, CA01000257

IFSC CODE FOR NEFT TRANSFER: - CORPO00000578, CA01000257

FOR S.S.ELECTRICAL SERVICES

B.CHANDRA





Refund of EMD - details requested -reg.

Polar sivaprakasam <sivapolarelectricals@gmail.com> To: Works kalakshetra <works@kalakshetra.in>

Thu, Feb 17, 2011 at 3:19 PM

Dear Sir,

Name of the bank: Axis Bank branch : Ashok Nagar Account No. : 285010200001694 IFSC code no. :600211012

Regards. Meenakshi.E





Works kalakshetra <works@kalakshetra.in>

Refund of EMD - reg.

Ravi Nilakantan <card@vsnl.com>

Fri, Feb 18, 2011 at 10:27 AM

To: Works kalakshetra <works@kalakshetra.in>

Cc: director@kalakshetra.in, dd@kalakshetra.in, CAO Kalakshetra <cao@kalakshetra.in>

Dear Sri. Srinivasan,

You may please release all EMD's of unsuccessful bidders as soon as the WO is issued.

Please release the EMD's of unsuccessful Electrical tender listed below.

Regards,

Ravi niil

From: Works kalakshetra [mailto:works@kalakshetra.in]

Sent: Thursday, February 17, 2011 2:17 PM

To: ravi

Subject: Refund of EMD - reg.

[Quoted text hidden]



kalakshetra

C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\ February 17, 2011 Electricl installation work.doc

Sub: Koothambalam - Electrical Installation work in Kalakshetra Foundation - Refund of EMD amount - Approval of - reg.

The tenders for the above work was opened on 14.9.2010, opened tender documents were handed over to M/s.CARD on the same day. Based on Works Committee approval as recommended by M/s.CARD and his associates M/s.Madras electrical consultant the work | PV5-361 e was awarded to M/s.Kevin Electricals.

The Earnest Money Deposit (EMD) for the following unsuccessful tenderer for the work of Electrical installation at Koothambalam may be released through bank by NEFT /RTGS

Sl.N	Name of the	Amou	Remarks	Banker details
0	contractor	nt		
1	M/s.K.K.Singh	57,000	Paid Vide	Karur Vysya Bank Limited,
	electricals		R.No.121	Tambaram Branch, Chennai -45.
			dated	Bank's IFSC Code KVBL0001190
			20.9.2010	(mandatory 11 characters)
			Page -163	Account No. 119011500005385 page 162
2	M/s.Polar	63,740	Paid Vide	Name of the bank: Axis Bank
	electricals		R.No.123	branch : Ashok Nagar
			dated	Account No. : 285010200001694
			20.9.2010	IFSC code no. :600211012 page 170
1			Page 166	
3	M/s.S.S.Electri	68,000	Paid Vide	Name of the bank: Corporation bank
	cals		R.No.124	Branch: Ashok Nagar
			dated	Account No:CA01000 257
			20.9.2010	Swift code: CORP IN BB 122
			Page 165	IFSC CODE FOR RTGS :
1 - 1 - 1 - 1			7	CORP000000578, CA01000257 page169

Submitted for approval for refund of the EMD for the above work to the contractor, please.

Deputy Director

May le appel. EMD Regishi de le cipidaliet
(Achii-Esquie
Tef2.

Director

KALAKSHETRA FOUNDATION.



Dated 17-03-2011.

70

M/s.KEVIN Electricals PVT. Ltd;

No.7, Arunachalapuram, IInd Street,

Adyar, Chennai-600 020.

Sir,

Sub:- Koothambalam – Electrical Installation work in Kalakshetra Foundation - Renewal of Bank Guarantee Bond No.28277 dated 18-11-2010 for Rs.7, 36,316

Ref(1)Work Order: C:\20092010\V.ADMN\2.Engineering\i.Plan\
Koothambalam\Electrical Installation work.doc Dated 28-09-2010.

(2) Your Letter No.KE/KF/644/2010/605 dated 18.11,2010. — 6.129

Since the above Bank Guarantee Bond was expired on 17-02-2011, You are requested to renewal the bond for Rs. 736,136 with a validity for six months. The renewed Original Bank Guarantee Bond may be sent to this office immediately for record. The expired Bank Guarantee Bond is enclosed herewith for further action.

Kindly note no bill is to be passed, without the receipt of renewed Bank guarantee Bond from you.

Yours faithfully,

CAD

Encl: Original BG Bond No.28277 dated 18-11-2010.

Copy to CARD, 10A, 2nd Floor, Dhanalakshimi Colony, Ist Street, Vadapalani, Chennai-600 026 for Kind information.

2)M/s Madras Electrical Consultants, No.6, Park Avenue Ist Cross Street,

Velachery, Chennai- 600 042.

men my living see beds ince

de les

oneah 20/30

6/

174)

Dated 21-03-2011.

M/s.KEVIN Electricals PVT. Ltd, No.7, Arunachalapuram, IInd Street, Adyar, Chennai-600 020.

Sir,

Sub:- Koothambalam – Electrical Installation work in Kalakshetra Foundation - Renewal of Bank Guarantee Bond No.28277 dated 18-11-2010 for Rs.7, 36,316

Ref (1) Work Order: C:\20092010\V.ADMN\2.Engineering\i.Plan\
Koothambalam\Electrical Installation work.doc Dated 28-09-2010.

(2) Your Letter No.KE/KF/644/2010/605 dated 18.11.2010.

Since the above Bank Guarantee Bond was expired on 17-02-2011, you are requested to renewal the bond for Rs.7, 36,316 with validity for six months. The renewed Original Bank Guarantee Bond may be sent to this office immediately for record. The expired Bank Guarantee Bond is enclosed herewith for further action.

Kindly note no bill is to be passed, without the receipt of renewed Bank guarantee Bond from you.

Yours faithfully,

Diretor

Encl: Original BG Bond No.28277 dated 18-11-2010.

Copy to CARD, 10A, 2nd Floor, Dhanalakshimi Colony, Ist Street, Vadapalani, Chennai-600 026 for Kind information.

2)M/s Madras Electrical Consultants, No.6, Park Avenue Ist Cross Street, Velachery, Chennai- 600 042.

(89)





Dated 29-03-2011.

M/s.KEVIN Electricals PVT. Ltd, No.7, Arunachalapuram, IInd Street, Adyar, Chennai-600 020.

Sir,

4 .

Sub:- Koothambalam - Electrical Installation work in Kalakshetra
Foundation - Insurance Policy
Ref (1) Work Order: C:\20092010\V.ADMN\2.Engineering\i.Plan\
Koothambalam\Electrical Installation work.doc Dated 28-09-2010.

As per stipulated under Sl.No.20 of Agreement, copies of the following may be submitted to us at the earliest.

- 1) Workmens' Compensation (General) policy.
- 2) Contractors all risk insurance policy.
- 3) Insurance for policy schedule for employees compensation insurance.

Yours faithfully,

Director.

Copy to:

1) CARD, 10A, 2nd Floor, Dhanalakshimi Colony, Ist Street, Vadapalani, Chennai-600 026 for Kind information.


2) M/s Madras Electrical Consultants, No.6, Park Avenue Ist Cross Street, Velachery, Chennai- 600 042.


185

Founder: Smt Rukmini Devi Chairman: Justice Sri S. Mohan Director & Secretary: Ms. Leela Samson



E-mail: admin@kalakshetra.in Phone: +91-(0)44-24520836/4057/1844 Fax: +91-(0)44-24524359







The due date of the guarantee referred above has been extended for a further period of valid up to 16.08.2011.

Except extension of the due date, all other terms and conditions in the original guarantee remains unchanged. No Changes in the other conditions. This letter has to be read as part and parcel of our guarantee dated **18.11.2010**.

MONS BY NO 30056
BG NO: 28277DATED: 18-11-10
AMOUNT: PS 736316/DUE ON: 16-8-2011
VALID UPTO: 16-8-2011
Soury serial no 16328

FOR CITY UNION BANK LID.

Managar Mandavell, Chennal – 28. K. Seethalakshmi 608-538 For CITY UNION BANK LIQ.

Mandaves, Chennal - 28.





कार्णिक कि तमिलनाडु TAMILNADU

SL.No 4241 Date 3, 3, 2011

Name Kevin Electrica & PHD.

Value Rs. 100/

X 313461 SP. Varab

S.P. VASANTHA

STAMP VENDOR

L.No. C4/22702/81 dt. 27-

15, Hobertson Lane, Mandave pakkam, R.A. Puram

Chennal - 600 028, Ph : 24939524

To
The Director,
Kalakshetra Foundation,
Thiruvanmiyur,
Chennai - 600 041.

POLICY Seval no 16328

MENBYNO 30056

BG NO: 38277DATED: [8-1110

AMOUNT: Ps 7 36316/
DUE ON: [6.8-11

VALID UPTO: [6.8-11

BANK GUARANTEE NO: 28277

Dt 18.11.2010

for Rs.7,36,316/-

In favour of

: The Director,

Kalakshetra Foundation,

Thiruvanmiyur, Chennai - 600 041.

On behalf of

: M/s. Kevin Electricals Pvt Ltd,

No: 1B, Arunachalapuram II Street,

Adyar, Chennai - 600 020.

Due on

: 17.02.2011.

For CITY UNION BANK LTD.

K Seethalakshmi
Manager
608-538
Mandaveli, Chennal - 28.

Manager Mandavell, Chennal – 28.

FOR CITY UNION BANK LID.



Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020.

©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/KF/644/2011/899

31.03.2011

To

The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation to be carried out for M/s. Kalashetra at Chennai - Submission of Renewal Bank Guarantee - Reg.

REF: - Your Order No: C:\2009-2010\V.Admin\2.Engineering\i.Plan\Koothambalam\Electrical Installation work.doc Dt.28.09.2010.

With reference to the above, we are herewith submitting the Bank Guarantee (No:28277 Dt.18.11.2010) for Rs.7,36,316/-(Rupees Seven Lakhs Thirty Six Thousand Three Hundred and Sixteen Only) which is renewed for the period upto 16.08.2011 for the above mentioned work.

Thanking you,

Yours faithfully, for Kevin Electricals Pvt Ltd,

L.Wilson Susai Raj (Managing Director)

(189)

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)
Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

139

K.K.SINGH ELECTRICALS GRADE -A-ELECTRICAL CONTRACTOR

TIN .NO.33970885459/05-06
CST. NO. 839866 Dt. 04.04.05
AREA CODE 0 4 5
No.3, NEW MARKET
WEST TAMBARAM,CHENNAI - 600 045.
PH: 22266663, 22260939 FAX: 22264551.

To

08.02.2011

The Director, M/s. Kalakshetra Foundation, Chennai.

Sir,

Sub: EMD - Return Reg.,

We would like to bring to your kind notice that we have paid Rs.57,000/- toward M/s Kalakshetra Project Electrical Tender EMD, We request you to kindly release our DD.

Kindly doe the needful.

Please Note:

DD Details

DD Amount : Rs. 57000.00 DD No : "058663"

Bank : The Karur Vysya Bank Ltd

Dated : 14.09.2010

Thanking you, Yours faithfully,

For K.K.Singh Electricals

Wanager



中 A A A A A A A A A A A A A A A A A A A	पत्र/पोस्टकार्ड/पैकेट बीमा Registered Letter/ Insured Letter/ ने वाले का नाम Idressed to (Name) प्राप्त के प्राप्त में) sured 207 Rundes त्रप्त के जिल्हा दिया जाए। ore out the state of del	Postcard/Packet/Parcel S Kenin Electr 0:7, Aswnach Adyan Chempai	alapuas Joseph 600020
			0
a Post व्र-मोहर -Stamp	प्रेषक डाकघर की नाम मोहर Name stamp of office of posting भेजने वाले का पता Sender's Address	CALAKSHETRA FOUNDATI THIRUYANMIYUR. CHENNAI-600 041	



Revin Electricals Put. Ltd., Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, Ilnd Street, Adyar, Chennal-600 020. ©:24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

		7	Mg. Madra	77	
No	Weles Ches		adras		
			Don		
•	# # # # # # # # # # # # # # # # # # #	(100)			
	# 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	LICELY COMPANITORNO			
	1 2 0 0	Pure /		<u> </u>)
,		K	9	4	



Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

Ref: MEC/AG/2011

21.05.2011

M/s.Madras Electrical Consultants No.6, Park Avenue 1st Cross Street Velachery Chennai – 600 042.

Dear Sir

<u>Sub</u>: Koothambalam – Electrical Installation work – Request for Extension of Completion Period – reg.

We request you to kindly arrange to extend the Period of Completion till 31.09.2011, since lot of co-ordination works are involved and civil works are yet to be completed for Electrical room. We request the extension of Contract validity till that period.

Kindly do the needful and oblige.

Thanking you

Yours faithfully

For Kevin Electricals Pvt Ltd

L.Wilson Susai Raj

(Managing Director)

U.R. Nagarapa

MEC

Reg on 12.6.11.

(193)

Branch Office:

Bangalore: # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in **Secunderabad :** No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

scratch and create infrastructure like HT Panels, Transformer, MV Panel, capacitor panels, buildings to house all equipments etc., This process will definitely take about one year. Before this, we'll have to take necessary sanctions for budget etc., but the main point is that the Auditorium cannot wait that long for inauguration.

Considering all the above, our recommendation will be:

- 01. Retain present arrangement for all buildings till an overall study is conducted to determine the cost of conversion to HT and other details.
- 02. Obtain a new LT Connection for the koothambalam Auditorium.
- 03. If the theatre is going to run with ACs and the Lighting aspects in full paraphernalia for only about 90-100 days in a year and additionally about 50-60 days with just basic lighting etc., then obtain LT Connection for basic loads and the balance can be met with a DG Set which can run during special days only.


Thanks and Regards M.S.Ramesh

Madras Electrical Consultants , #6 Park Avenue , I Cross Street , Velacherry , Chennai 600 042. Office : (044) 29728201 / 03

E-mail: msramesh@mec-india.com; mecramesh@eth.net

L.) What is the total local un the theater Complete.

(194)



Works kalakshetra <works@kalakshetra.in>

GEN - MSR - 01 - Kalakshetra - Reg : HT Connnection for koothambalam Auditorium

M S Ramesh <msramesh@mec-india.com>

Tue, Mar 22, 2011 at 4:15 PM

To: works@kalakshetra.in

Cc: card@vsnl.com, Madras Electricals <mecramesh@eth.net>

Dear Sir,

This is with reference to the HT Applications form submission to TNEB for the auditorium. We need the following clarifications: -

- 01. Is the HT Supply Application form pertaining to the whole campus?
- 02. What is the power requirement for the other areas? If it is readily available, it'll be useful. Otherwise we will have to send an engineer / supervisor to study the whole system.
- 03. The electrical work in the other areas has not been carried out as per TN CEIG norms. If we obtain a single HT Connection, then the existing electrical system in all existing buildings will have to be revamped and it might even cost about Rs.2.0 crores.
- 04. Apart from the above, additional investments to the tune of Rs.1.5 crores will be required to be made to transfer power obtained at one single location to all the buildings through underground cables.
- 05. In case you have decided to go ahead with HT Power connection, then the following points must be noted:
 - a. A fixed outflow per month towards demand charges may be to the tune of Rs.75,000 /- to Rs.1,00,000/-
 - b. More frequent power cuts as it is the HT Consumer who will get affected first in case of power shutdown or load shedding. Hence additional cost of running DG set, as well as investing in new DG set of maybe 320 KVA, costing about Rs.20.0 Lakhs.

(195)

06. If we have to obtain HT Connection, then we will have to develop Sub station from

C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\ Electricl installation work.doc

June 15, 2011

Sub: Koothambalam - Electrical Installation work in Kalakshetra Foundation - Extension of contract period – approval of – reg.

Ref: i) Works Committee approval note dated 22.6.2010

P-25, 26

ii) Work order dated September 28, 2010

P- 107,108

iii) Extension of contract period, request from M/s.Kevin Electricals Pvt.Ltd Dated 21.05.2011, Recommended and forwarded by M/s.CARD and M/s.Madras Electrical consultants dated 11.06.2011 P - 181

The electrical installation work at Koothambalam was awarded to M/s. Kevin Electricals at a total cost of Rs.49,08,773.27/- based on the Works Committee approval as recommended by the consulting Architect M/s.CARD and his associates M/s.The Madras electrical consultant, with the works to be prepared for the project.

As per the terms the contractor should be completed the work in all respects by 30th November 2010. Meanwhile, the contractor has further requested to extent the contract period till 31.09.2011 stating the reason that "Since lot of co-ordination work are involved and civil works are yet to be completed and extend the contract (Validity) period up to 31.09.2011," recommended by the consulting Architect M/s.CARD and his associates M/s. The Madras Electrical consultants forwarded to this for approval.

Submitted for approval for extension of contract period till 31.09.2011 as recommended by the consulting Architect M/s.CARD and his associates consultants, for the above work to M/s.Kevin Electricals..

qu'té le clause no under which

Deputy Director

DIRECTOR

Hes please,
As per bender Conduction page 14 of 26 lunder the head Extension of time subdivision (c).

C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\ Electricl installation work.doc

June 16, 2011

M/s.Kevin Electricals, No.7, (O.No.1-B) Arunachalapuram, IInd Street, Adyar, Chennai 600 020.

Sir,

Sub: Koothambalam – Electrical Installation work in Kalakshetra Foundation – Extension of contract period – Reg.

Ref: i) Work order dated September 28, 2010

ii) Extension of contract period, request from M/s.Kevin Electricals Pvt.Ltd Dated 21.05.2011, Recommended and forwarded by M/s.CARD and M/s.Madras Electrical consultants dated 11.06.2011

The extension of time for completion of the above work was granted till 3\$\vec{\psi}\$.09.2011 as recommended by the consulting Architect M/s.CARD and his associates M/s.The Madras Electrical consultants under the clause the extension of time subdivision (c), tender condition page 14 0f 26.

PHIC

(Leela Samson) Director

Draft for approval please

FO

20/6/1

Deputy Director

Director

(197)





Works kalakshetra <works@kalakshetra.in>

Bank Details

Kevin Electricals Pvt Ltd., <kevinelectrical@yahoo.co.in>
To: Srinivasa Kalakshetra <Works@kalakshetra.in>

Wed, Sep 28, 2011 at 5:04 PM

Dear Sir,

Beneficiary Bank Name : City Union Bank Beneficiary A/c No: OSOD 35317 Beneficiary Ifse Code : CIUB 0000036

Beneficiary Address: Manadaveli, No. 67, Mandaveli Street,

Chennai - 600 028

Beneficiary Name: M/s. Kevin Electricals (P) Ltd.,

Thanks & Regards,

Saravanan,

Site Supervisor

KEVIN ELECTRICALS PVT LTD., ADYAR, CHENNAI - 600 020

Ph:+91 44-2446 6938 Fax:+91 44 -2491 2704.



\vdash	+	33 16.0	-	+	30	29	+	27 11.0	26 10.0	25 10.0		23 08.0	22 08.0	21 08.0	20 08.0	19 08.0	18 07.1	17 07.0	16 07.0	15 07.0	14 07.0	13 07.0	12 07.0	11 03.0	10	+	+	7 03.0	+	+	4 02.0	3 02.0	2 02.0	1 02.0		NO NI
	16.01.00 supply erection 14 swe thick junction box with cover	16.00.00 JUNCTION BOXES		13.00.00 Empty pvc conduit	200 X 45 MM	150 X 45 MM		11.00.00 GI TRUNKING BOX	10.03.00 SUPPLY ERECTION CONNECTING AND COMMISSIONING OF 6 MM THREAD RODWITH SLOTTED CHANNEL	10.02.00 300 MM (W) X 50 MM (h)	10.00.00 CABLE TRAY	08.03.00 SAME AS ITEM 8.01.00 BUT FOR CEILING FAN POINT	08.01.02 SAME AS ABOVE ITEM WITH ADDITIONAL LIGHT POINT	08.01.01 ONE LIGHT CONTROL WITH ONE SWITCH	SUPPLY WIRING CONNECTING AND COMMISSIONING 08.01.00 THE LIGHT POINT WITH 3 RUN OF 1.5 SQMM WITH PVC CONDUIT	08.00.00 LIGHT POINT WIRING	07.13.00 SUPPLYING AND LAYING OF 25 MM DIA PVC CONDUIT	07.09.00 COMMISSIONING OF 3 CORE 4 SQMM	07.08.00 COMMISSIONING OF 3 CORE 2.5 SQMM	07.07.00 SUPPLYING AND LAYING CONNECTING AND COMMISSIONING OF 3 RUN OF 6 SQMM	SUPPLYING AND LAYING CONNECTING AND COMMISSIONING OF 2 RUN OF 6 SQMM WITH 1 RUN OF 2.5 SQM	SUPPLYING AND LAYING CONNECTING AND COMMISSIONING OF 2 RUN OF 4 SQMM WITH 1 RUN OF 2.5 SQM	07.00.00 RAW / UPS POWER WIRING	03.06.00 UPS MAIN VERTICAL DB	8 WAY TPN VERTICAL MCB DB			03.03.00 PDB - 8 WAY TPN MCB DB	_		02.04.00 AC Panel (Out door type) - Cable etnry bottom, incomer and	02.03.00 DG panel - Cable entry: top and bottom, DG incomer 1, DG Incomer 2, Bus coupler and out going	02.02.00 LT panel - MAIN PANEL - 2 Cable Entry: Top/Bottom and EB&DG Incomer and connecting Out going	02.01.00 LT panel - MAIN PANEL 1 Cable Entry : Top/Bottom and EB&DG Incomer and connecting Out going		NO DESCRIPTION
	sqft		Mtr		Mtr	Mtr	Mtr		Mtr	Mtr		Pts	Pts	Pts			Mtr	Mtr	Mtr	Міт	.5 Mtr	.5 Mtr		set		set	set	set .	SPT		each	each	set	set		UNIT
	500.00		100.00		50.00	100.00	200.00		300.00	100.00		20.00	70.00	100.00			600.00	2,800.00	1,200.00	800.00	450.00	1,500.00		2.00	1.00		1.00	2.00	2.00		1.00	1.00	1.00	1.00	Qty	
	120.00		75.00		475.00	425.00	350.00		160.00	550.00		1,200.00	420.00	550.00			30.00	85.00	68.00	55.00	130.00	75.00		8,500.00	16,500.00		8,000.00	8,000.00	8.000.00		1,38,000.00	2,65,000.00	2,30,000.00	2,16,000.00	Rate	Tender Quantity
18,90,250.00	. 60,000.00		7,500.00		23,750.00	42,500.00	70,000.00		48,000.00	55,000.00		24,000.00	29,400.00	55,000.00			18,000.00	2,38,000.00	81,600.00	44,000.00	58,500.00	1,12,500.00		17,000.00	16,500.00		8,000.00	16,000.00	16,000.00		1,38,000.00	2,65,000.00	2,30,000.00	2,16,000.00	Total	tity
0	0 40.00		0 50.00		0 50.00	0 50.00	1		0 300.00	23.00		0 20.00	0 70.00	50.00			300.00	2				1,000.00		2.00	1.				2.00		1.00	1.00	1.00	1.00	Qty	M.
	120.00		75.00		475.00		10		160.00	330.00	550.00	960.00	420.00	550.00	/		30.00	85.00	68.00	55.00	130.00	75.00		8,500.00	16,500.00		8,000.00	8,000.00	8,000.00		1,38,000.00	2,65,000.00	2,30,000.00	2,16,000.00	Rate	MATERIAL SU
16,06,400.00			3,/50.00		23,750.00				48,000.00	15,750.00		19,200.00		27,500.00			00.000,6	2,				75,000.00		1/,000.00					16,000.00		1,38,000.00	2,65,000.00	2,30,000.00	2,16,000.00	Total	AL SUPPLY
	500.00		00.001		50.00	1			300.00	100.00		20.00					00.00					1,500.00		2.00			1.00		2.00		1.00	1.00	1.00	1.00	Qty	
	25.00		20.00		90.00				50.00	100.00	100 00	150.00	60.00	90.00			10.00	10.00	12.00	10.00	25.00	10.00		/00.00	700.00	900 00	700.00	700.00	700.00		4,000.00	5,000.00	5,000.00	5,000.00	Rate	CHARGES
1,90,350.00	T			2 000 00	4,500.00				15,000.00		10 000.00	3,000.00						5,000.00				15,000.00		T-+00.00			700.00		1,400.00		4,000.00	5,000.00	5,000.00		Total	
	0.00			30.00	0.00			000	0.00		0.00	0.00									0.00	0.00				0.00	0.00				0.00	0.00	0.00		Qty	,
Took !	1			20.00		0.00		0.00	0.00		0.00	0.00			0.00						0.00	0.00				0.00	0.00	50			0.00	0.00	0.00	0.00	Rate	CHARGES
2,840.00	2	0.00		00.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00			0.00	0.00	0.00	0.00	0.00			0.00	0.00	0.00	1,120.00	1,120.00		0.00	0.00	0.00	0.00	Total	CHARGES

TEM NO.	DESCRIPTION			SUPF	LY (Rs.)	ERECTI	
		Qty	Unit	RATE	AMOUNT	RATE	AMOUNT
10.03.00	Supplying erecting connecting & commissioning of the 6 mm thread rod with slotted channel supports and welded in the stress supports for the GI trunking and related to all accessories etc.	300	Mtrs	160.00	48,000.00	<u>`</u>	-
1.00.00	G I TRUNKING						
2100100							
	Supplying, fabricating, laying and connecting the following GI TRUNKING with cover of 1.6 mm. Thick embedded in the floor (or) open in ceiling / laid in below false flooring with thread rod and rail supports including of L shape,T shape and necessary support,clamps screws and all accessories etc.						
	100 × 45 mm	150	MTS	350.00	52,500.00	60.00	9,000.00
		1	2				
	150 x 45 mm	50	MTS	425.00	21,250.00	75.00	3,750.00
	200 x 45 mm.	50	MTS	475.00	23,750.00	90.00	4,500.00
	200 X 45 Huit.	1	11110	/			
13.00.00	EMPTY PVC CONDUITS						
13.01.00	Supplying, laying of Heavy duty PVC conduit laid in floor / concealed in wall / partitions with accessories, necessary clamps, screws etc.						
13.01.04	60 mm. dia PVC Conduits	50	Mts	75.00	3,750.00		-
13.01.04	oo hiii. tiii 1 ve contains	1		/			
13.01.04	60 mm. dia PVC Conduits	30	Mts		-	20.00	600.00
		2				-	
16.00.00	JUNCTION BOXES						
16.01.00	Supplying, erecting 14 G thick Junction boxes with cover of 40 mm. height of suitable sizes as per Site conditions. The Junction boxes shall be fixed flush with the floor (powder coated)	40	SQ.FT	120.00	4,800.00		-
	Total			1606400	16,11,200.00	2840	20,650.00
	Discount 3%			48192.0	48,336.00	85.20	619.50
	Total			15	15,62,864.00 58, 208.00	2754.8	<u>20,030.5</u> 0
	Add: Service Tax 10.3% on Erection			15	56,208.00	283.7	2,063.00
				15,58,208	15,62,864.00	3038.5	22,093.50
	Grand Total						15,84,957.50
	(Rupees Fifteen lacs eighty four thousand nine hundred and f	ifty sev	en and	paise fifty onl	y)		15,61.24

Randed off: 15,61,246.50

CHECKER

Page 6 of 6

FOR KEVIN ELECTRICALS PVT, LTD.,

Managing Director

ITEM NO.	DESCRIPTION	1		SUP	PLY (Rs.)	ERECT	TION (Rs.)
		Qty	Unit	RATE	AMOUNT	RATE	AMOUNT
07.04.00	Supplying, laying, connecting & commissioning 2 Runs of 6 Sq.mm. with 1 Runs of 2.5 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in in PVC Conduits open above false ceiling or concealed in wall / ceiling with	360	Mts.	130.00	46,800.00		-
07.07.00	Supplying, laying, connecting & commissioning 3 Runs of 2.5 Sq.mm.PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in already laid PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to Power Points.		Mts.	55.00	44,000.00		-
07.08.00	Supplying, laying, connecting & commissioning 3 core 2.5 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	900	Mts.	68.00	61,200.00		-
07.09.00	Supplying, laying, connecting & commissioning 3 core 4 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) GI tray open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	2400	Mts.	85.00	2,04,000.00		-
07.13.00	Supplying and laying of 25mm. Dia Heavy duty PVC Conduits concealed / open in wall / ceiling etc. with necessary clamps, screws etc. with 1 Run of 16 SWG G.I. Fish wire.	300	Mtrs	30.00	9,000.00)	-
08.00.00	LIGHT POINT WIRING						
	Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc. including supplying and fixing 6 Amps. Switch in manufacturers mounting box fixed flush with the wall.						
08.01.01	One Light Controlled by one Switch	50	Pts.	550.00	27,500.00		_
08.01.02	Same as above item with additional light point.	70	Pts. /	420.00	29,400.00	/	
		70	1 13.	420.00	29,400.00		-
	Same as the Item No. 08.01.00 but for Ceiling Fan points including supplying, and fixing concealed type fan hook box and electronic regulator.	20	Pts.	1,200.00	24,000.00		-
0.02.00	CABLE TRAY Supplying, labricating, erecting, connecting & commissioning of the Perforated type GI Cable Trays with necessary Angle irons for cable supports and other allied fabrication works. Fixing to concrete surfaces shall be done with the help of expandable type anchor fastners capable of bearing a weight of 500 Kgs. Fixing to brick walls shall be done with grouting. The distance between two supports shall be 2000mm. Thematerials and labour for grouting, cable supportsand Provision for fixing allied fabrication work shall supplied by the contractor with provision for fixing Gi flats Throughout with connection point once every mtrs. on both sides all supports shall be with threaded rods once every 1500mm.	1 1		80/m	19,20))	
	300 mm (w) v 50 mm (H)	25	Mtrs	550.00	12 750 00	<u> </u>	
	300 mm (w) x 50 mm (H)	25	WITTS	550.00	13,750.00		-

FOR KEVIN ELECTRICALS PV

(201)a

Managing Director

BILL

	DILL						
ITEM NO.	DESCRIPTION				LY (Rs.)		ON (Rs.)
		Qty	Unit	RATE	AMOUNT	RATE	AMOUNT
	i) CTs of ratio 250 /5A and Class 0.5 for metering and						
	burden 10 VA.						
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 -						
	250 A) with Inbuilt Selector Switch.					7/11/2	
	iii) RYB LED Cluster type Indicating Lamps and Control	1	/	1,38,000,00	1,38,000.00		
	fuses shall be provided.	1		1,38,000.00	1,38,000.00		
03.00.00	MCB DBs						
00100100							
	Supplying, fixing, connecting & commissioning the following MCB DISTRIBUTION BOARDS fixed flush with the wall. All DBs shall have Double door. Lighting and Power DB - C curve and UPS DB - D curve						
03.01.00	LDB						
	8 Way TPN MCB DB						
	Incomer: 63 Amps 4P ELMCB,30mA 1 No.					560	
	Outgoing: 6-16 Amps SP MCB 24 Nos.	2	Sets	8,000.00	16,000.00	700.00	1,400.00
	Outgoing: 6-16 Antips SF MCB 24 Nos.		Jets	0,000.00	10,000.00	_	
03.03.00	PDB					80,1.	1120.0
	8 Way TPN MCB DB	1					
	Incomer: 63 Amps 4P ELMCB,30mA 1 No.	-				560	
	Outgoing: 6-16 Amps SP MCB 24 Nos.	2 V	Sets	8,000.00	16,000.00	700.00	(1,400.00)
03.04.00	External LDB	V			•	80.7.	1120.00
05.01.00	8 Way TPN MCB DB	-					
	Incomer: 63 Amps 4P ELMCB,100mA 1 No.						
	O	1	Set	8,000.00	8,000.00		
	Outgoing: 6-16 Amps SP MCB 24 Nos.	V	Set	8,000.00	8,000.00		
03.05.00	AHU Vertical DB						
	8 Way TPN VERTICAL MCB DB	-					
3	Incomer: 125 Amps 4P MCCB with 25 Ka Ics with standing capacity 1 No.						
	Outgoing: 63 Amps TP MCB 1 No.						
124	Outgoing: 32 Amps TP MCB 7 Nos.	1	Set	16,500.00	16,500.00		-
03.06.00	UPS Main Vertical DB						
	8 Way TPN VERTICAL MCB DB						
	Incomer: 63 Amps TP2N MCB 1 No.						
	Outgoing: 10-32 Amps SP MCB 18 Nos	2	Sets	8,500.00	17,000.09		-
07.00.00				V			
07.00.00	RAW/UPS POWER WIRING						
07.01.00	Supplying, laying, connecting & commissioning 2 Runs of 4 Sq.mm. with 1 Run of 2.5 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in already laid PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to Power Points.		Mts.	75.00	75,000.00		-
		~		~	~		

FOR KEVIN ELECTRICALS PVT. LTD.,

Page 4 of 6





BILL

TEM NO.	DESCRIPTION			SUPI	PLY (Rs.)	ERECT	ION (Rs.)
		Qty	Unit	RATE	AMOUNT	RATE	AMOUNT
	BUS COUPLER: 315 AMPS 4P MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.	2.7					
	Note: All the incomer and Buscoupler are electrical and mechanical interlock with auto/manual selector switch.						
	OUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays4 Nos.						
	BUSBAR : ALUMINIUM						
	RATING: 315 AMPS						
	The Phase Bus bar shall be 50×10 mm. and the Neutral bar shall be 25×06 mm. The Earth Bus bar shall be 2 Runs of 25×6 mm.						
	There shall be TWO set of Metering Compartment incorporated with the following:-						
	i) CTs of ratio 250 & 315 /5A and Class 0.5 for metering and burden 10 VA.						
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 & 315 A) with Inbuilt Selector Switch.						
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.	1		2,65,000.00	2,65,000.00		-
2.04.00	AC PANEL (OUTDOOR TYPE)						
	CABLE ENTRY: BOTTOM						
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated AC PANEL (outdoor type). The Board shall be incorporated with the following:-						
	INCOMER: 250 AMPS 4P MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.						
	OUTGOING: 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays2 Nos.				-		
	100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays 3 Nos.						
	32 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays5 Nos.						
	BUSBAR : ALUMINIUM						
	RATING: 250 AMPS						
	The Phase Bus bar shall be 40×10 mm. and the Neutral bar shall be 25×6 mm. The Earth Bus bar shall be 2 Runs of 25×3 mm.						
	There shall be ONE set of Metering Compartment incorporated with the following:-						

FOR KEVIN ELECTRICALS PVT. LTD.,

Page 3 of 6

Managing birector

BILL

iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided. MAIN PANEL - 2 CABLE ENTRY: TOP/BOTTOM Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet	Qty 1	Unit	2,16,000.00	AMOUNT 2,16,000,00		RATE	AMOUNT
MAIN PANEL - 2 CABLE ENTRY: TOP/BOTTOM Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet	1	Set	2,16,000.00	2,16,000,00			
CABLE ENTRY: TOP/BOTTOM Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet				//	-		7
Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet							
MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet							
compartmentalised modular type with powder coated MAIN PANEL -2. The Board shall be incorporated with the following:-							
EB & DG INCOMER: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos.							
OUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays1 No.							
(Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and							
BUSBAR : ALUMINIUM							
RATING: 250 AMPS							
The Phase Bus bar shall be 40×10 mm. and the Neutral bar shall be 25×6 mm. The Earth Bus bar shall be 2×6 Runs of 25×3 mm.							
There shall be TWO set of Metering Compartment incorporated with the following:-							
i) CTs of ratio $200/5A$ and Class 0.5 for metering and burden $10\mathrm{VA}$.							
ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch.							
iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.			2,30,000.00	2,30,000.00			-
DG PANEL					F		
CABLE ENTRY: TOP/BOTTOM							
Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated DG PANEL. The Board shall be incorporated with the following:-							
DG INCOMER 1: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.							
DG INCOMER 2: 315 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.			2				
	with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos. DUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays1 No. 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos. BUSBAR: ALUMINIUM RATING: 250 AMPS The Phase Bus bar shall be 40 x 10 mm. and the Neutral bar shall be 25 x 6 mm. The Earth Bus bar shall be 2 Runs of 25 x 3 mm. There shall be TWO set of Metering Compartment incorporated with the following:- i) CTs of ratio 200 /5A and Class 0.5 for metering and burden 10 VA. iii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch. iiii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided. DG PANEL CABLE ENTRY: TOP / BOTTOM Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated DG PANEL. The Board shall be incorporated with the following:- DG INCOMER 1: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No. DG INCOMER 2: 315 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.	with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos. DUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays1 No. 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos. BUSBAR: ALUMINIUM RATING: 250 AMPS The Phase Bus bar shall be 40 × 10 mm. and the Neutral bar shall be 25 x 6 mm. The Earth Bus bar shall be 2 Runs of 25 x 3 mm. There shall be TWO set of Metering Compartment incorporated with the following:- i) CTs of ratio 200/5A and Class 0.5 for metering and burden 10 VA. ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch. iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided. DG PANEL CABLE ENTRY: TOP/BOTTOM Supplying Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated DG PANEL. The Board shall be incorporated with the following:- DG INCOMER 1: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No. DG INCOMER 2: 315 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.	with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos. DUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short-circuit relays 1 No. 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays 3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays 3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays 3 Nos. BUSBAR: ALUMINIUM RATING: 250 AMPS The Phase Bus bar shall be 40 x 10 mm. and the Neutral bar shall be 25 x 6 mm. The Earth Bus bar shall be 2 Runs of 25 x 3 mm. There shall be TWO set of Metering Compartment incorporated with the following:- i) CTs of ratio 200 /5A and Class 0.5 for metering and burden 10 VA. iii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch. iiii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided. DG PANEL CABLE ENTRY: TOP/BOTTOM Supplying Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated DG PANEL. The Board shall be incorporated with the following:- DG INCOMER 1: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No. DG INCOMER 2: 315 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and	with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers . 2 Nos. DUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays1 No. 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/ Fixed overload and Fixed short circuit relays3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/ Fixed overload and Fixed short circuit relays3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/ Fixed overload and Fixed short circuit relays3 Nos. BUSBAR: ALUMINIUM RATING: 250 AMPS The Phase Bus bar shall be 40 x 10 mm. and the Neutral bar shall be 25 x 6 mm. The Earth Bus bar shall be 2 Runs of 25 x 3 mm. There shall be TWO set of Metering Compartment incorporated with the following:- i) CTs of ratio 200 /5A and Class 0.5 for metering and burden 10 VA. ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch. iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided. DG PANEL CABLE ENTRY: TOP / BOTTOM Supplying Erecting, Testing & commissioning FLCOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated DG PANEL. The Board shall be incorporated with the following:- DG INCOMER 1: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays1 No. DG INCOMER 2: 315 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and	with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between n.comers 2 Nos. DUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays 1 No. 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/ Fixed overload and Fixed short circuit relays 3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/ Fixed overload and Fixed short circuit relays 3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/ Fixed overload and Fixed short circuit relays 3 Nos. BUSBAR: ALUMINIUM RATING: 250 AMPS The Phase Bus bar shall be 40 x 10 mm. and the Neutral bar shall be 25 x 6 mm. The Earth Bus bar shall be 2 kuns of 25 x 3 mm. There shall be TWO set of Metering Compartment incorporated with the following: i) CTs of ratio 200 /5A and Class 0.5 for metering and burden 10 VA. ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch. iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided. CABLE ENTRY: TOP / BOTTOM Supplying Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated DC PANEL. The Board shall be incorporated with the following:- DG INCOMER 1: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.	with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between n.comers. 2 Nos. DUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays1 No. 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/ Fixed overload and Fixed short circuit relays3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/ Fixed overload and Fixed short circuit relays3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and Fixed short circuit relays3 Nos. BUSBAR: ALUMINIUM RATING: 250 AMPS The Phase Bus bar shall be 40 x 10 mm. and the Neutral bar shall be 25 x 6 mm. The Earth Bus bar shall be 2 Runs of 25 x 3 mm. There shall be TWO set of Metering Compartment incorporated with the following:- i) CTs of ratio 200 /5A and Class 0.5 for metering and burden 10 VA. ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch. iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided. CABLE ENTRY: TOP / BOTTOM Supplying Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated DG PANEL. The Board shall be incorporated with the following:- DG INCOMER 1: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No. DG INCOMER 2: 315 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.	with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between necomers 2 Nos. DUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays 1 No. 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable / Eixed overload and eixed short circuit relays 3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable / Fixed overload and eixed short circuit relays 3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable / Fixed overload and eixed short circuit relays 3 Nos. 100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable / Fixed overload and eixed short circuit relays 3 Nos. 100 AMPS TPN MCCB with 25 KA Ics) Withstanding Capacity Adjustable / Fixed overload and eixed short circuit relays 3 Nos. 100 AMPS TPN MCCB with 25 KA Withstanding Capacity Adjustable overload and 100 AC (Ics) Amps Tened (Ics) Amps Te

FOR KEVIN ELECTRICALS PVT. LTD.,

Page 2 of 6

205

Managing Director



Engineers and Government Licenced 'A' Grade Contractors No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar,

Chennai - 600 020. ② : 24466938, Telefax : 24912704

E-mail: kevinelectrical@yahoo.co.in Web: www.kevinelectricals.com

To

The Director, Kalakshetra Foundation Thiruvanmiyur, Chennai - 600 041. TIN No.: 33680862581

TNGST No.: 0862581 / 2003-2004

CST No.: 794079 / Dt. 13-10-2003

Area Code No.

0 4 4

Bill.No:134 Date:28.03.2011

Name of Work:- Electrical Installation work for M/s. Kalashetra Foundation at Chennai.

TEM NO.	DESCRIPTION			SUP	PLY (Rs.)	ERECTION (Rs.)		
		Qty	Unit	RATE	AMOUNT	RATE	AMOUNT	
2.00.00	LT PANEL							
2.01.00	MAIN PANEL - 1							
	CARLE ENTERV. TOR / POTTOM							
	CABLE ENTRY: TOP/BOTTOM							
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated MAIN PANEL -1. The Board shall be incorporated with the							
	following:-							
	EB & DG INCOMER: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos.							
	OUTGOING: 125 AMPS TPN MCCB with 25							
	KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays1 No.							
	100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays1 No.							
	63 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos.							
	32 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays4 Nos.							
	BUSBAR : ALUMINIUM							
	RATING: 250 AMPS							
	The Phase Bus bar shall be 40×10 mm. and the Neutral bar shall be 25×6 mm. The Earth Bus bar shall be 2 Runs of 25×3 mm.							
	The shall be TWO set of Materiae Comments				-10-2			
	There shall be TWO set of Metering Compartment incorporated with the following:-					3.		
	i) CTs of ratio 200/5A and Class 0.5 for metering and burden 10 VA.			marie de la companya della companya della companya della companya de la companya della companya				
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch.							



For KEVIN ELECTRICALS PVT. LTD.,

Managing Director



Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/KF/644/2011/890

28.03.2011

To

The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation to be carried out for M/s. Kalashetra at Chennai - Submission of RA.Bill - 1 - Reg.

REF: - Your Order No: C:\2009-2010\V.Admin\2.Engineering\
i.Plan\Koothambalam\Electrical Installation work.doc
Dt.28.09.2010.

With reference to the above, we are herewith submitting the RA.Bill - 1 for the above mentioned work

Bill Value (Bill.No:134 Dt.28.03.2011)

Rs.15,84,957.50

Less:

15% Advance Adjusted prorata Basis

Rs.2,37,743.62

5% Retention

Rs. 79,247.87

5% Commissioning

Rs. 79,247.87

Amount to be payable

Rs.3,96,239.36 Rs.11,88,718.14

We request you to kindly arrange to release the Payment of at the earliest & oblige.

Thanking you,
Yours faithfully,
for Kevin Electricals Pvt Ltd,

L. Wilson Susai Raj (Managing Director)

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank) Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

(205)



Mr.Ravi Neelakandan, #10-1A, First Street, Dhanalakshmi Colony, Vadapalani, Chennai - 600 026.

OUR REF # 1744-02/MSR/2010

July 30, 2011

PAYMENT ELECTRICAL WORKS M/S.KALASHETRA CERTIFICATE OF FOUNDATION, CHENNAL.

Dear Sir,

This has reference to the bill submitted by M/s.Kevin Electricals Pvt. Ltd., vide their Ref: KE/KF/644/2011/890 dt.28.03.2011 for the above mentioned project, we are recommending for payment a sum of Rs. Rs.11,70,935.00 (Rs. Eleven Lakhs Seventy Thousand Nine Hundred and Thirty five Only) as per the enclosed Certificate of Payment dt.30.07.2011

Kindly acknowledge.

Regards,

For Madras Electrical Consultants

M.S.Ramesh

Wadras Electrical Consultants

No.6, Park Avenue 1st Cross Street, Velachery, Chennai - 600 042.

Email: mecramesh@eth.net/msramesh@mec-india.com

Phone: 044 - 29728201 / 03





Mr.Ravi Neelakandan, #10-1A, First Street, Dhanalakshmi Colony, Vadapalani, Chennai – 600 026.

OUR REF # 1744-02/MSR/2010

July 30, 2011

CERTIFICATE OF PAYMENT ELECTRICAL WORKS M/S.KALASHETRA FOUNDATION, CHENNAI.

CERTIFICATE OF PAYMENT (SUPPLY)

Name of the work

Electrical works for M/s.Kalashetra Foundation,

Thiruvanmiyur Chennai- 600 041

Name of the contractor

M/s.Kevin Electricals Pvt. Ltd.,

7,(old No.1-B) Arunachalapuram II Street

Adyar, Chennai - 600 020.

Work order value

Rs.49,08,773.27

Contractor Bill # & Date

REF:KE/KF/644/2011/890 dt.28.03.2011

Total Cost of work executed:

Rs.15,61,246.50

DEDUCTIONS AS PER TERMS OF PAYMENT :-

01. 15% Advance adjusted prorate basis Rs.2,34,186.97

02.5% Retention

Rs. 78,062.32

03.5% Commissioning

Rs. 78,062.32

Rs. 3,90,311.61

Balance amount payable

Rs.11,70,934.89

Rounded off to

Rs.11,70,935.00

(Rs. Eleven Lakhs Seventy Thousand Nine Hundred and Thirty five Only)

Regards,

For Madras Electrical Consultants

M.S.Ramesh

Madras Electrical Consultants

No.6, Park Avenue 1st Cross Street,

Velachery, Chennai - 600 042. Phone: 044 - 29728201 / 03

Email: mecramesh@eth.net/msramesh@mec-india.com

Certification of the Certifica



	*												76206			10
											00 2 20,00	28703.00				19
Certain	(A) - 16,06,400	Dr. Laboury " 2,840 L	16,09,240	34. Disco 48,277.00 (C)	(g)- 00.245'09'51	10.34. 283.74 (E)	15,61,24674 (F)		Much = 2,34,186.57 - (G)	57. 4. Lebent 78,062.32 (3)		27. 17 至二年	E= 1+1 1/2-10			
	16,06,400.00	1,60, 640.00 K- 1	14,45,760 × (A).	2,840 - (2)	No.	43,458 (-) -C		14:05.42 E)		(2,10,770.0° G)		2 28,102.00		3,37,35 (-)	VIPEL 1 201/01/01/01/01/01/01/01/01/01/01/01/01/0	
- 1	Supay	104.		Loboun	34. Dis.		Not oppliate	1	c		dul 00 = 14,05,142	() - MK-	Sylphy - (D)	60	783	1- JES

If approved, the payment of Rs. 14, 05,142/- (Rupees Fourteen lakh five thousand one hundred and forty two only) may be paid to the M/s. Kevin Electricals (P) Ltd., as 1st and part bill payment as certified by the consulting Architect M/s.CARD and his associate M/s.Madras Electrical consultants.

Submitted for approval of payment:

S.No	Bill amount	Deductions	Gross amount
1	In this bill value		14,05,142.00
2	Income tax	28,103.00	
3	VAT	28,103.00	
4	Retention amount	70,257.00	
5	Mobilization advance	2, 10,770.00	3,37,233.00(-)
	Nett payab	le to the contractor	10,67,909.00

3/10/11

Working to paymer, as for come calculation his-a wis

Carpultans works is A ween in paymen surject to (A) almo

Hay be pain to payment surject to (A) almo

As Thereof

Deputy Director

Director

However, the consultant has differentiated the materials and labour cost in his recommendation in the statement dated September 18th, 2010 and details is,

Supply of materials cost

= 39, 39,639.75

Labour charges Service tax 10.3%

= 8,87,700.3591,433.00

= 9,79,133.35

Total value of work recommended

49, 08, 773.10

While, working out the service tax clarification need to be obtained from the consultant has to whether service tax applicable for work order value (irrespective of materials + labour component) or labour component alone. Pending clarification from the consultant we may release 90% of material cost in this bill.

On approval a separate letter to consultant will be put please.

Payment & lill: i) Towards supply of materials

Total value of supply of materials as certified (As per the statement) = Rs. 16, 06, 400.00 Payable to the supplier @ 90% on 16, 06, 400.00 as per page 105/c14, 45,760.00

ii) Towards labour charges as certified

2,840.00

Discount 3% (page 9) @3% on 14, 48, 600.00

14, 48, 600.00 43,458.00(-)

Deductions - 2% Income tax on14, 05,142= 28,103.00

2% VAT

= 28,103.00

5% Retention amount

= 70,257.00

1, 26,463.00(-)

14, 05, 142.00

Mobilisation Advance paid

= 736316

On Pro rata basis 14.051/49.087

page 131

Deduction @ 28.625% x 736316

=210770

In this bill deduction

2, 10,770.00(-)

(Balance to be deducted = Rs5, 25,546/-) Net Bill value

10, 67,909.00

M/s. M/s. Kevin Electricals (P) Ltd., - Banker details Beneficiary Bank Name:

City Union Bank

Beneficiary A/c No

OSOD 35317

Beneficiary Ifsc Code:

CIUB 0000036

Beneficiary Address:

Mandaveli, No. 67, Mandaveli Street,

Chennai - 600 028

Beneficiary Name:

M/s. Kevin Electricals (P) Ltd.,



. kalakshetra

C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\ Electricl installation work.doc

September 28, 2011

Sub: Koothambalam – Electrical Installation work in Kalakshetra Foundation – 1st and part Bill – Payment – Approval of – Reg.

Ref: i) Works Committee approval note dated 22.6.2010

P-25, 26

ii). Work order dated September 28, 2010

P -107,108

iii) Certificate of Payment as 1st and part bill, recommended by M/s.CARD And his associates M/s. madras electrical consultant Dated 26.9.2010 P

P - 188-196

Chronology

i) Based on the approval by the Works Committee, the work was awarded to M/s.Kevin Electricals pvt ltd at a total cost of Rs.49,08,773.27/-

108 Ree 131

ii) An mobilization advance for Rs.7, 36,316/- was paid to the contractor against the Bank guarantee as per the terms

Puge 181

The consulting Architect M/s.CARD/Shri.Ravi Niilakantan and his associate M/s.Madras Electrical Consultants have certified and forwarded 1st and part bill payment to M/s.Kevin Electricals for Rs.11,70,935/- (Rupees eleven lakh seventy thousand nine hundred and thirty five only)

The details of items supplied and labour charges have been recorded in Measurement book by Clerks of works appointed by the Consulting Architect. The bill of quantities was checked and certified by the Consulting Architect M/s.CARD\Shri.Ravi Niilakantan and his associate M/s.Madras Electrical Consultants.

As per work order conditions, 15% of awarded value as mobilization advance need to be paid and to be adjusted on pro-rata basis in subsequent bills based on the measurement recorded, checked and certified by the consulting Architect and his associates electrical consultant will be admitted.

Age 108

In accordance with above, 15% mobilization advance Rs.7, 36,316/- was already paid. Now that the bill is certified by the consulting Architect and his associates for Rs.11, 70,935/- net value. This is the amount representing, the value of materials received at site and labour charges for some items as per the details recorded in the measurement book and the rate adopted as per the tender.

Puge 188

After deducting 10% towards completion of work and pro-rata adjustment of mobilization advance the following may be approved for payment.

Regarding the payment of Service tax the following submitted.

 The work order was issued consolidatively for materials as well as labour charges at a total cost of Rs. Rs.49,08,773.27/- Page 107

(21)

.....2

8	**			, a
Chargeable to the Head of Account				and to be
included in accounts for				
To be credited into Bank Account as per details given by the contractor	s Account			•••••
on this Bank RTGS / NIFT				
	T 5			
Memo of payments made	Rs.	P.	Rs.	P.
Total value of work done				
Amount of previous Payments from Last Certificate No				
dated 20				
forwarded to the Kalakshetra Foundation Accounts Section				
on 20 with No 20			1 10 1000	
Payments how to be made				
By Cash			100	
By Cheque			20,211,70	
By ECS	1			
Deductions:				
1) Retention Amount:				
2) Income Tax:			*	
3) VAT				
4) Others				
5) Mobilisation Advance (or) Advances				
By Cheque	Albert Street		37.8770.002	
By Deduction for value of Stores, etc.	2 V			
South first the same of the sa	1/1/19/1		10	
		1.		1
(To be filled by Kalakshetra Fo				
E.O.	ALLOCA	TION:	Dr. PLAN	
Heado	f Account :) ga V destyr er griffi or o	
A.O. 30 19/11 Gross	Amount :	Rs:		
Less D		Rs:	janda jalan n	
Net Am	ount Payable :	Rs:		
CAO Net (Ru	pees in words)			
The control of the co	**	11 -		14 1,1
Dy. Director				
Reve	and the same of th			
Star	ijų .	Sig	nature of Contr	actor
Director		•	(12)	

	19 Sept 17 1		1 1		1.	1		Amo	unt		- (
	Quantity executed since last certifi- cate	Quantity executed up-to-date as per Measurement Book		Items		Rate	Up-to-date		Since I Certific	The second	Reference to item as per tender	Remarks
1	2	3		4		5	6		7		8	9
1							Rs.	P.	Rs.	P.		
							110.			1		
• • •						B/F						19 1 1 1
200 000000												
						nistes i						
• • •	:						1					
										.		
										-		1
Tota	al volue of	f work done inc	uding Proepe	ctive Paym	nent .				100		100	
1016	ai value oi	I WOLK GOLIE ILIC	duling i Tospe	ouve r ayn	1011111							Value of the state
Tota	al value of	f work done				••	156	12	46.	5	4	
											1	
l es	s value o	f work shown o	n Last Certific	ate								
	o value o	I WOLK SHOWN O	, Laot oortiine									West of
							1561	0	1.6.	5	0	
	ount due	Rupeesf.i.		••	••	·· Say	1001	25	70			
	page	easurement we	of N	leasureme	nt Book NELEC1	Nos	L VI. LTb.			1.00	Payoul)
		MALKI - 11				Macroping					gineer in	
	Certific	ate that the for	egoing claim	is correct	that the r	necessary	measurer	nen	ts were t	ake	n by the i	-ngineer ii
cha	arge on	the22_	07	20.1.	l	. checked	by me o	n the	e3.5) - (07	20.].]
an	d are rec	corded at page			of Mea	asurement	Book No		1		a	nd that the
wo	ork has be	en satisfactoril	y performed.	ForKEV	IN ELECT	TRICALS P	VI. LIU.				8	
						APDX	2./		4	A	$\Lambda \Lambda$	19/11
_		22 -072	. 11	ž		Managing	Director		11	1	1 2	6111
Da	itea)./	•	Co	ntractor			Engir	1961	/ Consult	Architect
		y 1 - 2 - 200 4					MITEG	70_(70	N	
And the second second second second	•//						S Ghr	Man-	TO A	<i>J</i> .		

			4							
	Quantity	Quantity				Amo	ount		Refer-	
		executed			<u>'</u>					S
	executed			_					ence to	<u>z</u>
Unit	since	up-to-date	Items	Rate	I la la ala		Since la	ast	item as	Remarks
	last	as per			Up-to-da	ate	Certific		per	Re
	certifi-	Measurement					00111110		tender	
	cate	Book							10110101	<u> </u>
	100	A STATE OF THE STA	4	5	6		7		8	9
_1	2	3			Rs.	P.	Rs.	P.		4
	1 0 8				ns.	١	110.	1, .		
							1			
			1 A	B/F		l]	1		
				1		[,	1			
				=)	27.54	19.7	S.O. /	T		
		1			'	1	7			
		1.7	Add Gervice ton.				1	1.		1
			. 10.1.3. %. ON Oxtree!	firm of	100-2	9	1/	1		1
	,		10.9.3. You Car (C.) (C.)	1.00	1200	110	1. /	1	1	
				1		ļ	 .			
					- 000		1.1/	1		
		1	Exection -	· · · · · · · · ·	30.38	6	D41/			
	1				-	-				
							1		1	1
		A	Total	1	1	1	1	.		
	.									
						.		.		
		1	la - alu 1 Pi-antin	who is						
			Supply + Errection			.	4	.		1
										1
				1		. [1			
			15.58.208.00/							
				100						
			3038:54/				.			
				/			1			
			15.612.461.54.							
										\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
								. .		
		=	Say Rs - 15.61246.5	2/-				. .		
		<i>i</i>	. July	/	-	1				
								. .		
• • •										
								. .		
			-)			.		.		
						1				
								.		
• • •										
								.		
			£			٠.١.				
			\$.		
		00	S							10000000
			×					.		1
	. 1	The same								
								.		
						1				.
٠				• • • • • • •		• • •				
]			
									1	
		SADOSISTA DO ALBORRAS DE ORGANISTA -								
• •										
									Andrew Property Co.	
			THE STATE STATES OF THE STATES	C. O.					(in)	
						اب		4	1110	
								D	X)	

			3		· · · · · · · · · · · · · · · · · · ·		ount	7		
	Quantity	Quantity			<i>P</i>	imc	ount		Refer- ence to	S
	executed since	executed up-to-date		Rate			Since la	et	item as	Remarks
Unit	last	as per	Items	Tiale	Up-to-da	te	Certifica		per	Rer
	certifi-	Measurement		*			00,11110	36	tender	
	cate	Book	-		6	_	7		8	9
1	2	3	4	5		P.	Rs.	P.		
• • • •				B/F				l		
						••	1			
						••	1		in 60 h	
MI	8	300	THREAD ROD	.160	4.8000		ļ,		(0:03:0)	J
**177										
• • • •							1	1		
			0 - 6 1 1 0 000							
···			G. I. TRUNKING BOX.				1	1	11 00.0	
mT.	3	150	100. X. 45 mm	35.0	52.500	··			1/10010	Ψ
MI		50	150. X. A. 5. mm	.A.2.5.	21250	١, .			37	
		60	200.X.45mm	475	23750				P	
เทา	K		208. A. A. 2	1.7/1.4						
							1		1	
								• • •		
		1						.		
MJ.	0	50	600mm. CONDUIT-SUPPL	y .75.	37.50	1.		.	13.01.1	4
			. bo mm. CONDUIT-ERPECTI	20	600	K				
mil	3	3D	. DO MM. CONDUTT ERECUT	D	1		1			
						1.		.		1
						1.	;			
r F. T	- 1	AD	. JUNICTION BOX	. 120.	4.800	1		. .	16:01:	б <u>р</u>
						-				
• •				1						
٠.				1	0.4		.1	1.		
			Total Supply of a	mod:	. Rs/-	+.		. .		
							
					16064	do	I.F			
• •			Discont.	3%			X			
• •			1	٠٠٠٠٠٠	. 60.60	1	- V	1		
٠.			Supply total	_크]·····	1558	5	08/-			
										0-1
			Total Exection of an	cont	As			.		Reference It
						. [.	ار			
• •					1120	K				.03-01-9
					1000	11/				0.30.1-9
					11.20.			.		
					6.00	A				130.1-9
		gree shearcon manner			28.1	10	1			
•					. 0	7				
•			(I) MA 1- 0 -2		80	1	201/-	-		15)
•		<u></u>	Discount 3.7.			-	4 - 80	1/	10	
			N. Mar. Car.	C. O.	27	5	4 10 00	/ ,		

Bor Baker 18/14/11

pt. Land

	Quantity	Quantity	2		. Am	ount	Refer-	
Unit	executed since last certifi- cate	executed up-to-date as per Measurement Book	Items	Rate	Up-to-date	Since last Certificate	ence to item as per tender	Remarks
_1	2	3	4	5	6	7	8	9
MAR.		35		B/F	Rs. P.	Rs. P.		
						J		
MJ.R.		360		.130.	4.6.800		0.7:04/1	o
••••				×.	<u>/ </u>			
MIR.		80.0	3R. X 2:5. Symm. Cu:	5.5./	44000		07.97.0	0
			WIRR			\\range \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\		
MIR 		9.00	.3C. X.215. SSmm. Cb 	в.	612.00		671.08.0	0
UTR.		. 2.400	.3C.X.4.a.Somm.Cu WIRE	85	2.04000		07/10/9/10	p
MT.R.		300	25 mm. PVC. CONDUIT.	39.	9000/		07(113,00	D
PIS		5.0	ONE LIGHT POINT	5.50/.	27500		0 % pl:0	1
			CONTROL					
P.T.S.			ADDITIONAL LIGHT. POINT CONTROL	420	29400		0.8:01-0	2
TS		20	F.A.N. POINT CONTROL	960/120	5. 19200		.08.03·0	10. 80:1: Relese
M.TR.		25	.300 X.50.mm. CABLE. TRAY	.550	1.3.750		10,02,0).,,,
			,,					
			<u> </u>	C. O		ļ		/
	1.	7	Carles 2/14	<u> </u>	2		(11)	7 ,

C. Or Bondarain

J. P

010

KALAKSHETRA FOUNDATION

RUNNING ACCOUNT BILL / FINAL BILL ELECTRICAL.

Nom											
Nam	e of Worl	k Koo T.	HAMBALAM ELECT	RICAL	WOK	KS				······································	
	•							•••••			
Nam	e of Con	tractor K.E.	EVIN ELECTRICALS PV	T.LII	دۇ		0.00	201	2 A A . A		Engino
Cont	ract Agree	ement No	/ of 20	Work Or	der No	Ç.,ŝ.,`	12009 -	201	0 \\\	DMIN Y	- mos
Date	of comm	nencement of	work 15:11:2010	Li.P.lar	7./Y.60, T.	H.m.E	laudm.	E.L.	CIBICAL.	JUSTALANI	GIO
	Quantity executed	Quantity executed				Amo	ount	-	Refer-		
Unit	since	up-to-date	Items	Rate	Up-to-d	2+0	Since la	ast	ence to item as	Remarks	**
	last	as per Measurement			Up-to-u	ale	Certifica	ate	per tender	Re	
	cate .	Book		-	6		. 7		8	9	
1	2	3	4	5	Rs.	P.	Rs.	Ρ.		7,714.6	
SE.T.		1	MAIN PANEL-1	216.000		100 00			02:01:0	o⁄	
SET.			MAIN PANEL -2	2.30000	230000			l	2:2:00	1	
JF1			. Delta de la constante de la								
SET.		1	D.G. PANEL	26.5005	26500	ď			02.03.0	ø	
SR.J.		4	Ale PANEL (OUTDOOR)	13.8005	13.8000	2/.			02:04:0	þ	
						1					
SET.		2	LIGHTING D.B-SUPPLY	8000/	16.000					n/	Α
SET		2	LIGHTING D. BERRECTIO	M560 700	1120				. 0.3.01.0g	2.80% R	eleseo
SET.	h-x	2	POWER D.B SUPPLY.	8000	16000		l		03.03	90	
SET.	1	2	POWER DIB - ERRECTION]		1 - 2	80%	Relese
٠٠٠ تو د			D. D. C.							,	
SET		4	EXTERNAL . LIGHTING DI	B.8000	8009				03:041	2	
								. ;			
SET		1	AHUVERTICALDB	16500	10:000). 	 · · · · · · ·		3:05.0	4	
	S Mark Contracts		Was along use Treat Se	0.806	ITINO	J.			03:06:	m	-
SET		2	. UPS . MAIN VERTICAL DE	Space.	1.1001	7			. 0.3.44		
mtr		1000	2R. X. 4.0. Segmm. 3				1			J	
ind v				22 75	75001	ś[07.01.0		
•••					1]		/		
	1										. 1949
				C. O		1	1		16	(7)	
			B. Ra. Saylard	There's to	J. N.R.	Nacy	arajon.		12		,



<u>UNITED INDIA INSURANCE COMPANY LIMITED</u> DIVISIONAL OFFICE 011400, 50, NORTH USMAN ROAD CHENNAI 600 017 PHONE: 28142743, 28142511

Provisional Policy/Certififcate

ERECTION ALL RISK POLICY

Serial No: W.C//2011

Name of the Insured : M/S. KEVIN ELECTRICALS PVT LTD AND

KALAKSHETRA FOUNDATION

Address of the Insured : NO. 7, OLD NO. 1-B ARUNACHALAPRAM II nd street

ADAYAR, CHENNAI. 600 020

SUM INSURED : Rs. 49,08,773

PREMIUM : RS. 8,342/- (INCLUDING S.TAX)

Nature of work : ELECTRICAL INSTALLATION WORK

PLACE OF WORK : AT KOOTHAMBALAM IN KALASHETRA

FOUNDATION, THIRUVANMIYUR.CHENNAI 41.

Period of Insurance : 29.6.2011 to 28.12.2011 (SIX MONTHS)

Receipt No: 1842, Dt. 29-06-2011

Conditions : As per ERECTION ALL RISK POLICY

This provisional certificate is issued in proof of insurance of above material/goods as the regular receipt and policy issuance is delayed due to technical reasons at our end. The Original Policy and receipt will be issued as soon as the problem is rectified.

Date: 29-06-2011 Place: Chennai 17 for UNITED INDIA INSURANCE CO.LTD.,

Authorised Signatory



UNITED INDIA INSURANCE COMPANY LIMITED DIVISIONAL OFFICE 011400, 50, NORTH USMAN ROAD CHENNAI 600 017 PHONE: 28142743, 28142511

Provisional Policy/Certififcate

Workmen Compensation (General) Policy

Serial No: W.C//2011

Name of the Insured

: M/S. KEVIN ELECTRICALS PVT LTD.,

Address of the Insured

: NO. 7, OLD NO. 1-B ARUNACHALAPRAM II nd street

ADAYAR, CHENNAI. 600 020

PREMIUM

: RS. 5,877/- (INCLUDING S.TAX)

No. of workmen

: 6 Workers (4 ELECTRICIAN. 2 HELPER)

Nature of work

: ELECTRICAL INSTALLATION WORK

PLACE OF WORK

: AT KOTHAMBALAM IN KALASHETRA

FOUNDATION, THIRUVANMIYUR.CHENNAI 41.

Period of Insurance

: 29.6.2011 to 28.12.2011 (SIX MONTHS)

Receipt No: 1842, Dt. 29-06-2011

Conditions : As per Workmens Compensation (General) Policy

This provisional certificate is issued in proof of insurance of above material/goods as the regular receipt and policy issuance is delayed due to technical reasons at our end. The Original Policy and receipt will be issued as soon as the problem is rectified.

Date : 29-06-2011

Place: Chennai 17

for UNITED INDIA INSURANCE CO.LTD.,





Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/KF/644/2011/231

30.06.2011

To

The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir,

SUB: - Electrical Installation work for M/s. Kalakshetra Foundation at Chennai - Submission of Workmen Compensation Policy & Erection All Risk Policy-Reg.

REF: - Your Order No: C:\2009-2010\V.Admin\2.Engineering\i.Plan\Koothambalam\Electrical Installation work.doc Dt.28.09.2010.

With reference to the above, we are herewith submitting the copy of Workmen Compensation Policy & Erection All Risk Insurance Policy for the above mentioned work

Thanking You,

Yours faithfully, For Kevin Electricals Pvt Ltd

L. Wilson Susai Raj (Managing Director)

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road, (Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

(220)

i) Towards supply of materials

Mobilization Advance paid = 736316 On Pro rata basis 14.051/49.087 Deduction @ 28.625% x 736316 =210770 In this bill deduction ---------------(Balance to be deducted = Rs5, 25,546/-)

(221)

, kalakshetra

C:\ 2011-2012\V.Admin\2. Engineering\i.Plan\Koothambalam\ electrical installation work.doc

October 4, 2011

To

M/s.Kevin Electricals,

No.7, Arunachalapuram IInd Street,

Adyar.

Sir,

Sub: Name of the work: Electrical installation works at Koothambalam - first and part bill payment

- Remittance advice - regarding

We have now forwarded a request to our banker to remit Rs. 10, 67,909/- (Rupees Ten lakh sixty seven thousand nine hundred and nine only) in your account through NEFT/RTGS today, towards first and part bill settlement for the above work to the following account and banker details.

• Beneficiary Bank Name:

City Union Bank

o Beneficiary A/c No

OSOD 35317

o Beneficiary Ifsc Code:

CIUB 0000036

o Beneficiary Address:

Mandaveli, No. 67, Mandaveli Street, Chennai -28

o Beneficiary Name:

M/s. Kevin Electricals (P) Ltd.,

The summary of the amount remitted is as follows;

	Contract value	Total submitted bill value	Total passed sofar(see the attachment	Current bill value	Bill No/Date	Disallowed value	Total amount passed	Add Service tax	Gross bill value	TT . TI	Dedu	Retention	Mobilsation	Nett amount	Remarks
In Rs.	49,08,773.27	15,61,246.50	14, 05,142.00	14,05,142.00	26.092011	1,56,104.50	14,05,142.0	00.00	14,05,142.0	28,103.00	28,103.00	70,257.00	2,10,770.0	10, 67,909	Service tax subject to clarification

Kindly acknowledge

Yours faithfully,

Chief Accounts Officer

Copy to 1. M/s.CARD/Chennai

2. M/s.Madras Electrical consultant/chennai

(622)

fol Engines Corino Colores Colores



CITY UNION BANK LTD

NO 67,MANDAVELI STREET,MANDAVELI, CHENNAI 600028 PHONE: 044 24937874

REMINDER-II

DATE: 09.02.2012

To The Director, Kalakshetra Foundation Tiruvanmiyur, Chennai 41 No.: 1638

Sir,

Sub: Bank Guarantee no 30056 dated 30.03.2011 Issued on behalf of M/s Kevin Electricals P LTd For Rs 7,36,316/-

Date of expiry of the Bank Guarantee: 16.08.2011

We refer to our above guarantee No 30056 dated 30.03.2011 issued by us for a sum of Rs 7,36,316/- for performance of /on account of Kevin Electricals P Ltd in your favour.

The validity period expired on 16.08.2011 .No claim has been received by us from you within the period mentioned therein, i.e., on or before 16.08.2011

Please note that our obligations under the said guarantee have ceased to have any validity and legal force as we have not received any claim under the guarantee within the validity period. We are sure that you are aware of the position that retention of the document emboding the guarantee after the expiry of its validity period does not confer any right whatsoever upon you, (the beneficiary). In the circumstances, we shall be glad if you will please return to us the obsolete document of guarantee duly cancelled, to be kept by us for our record/ audit purposes as the retention of the same by you does not serve any purpose.

Please treat this as urgent and return back the expired bank guarantee at the earliest.

Thanking you, L

Yours faithfully

Manager. Copy to

1.Central Office

2 Kevin Electricals P LTD,

No 7,Old no 1-B, Arunachalapuram II St, Adyar Chennai 20

(223)

The due date of the guarantee referred above has been extended for a further period of valid up to 19.10.2012.

Except extension of the due date, all the other terms and conditions in the original guarantee remain unchanged. No changes in the other conditions. This letter has to be read as part and parcel of our guarantee dated 18.11.2010.

Notwithstanding anything contained herein:

- a) Our liability under this Bank Guarantee shall not exceed Rs.7,36,316/-(Rupees Seven Lacs Thirty Six Thousand Three Hundred and Sixteen Only).
- b) This Bank Guarantee shall be valid up to 19.10.2012. and
- c) We are liable to pay the guaranteed amount or any part thereof under this Bank Guarantee only and only if you serve upon us a written claim or demand on or before 19.10.2012.

FOR CITY UNION BANK LTD





काणीं कितिमलनाडु TAMILNADU

Name Kewin Electricals & 12.

Value Rs.

The Director, Kalakhshetra Foundation, Thiruvanmiyur, Chennai – 600 041.

BANK GUARANTEE NO: 28277

Dt:18.11.2010.

For Rs.7,36,316/-

L.No. C4/22702/81 dt. 27-1-82 15. Roberts of Lane,

Mandavelpakkam, H.A. Puram

Seamy Senal WU: 2/206.

In Favour of -

: The Director,

Kalakhshetra Foundation,

Thiruvanmiyur, Chennai – 600 041.

On Behalf of

: M/s.Kevin Electricals Pvt Ltd,

No:1B, Arunachalapuram, II Street,

Adyar, Chennai - 600 020.

Due On

: 17.02.2011.

FOR GITY UNKIN MANKETS.

Managy. Managyell, Chennal-28

(22)



Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF:KE/KF/644/2012-13/017

20.04.2012

To

The Director, Kalakhshetra Foundation, Thiruvanmiyur, Chennai – 600 041.

Dear Sir,

SUB:- Electrical Installation to be carried out for M/s.Kalakhshetra At Chennai – Submission of Renewal Bank Guarantee – Reg.

REF:- Your Order No: C / 2009-2010 / V.Admin / 2.Engineering / i.Plan / Koothambalam / Electrical Installation work.doc Dt.28.09.2010.

With reference to the above, we are herewith submitting the Renewal Bank Guarantee (BG No.28277 Dt.18.11.2010) for Rs.7,36,316/- (Rupees Seven Lacs Thirty Six Thousand Three Hundred and Sixteen Only) which is renewed for the period upto 19.10.2012.

Thanking You,

Yours Faithfully,

For Kevin Electricals Pvt Ltd,

L. Wilson Susai Raj (Managing Director)

for unfromation please

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

CAO

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

- 12. Any notice by way of request, demand or otherwise hereunder may be sent by post to the Bank, addressed as aforesaid, and if sent by post, it shall be deemed to have been given at the time when it would be delivered in due course of post, and in proving such notice, when given by post, it shall be sufficient to prove that the envelope containing the notice was posted and a certificate of posting from postal Authorities / Agencies, to the effect that the envelope was so posted shall be conclusive.
- 13. These presents shall be governed by and construed in accordance with Indian Law.
- 14. The Bank hereby declares that it has the power to issue this Guarantee and the undersigned has full power to do so.

Notwithstanding anything contained hereinabove our liability under this guarantee is restricted to Rs5,25,545/- (Rupees Five Lacs Twenty Five Thousand Five Hundred and Forty Five only). This guarantee is valid upto 15.05.2013. Any claim arising out of the guarantee must be lodged with the bank at its office at Mandavelli Branch, Mandavelli, Chennai – 600 028 on or before 15.05.2013, after which the liability of the bank would be extinguished.

In witness thereof the Bank has executed these present the day and year first above written.

Signed and delivered for and on behalf of the above named.

FOR CITY UNION BANK ETD

Manday li Chennai-28

BO 10: 37-3510 1750: 16-11-12 15-5-2013 15-5-2013 Sourty Sourcel 23828.

For CITY UNION BANK 'TD

Manager Manday II.Ch nng ASE 507



03. The CLIENT may, without affecting Bank's liabilities and obligations hereunder and without reference to the Bank grant time or other indulgence to or compound with the Contractor or enter into any agreement or agree to forbear to enforce any of the terms and conditions of the Contract.

04. This Guarantee shall not be affected by any change in the Constitution of the Bank of the CLIENT or by absorption / merger of the CLIENT with any other body or corporation or otherwise and this Guarantee will be available to or enforceable by such body or corporation.

05. All composition and payments received by the CLIENT from or on behalf of the Contractor shall be regarded as payments in gross and in the event of the contractor being wound-up, the CLIENT will be entitled to prove against the properties of the Contractor in respect of the whole of the contractor's indebtedness to the CLIENT without any right on the part of the Bank to stand in the CLIENT's place in respect of or to claim the benefits of such composition and payment or any security held by the CLIENT until the CLIENT shall have received the full amount of the claims against the contractor.

06. In order to give effect to this Guarantee the CLIENT will be entitled to act as if the Bank were the principal debtor and the Bank hereby waives all and any of its rights of surety ship.

07. THE GUARANTEE HEREIN CONTAINED is unconditional and not revocable by notice during its currency and will remain in full force until full payment has been made to the Client by BANK on the Client having lodged a claim under the Bank Guarantee within its validity i.e. 15.05.2013 (Due Date) and if no claim is lodged by the Client then the Guarantee would expire within the period specified in this Guarantee. The BANK's liability under this Guarantee is restricted to Rs5,25,545/- (Rupees Five Lacs Twenty Five Thousand Five Hundred and Forty Five only). The CLIENT may claim the full or part of the amount under the Guarantee entirely at its sole discretion and make this claim at one or more times before the expiry (including the claim period) of this guarantee. The total amount of claims is restricted to the BANK's liability under the Guarantee. The Bank is required to make a payment immediately on receipt of the claim in the enclosed format.

08. THIS GUARANTEE shall continue to be in force notwithstanding the discharge of Contractor by operation of law and shall cease only on payment of the full amount by BANK to Client of the amount hereby secured and on the claim of Client against Contractor in respect of Contract being satisfied.

09. This Guarantee shall be in addition to and not in substitution for any other guarantee or security for the Contractor given or to be given to the CLIENT in respect of the Contract by the Bank whether alone or jointly with others.

10. IN THE EVENT OF force majeure, according to the Contract the validity of the present guarantee shall be extended for a period to be mutually agreed upon by the Client and the Contractor.

11. Subject to clause 3 hereof, Guarantee shall remain in force until the date of issue of Substantial Completion Certificate under the Contract.

For CITY UNION BANK LTD

S.Kalyani

Manager 608 - 1031

Wand 1 h nnui-28

BG NO: 37351DATED: 16-11-12

AMOUNT: DO 52 5 545/
DUE ON: [5-5-2013

VALID UPTO: [5-5-2013

Soulg Sevel J8829

Manager AVEENDRAN

Manager AVEENDRAN

Manday li.Chennal-303



AND WHEREAS one of the conditions of Contract entered into, with Contractor is that Client should make an advance payment of **Rs5,25,545/-** (Rupees Five Lacs Twenty Five Thousand Five Hundred and Forty Five only) being **15%** (Fifteen Percent) of remaining Contract value of **Rs.35,03,631/-** (Rupees Thirty Five Lacs Three Thousand Six Hundred and Thirty One Only) against an indemnity in the form of a bank guarantee from a bank and in a form acceptable to the Client.

AND WHEREAS THE Contractor has requested BANK to issue one guarantee of **Rs5,25,545/-** (Rupees Five Lacs Twenty Five Thousand Five Hundred and Forty Five only).

NOW THIS GUARANTEE WITNESSETH that,

01. In consideration of Client, at the request of the Contractor, advancing a sum of Rs5,25,545/- (Rupees Five Lacs Twenty Five Thousand Five Hundred and Forty Five only), to the Contractor as and by way of Mobilization advance, the Bank hereby unconditionally and irrevocably guarantees to the Client for due performance of the Contractor's obligations under the contract and indemnifies the client in respect of the BANK hereby undertakes without recourse to amount of the mobilization advance. Contractor, to pay the Client, on mere demand in the enclosed format upto and not exceeding altogether a sum of Rs5,25,545/- (Rupees Five Lacs Twenty Five Thousand Five Hundred and Forty Five only) being the amount of the 100% (One hundred percent) of the mobilization advance payment or such other unadjusted amount of the said mobilization advance. If the Client notifies to the Bank that the Contractor has failed to observe, perform and fulfill the terms of the said Contract then the Bank shall immediately pay to the CLIENT, on Client's mere demand in the enclosed format, such sum or sums of money to the extent of Rs5,25,545/- (Rupees Five Lacs Twenty Five Thousand Five Hundred and Forty Five only) being 15% of the value of the Contract as may be claimed by the CLIENT by reason of non-fulfillment by the Contractor of his obligations under the Contract as aforesaid / and shall also indemnify the CLIENT against all losses and damages which may be suffered by the CLIENT as aforesaid and against all costs, charges, expenses which may be incurred by the CLIENT in connection herewith. The Bank shall pay the said amount without demur or protest or without recourse to the Contractor. Any such demand placed in the enclosed format on the Bank shall be conclusive with respect to the amount due and payable by the Bank under this Guarantee. The decision of Client as to whether the terms and conditions of this Guarantee or Contract have been observed or not shall be final and binding on BANK and the BANK will not have the discretion to withhold payment to the CLIENT if letter in enclosed format is delivered by the CLIENT to the BANK on or before 15.05.2013 (Tenure of Contract including extension period, if any or the complete recovery of mobilization advance which ever is later)

02. This Guarantee is a continuing Guarantee and not revocable except with the previous written consent of the CLIENT and as aforesaid, it will continue in force until the Contractor has maintained the schedule of delivery of the said work under the Contract and observed and fulfilled the terms and conditions of the Contract. The CLIENT has an irrevocable & unconditional right to claim under the Guarantee in case the Guarantee required to be extended in its opinion is not extended by the CONTRACTOR or the BANK within the time frames and for the time frames stipulated by the CLIENT.

For CITY UNION BANK LTD

S.Kalyani Onlanager608 - 1031

Manda F Channal-28

BG NO: 37357 D. TED: 16-11/17 AMOUNT: PA 525545/-DUE ON: 15.5.2013 VALID UPTO: 15.5.2013 Seuls Sound 23829 FOR CITY UNION BANK LTD

Manager RAVEENDRAW Manday Ji nnai-288 501





தமிழ்நாடு तमिलनाडु TAMILNADU

Name Kevin Electricals Pitts.

AK 777211
S.P. VASANTHA
STAMP VENDOR

No. C4/22702/81 dt. 27-1-83
15, Robertson Lane.
Mandavetpakkam, R.A. Furam
Chennal - 800 028, Ph : 24339524

Bank Guarantee For Mobilisation Advance

THIS GUARANTEE made this 16th day of November 2012 BETWEEN M/s. City Union Bank Ltd, Mandaveli Branch, Mandaveli, Chennai – 600 028. (hereinafter called BANK) which expression shall, unless repugnant to the context or contrary to the meaning thereof, include its successors and assigns on the one part and M/s.Kalakshetra Foundation having its office at Tiruvanmiyur, Chennai – 600 041 (hereinafter called Client) which expression shall, unless repugnant to the context or contrary to the meaning thereof, include its successors and assigns, of the other part.

WHEREAS Client has entered into a contract C: / 2009-2010/V.Admin/2.Engineering/i.Plan/Koothambakkam/Electrical Installation work.doc (hereinafter called Contract) at a total value of Rs.49,08,773.27 (Rupees Forty Nine Lacs Eight Thousand Seven Hundred and Seventy Three Paise Twenty Seven only) with M/s. Kevin Electricals Pvt Ltd, No:7, Arunachalapuram 2nd Street, Adyar, Chennai – 600 020 (hereinafter called Contractor) which expression shall, unless repugnant to the context or contrary to the meaning thereof, includes its successors and assigns.

For CITY UNION BANK LTD

S.Kalyani
608 - 1031

Manager

Manager

BG NO: 37 35 DATED: 16.1112 AMOUNT: Ph 5 25545/-DUE ON: 15.5.2013 VALID UPTO: 15.5.2013 Scentu Secrel 23829 Manager Menday II. Change South



Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/KF/644/2012-13/308

16.11.2012

To,
The Director,
Kalakshetra Foundation,
Thiruvamiyur,
Chennai – 600 041.

Dear Sir,

<u>Sub:</u> - Electrical Installation work to be carried out for M/s. Kalashetra at Chennai – Submission of Renewal Bank Guarantee - Reg

Ref: -Your Order No: C:\2009-2010/V.Admin\2.Engineering\i.Plan\Koothambalam\ Electrical installation work.doc.Dt:28.9.2010.

With reference to the above, we are herewith submitting the Bank guarantee (No: 37351 Dt.16.11.2012) for Rs. 5,25,545/-(Rupees Five Lakhs Twenty Five Thousand and Five Hundred and Forty Five Only) which is renewed for the period upto 15.05.2013 for the above mentioned work.

Thanking you,

Yourfaithfully,

for Kevin Electricals Pvt., Ltd.,

L.Wilson Susai Raj (Managing Director)

(23)

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank) Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in



Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

Ref: KE/KF/644/2012/306

DATE: 16.11.2012

To, The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai-600 041

Dear Sir,

<u>Sub:-</u> Koothambalam-Electrical Installation work-Request for Extension of Completion Period- reg

<u>Ref:</u> Your Order No: C:\2009-2010\ V.Admin\ 2.Engineering\ i.plan\Koothambalam\Electrical installation work.doc.Dt:28.9.2010.

We request you to kindly arrange to extend the period of completion till 15.05.2013, since lot of co-ordination works are involved and civil works are yet to be completed for electrical room and other related areas.

Kindly do the needful and oblige.

Thanking you

Yours faithfully

For Kevin Electricals Pvt Ltd

L. Wilson Susai Raj (Managing Director) V. Durunad

Branch Office:

Bangalore: # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

(332)

Registered *Received a Letter/Postcard/Packet/Parcel Insured पनि वाले का नाम Addressed to (Name) क्षीमा का मूल्य (रुपयों में) Dhanalakshmi ♣Insured for Rupees *अनावश्यक को काट दिया जाए। *Score out the matter not required. कैकेवल बीमा वस्तुओं के लिए। For Insured articles only. पाने वाले के हस्ताक्षर / Signature of addressee तारीख - मोहर प्रेषक डाकधर की नाम भोहर

FOUNDATION

पिन / PIN


Date - Stamp

PSD / CH-10 / RP-46 / OCT-10 / 10,000 / Shree VY

Name stamp of office of posting

भेजने वाले का पता Sender's Address

Registered *Received a Letter / Postcard / Packet / Parcel Insured The Kevin Blechricals पाने वाले का नाम Engineers and Government. Addressed to (Name) क्बीमा का मूल्य (रुपयों में) No.7, Cold Nol-B) Arunachala puram वितरण की तारीख / Date of delivery **♦Insured for Rupees** Chennai - 600020 *अनावश्यक को काट दिया जाए। KEVIN ELECTRICALS PVT. LTD., *Score out the matter not required. **%**केवल बीमा वस्तुओं के लिए। d Government Engine वाले के हस्ताक्षर \Signature of addressee ♣For Insured articles only. W No. / (Old No. 17) Army halapuram, II Street, Adyar, Cherna (500.020) New No MOId No. 1717



EOS UNDERTAKING

Date:

We The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai $-600\,041$, Owner of the property hereby agreed to provide sufficient space of $10mtr \times 4mtr$ or $5mtr \times 5mtr$ open to sky in our premises at No:26, 25^{th} cross street, Besant Nagar, Chennai -90, for installation of a Distribution Transformer structure along with associated switch gears and cable, at free of cost.

We here by undertake.

- 1. That we will provide necessary passage with fencing gate, etc. for easy accessibility to Tamilnadu Electricity Board staff at all time with or without tools to inspect the work on the post, structures, cables and other equipments installed in our premises.
- 2. That we will not ask for removal / shifting of the structure etc., to outside the premises in future and to vacate the space provide.
- 3. That we will not demand any rent or cost for the space provided to erect the transformer structure.
- 4. That we will allow the departmental vehicles in our premises for replacing transformer whenever required by the Tamilnadu Electricity Board.
- 5. We also here by undertake that, TNEB will have the right to use its supply lines and equipments provided in our premises to the promises in the neighbourhood.
- 6. We shall not interface with any manner in the property of TNEB and we are the fully responsible for the safety of the property of TNEB in our premises.

For Kalakshetra Foundation,

Name

Director

Witnesses:

100 - Start Propos -

FORM - I

TAMIL NADU ELECTRICITY BOARD

FORM OF REQUISITION FOR SUPPLY OF LOW TENSION ENERGY (Except Agriculture and Huls)

Applicant's Name	The Director,	•	
Father/Husband N	eme Kalak Shetra Fou	ndation,	
Address	Peruvanmeyar,		
	Charles	Tralif No	
	Chemai - 600 04	Reg. Fees:	
		Recelpt No	.,
		& Date	
То		Point No.	10
The Assistant Er	iglnend Junior Engineer	Regn. No	
T.N.E.B.		Regn. Date	"
	(Section Office)		
SIr/Madam,			
	st vou to gundly also it		
2. Lagren	st you to supply electrical energy to t	he premises hereinafter desc	ribed,
connection and oth	to pay the trailf as notified from limited dues including the current consulation and revised by the Board from time.	e to time for the energy supposed to time for the energy supposed to	olled through the service
3. I will av	and revised by the Board from time	la Ilme.	Consumption deposit as
			ater Supply/Recog, Edu.
Commercial).		madathes/modstres/informati	on Technology Industries/.
4. lagree	to take supply for more than two ye	ars and utilise the energy in	The promises of the interest o
5. In case			ma pramises described
In my name. I agre	i, i sell or otherwise dispose of the project to give one calender month/sever	party/vacate the premises whill	e the supply is continued
. DOB. O. Falling such	Dollas I bald	n bus busines in whill a sud b	ay all the arrears to the
and in the p	remises even after my vacation or di	spossession.	service including energy
Coor No	ollon of premises;	49.042 AV	
	ASISTERIA GIRALE	Kalakshetra Fou	ndation
Street		Tiruvanmiyur,	TLACELOTT,
Town/Village Taluk		Chappes for	
Owned by (name in	Block letters)	The Diposition	04) .
Tenanted by (Name	in Block latters)	THE THECTOR KA	HLAKSHETRA
7. The follo	owlon are my	FOUNDATION	
a manifodi &	Wattage		
Clglils	and the first of the second second second	Total: Points / Watt	age
Fans	NEST bears to test to give a many of the page	110 Kw	
Domestic electrical	appliance		
Cookers		D	
Water heaters		- ·	
Refrigeration			······································
Other Purpose	PROPERTY AND AUGUST A VEN		
Wall plups	TALLOFNOE NA 2032		
-do-	5 amps	· · · · · · · · · · · · · · · · · · ·	
Molors:	roamps		mananian ma
Industrial			***************************************
Pymps			
Diher purposes			
A STATE OF THE STA			
	.w.		
-	f^{-1}	4	(X)
	· ·	· · · · · · · · · · · · · · · · · · ·	// // //

						7100110				INCTTO-101	4
ITEM NO.	DESCRIPTION	Ì	:		-	SUPPLY			CLONI	EKECITON	CHOCK
		4	Units	മററ്	KEVISED	BOQ	KEVISED		KEVISED	ကိုက	KEVISED
				RATE	RATE	AMOUNT	AMOUNT	RATE	RATE	AMOUNT	AMOUNT
				RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.
9	Charges of Removing, Relaying and Damaged GI trunking box with 1.6mm cable trays. with including of L shape, Tshape and necessary sopports, clamps and all accessories etc.						-				
Ф	100 x 45 mm	63	Mtrs						300		18,900.00
q	150 x 45 mm	47	Mtrs	7			-		330		15,510.00
U	200 x 45 mm.	65	Mtrs						390		25,350.00
7	Charges of core cutting for speaker cabling										
מ ב	Lengh of 250mm X 75mm Dia	9 [Nos.						937.5		5,625.00
o U	Lengh of 250mm X 50mm Dia	10	Nos.						875		8,750.00
œ	Charges of laying for speaker cable in Tray / heavy duty PVC conduits concealed in wall /										
	ceiling or open above false ceiling with										
Ø	necessrav clamps screws etc. 12 core balanced audio cable (mistral mcf 12)	350	Mtrs						50		17,500.00
q	8 core balanced audio cable (Planet fmc 08)	200	Mtrs						40		8.000.00
O	6.0 sqmm speaker cable (meridian sp 260)	375	Mtrs						35		13,125.00
р	1core balanced audio cable (sc - source mkii)	700	Mtrs						35		24,500.00
Φ	4 sqmm speaker cable (NYFAZ)	350	Mtrs						35		12,250.00
+	Binary 434 cable	300	Mtrs						35		10,500.00
	Supplying, laying of Heavy duty PVC Re inforced fluxible conduit laid in floor / concealed in wall / partitions with accessories, necessary clamps, screws										
a	50 mm	100	Mtrs		86.00		8.600.00		15		1.500.00
q	75 mm	100	Mtrs		178.00		17.800,00		20		2,000,00
o	100 mm	100	Mtrs		247.00		24,700.00		25		2,500.00
	Total					12,81,925.00	21,99,340.00			3,41,650.00	7,27,110.00
	Add: Service Tax 10.3% on Erection										74,892.33
							21,99,340.00				8,02,002.33
	Grand total										20 01 242 22
											30,01,342.33
	(Ru	(Rupees Thirty		akhs One t	Lakhs One thousand Thre	e. Aturidise	nd Forty Two Only)	2			
NN	Contract)				(3)	6	0000	1	For Ke	For Kevin Electricals Pot. Ltd.	s Pvt. Ltd.
	114.50				373	ANI	2004	1		0 1	\
					2/	100	10000			2	

10

Page 7

Section Sect							Y IDDI Y				ERECTION	
Supplying, laying and connecting 25 Scimm. PVC Trained and pvc Conduits Trained some proper conductor white in PvC Conduits Trained some proper conductor white in PvC Conduits Trained some proper conductor white in PvC Conduits Trained some proper conductor with necessary clamps, screws, laying of Heavy duty PvC conduits Trained some proper conductor with a cressories, laying of Heavy duty PvC Conduits Trained some proper conductor with a cressories, laying of Heavy duty PvC conduits Trained some proper conductor with a cressories, laying of Heavy duty PvC conduits Trained some proper conductor with a cressories, laying of Conduits Trained some proper conductor with a cressories, laying of Heavy duty pvC conduits Trained some proper conductor with a cressories, laying of Heavy duty provide conduits provide conduits and commissioning of Heavy duty provide conduits provide connecting and commissioning the companies of the provide conduits provide and conduits provide conduits provide conduits provide conduits provide c	ITEM N		OTY		800	3666	800	REVISED		REVISED		REVISED
Supplying Jaying and connecting 25 Sq.mm.PVC Insulated coper conductor wires in PVC Insulated in Walf particips with a present of the coper in Insulated in Walf particips with a particip wire with a particip with a part			, ,		RATE	RATE	AMOUNT	AMOUNT	RATE	RATE		AMOUNT
Supplying, laying of heavy duty PVC conduit laid in the creasary damps, screws, factorised model at the creasary damps, screws, factorised model at the creasary damps, screws etc. Supplying, laying of heavy duty PVC conduit laid in the creasary damps, screws etc. Supplying, laying of heavy duty PVC conduit laid in the creasary damps, screws etc. Supplying, laying of heavy duty PVC conduit laid in the creasary damps, screws etc. Supplying, leaving and the creasary damps, screws etc. Supplying, leaving from the creasary damps, screws etc. Supplying, leaving from the creasary damps and la creasories Alticopywat, Mourise Custic Erry Pre 14 SW thick Conduits Supplying, leaving from the conduits of the with proder created control to the page to many from the conduits of the conduits of the conduits of the conduits of the creasary support, damps are support, damps and la creasories Supplying, leaving from the conduits repressibly the conduits of the conduits					RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.
Supplying, laying of leasy duty PVC conduits laid in necessary claims, streams etc. 25 mm, die PVC Conduits 26 mm, die PVC Conduits 27 mm, die PVC Conduits 28 mm, die PVC Conduits 30,000 35,000 35,000 10,500,000 10,500,000 29,000,000 1150 30,000,000 10,500,000 1150 30,000,000 115	09.10.0		100		190.00	280.00	19,000.00	28,000.00	25	40	2,500.00	4,000.00
ADDITIONAL ITEMAS Supplying, fixing of feeling fan box with front plate 9 Nos. 570.00 55.00 9,000.00 10,500.00 8 10 2,400.00 Supplying, fixing of feeling fan box with front plate 9 Nos. 170.00 1,100.00	13.01.0											
ADDITIONAL ITEMS Supplying, fixing of Cealing fan box with front plate 9 Nos. 570.00 5,120.00 150 Supplying, fixing of Cealing fan box with necessary 58 Nos. 170.00 9,860.00 75 Supplying, Erecting, Testing & commissioning FLOOR Mounts and all accessories and all accessories compartmentalised modular type with powder casted door type cable commentative modular type with too. Supplying, Erecting, Testing & commissioning FLOOR Mounts District Type 14 SWG thick CRCA sheet compartmentalised modular type with powder casted door type cable commentative modular type with too. Supplying, Erecting, Testing & commissioning from the commentation and commissioning the forces of the commentation and commissioning the large from the commentation and commissioning the multistranded Copper Conductor wires (one each for Phase, Neutral and East) in Haway duty PCC conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc And The ceiling with necessary clamps screws etc All Supplying, Wiring, connecting with necessary clamps screws etc All Supplying, Wiring, connecting with necessary clamps screws etc And The Commissioning the false ceiling with necessary clamps screws etc	13.01.0		300		30.00	35.00	00.000,6	10,500.00	ω	10	2,400.00	3,000.00
Supplying, Fixing of Foot lamp box with front plate 9 Nos. 570.00 5,130.00 150 and necessary clamps, screws etc. 170.00 5 p.860.00 75 supplying, Fixing of Celling fain box with necessary 1 se Nos. 170.00 9,860.00 75 supplying, Excepting 8 commissioning FLOOR Watch powder casted compartmentalised modular type with powder casted with top. 2 supplying Execting, Testing 8 commissioning and all accessories supplying Execting, Testing 8 commissioning the compartmentalised modular type with 2 supplying Execting, Testing 8 commissioning the powder casted door type Powder casted foor type and commissioning the powder casted foor type and commerced to the compartmentalised modular type with 2 supplying the compartmentalised modular type with 2 supplying the compartmental and cassories etc. 2 so the commerced foor type conductor wires (one each for multistranded Capper Conductor wires (one each for conductor wires (one each for type Capper and Each type Capper Capper and Each type Capper and Each type Capper and Each type Capper Cap		ADDITIONAL ITEMS										
Supplying, fixing of Ceiling fan box with necessary 58 Nos. 170.00 9,860.00 75 Supplying, Evecting, Testing & commissioning FLOOR compartmentalises modular type with powder coated door type powers and all accessories screws and all accessories supplying, Freeting, Testing & commissioning excess and all accessories supplying, Freeting, Testing & commissioning the converted modular type with powder coated door type collect rype 14 SWG thick CROS sheet compartmentalises modular type with powder coated door type cable connector box. (4500.00 or 150 mm.) With 25 Amps clip on type terminal sounder coated door type cable connector box. (4500.00 or 150 mm.) With 25 Amps clip on type terminal block connector door type connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated light points with 3 Runs of 1.5 Sq. mm. PVC insulated light points with a least of the screws etc. Supplying, wind, connecting and commissioning the light points with a least of the screws etc. Supplying, wind, connecting and commissioning the light points with a least of the screws etc. Supplying, wind, connecting with necessary clamps screws etc.	1	Supplying, fixing of Foot lamp box with front plate and necessary clamps, screws etc.	0	Nos.		570.00		5,130.00		150		1,350.00
Supplying, Freeting, Testing & commissioning FLOOR mouters customeratelised modular type with powder coated door type POWER TRUNKING BOX. (250 x 250 x 200 mm) with 13 z Amps alpin metal clade socet with top. The compartmentalised modular type with powder coated door type and all accessories are support, clamps screws and all accessories set. Supplying, Freeting, Testing & commissioning the learning in the any duty PvC. Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PvC insulated block connector one clarify in heavy duty PvC. Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PvC insulated may be a screws etc. Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PvC insulated may be a screws etc. Supplying, wiring, connecting and commissioning the light points with a Runs of 1.5 Sq. mm. PvC insulated may be a screw etc. Supplying, wiring, concealed in wall / calling or open above false celling with necessary clamps screws etc.	72	Supplying, fixing of Ceiling fan box with necessary clamps, screws etc.	28	Nos.		170.00		9,860.00		75		4,350.00
Supplying, Frecting, Testing & commissioning FLOOR/WALL MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated door type cable connector box. (450 X a) 300 X 150 mm With 12 S Amps clip on type terminal block connector necessary support, clamps screws and all accessories etc. Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc.	ю	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated door type POWER TRUNKING BOX. (250 X 250 X 200 mm) With 32 Amps 3pin metal clade socet with top. necessary support, clamps screws and all accessories are	1	Nos.		4,500.00		90,000.00		650		13,000.00
Supplying, Erecting, Testing & commissioning FluoRywalL MounTeb CuBric TYPE 14 SWG thick CRCARWALL MounTeb Cubric Type with powder coated door type cable connector box. (450 x 300 x 150 mm) With 25 Amps clip on type terminal block connector necessary support, clamps screws and all accessories etc. Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc. As Alexander Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc. As Alexander Copper Co												
Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc.	4	Supplying, Erecting, Testing & commissioning FLOOR/WALL MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated door type cable connector box. (450 X 300 X 150 mm) With 25 Amps clip on type terminal block connector necessary support, clamps screws and all accessories etc.		Nos.		2,500.00		20,000.00		550	,	4,400.00
Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc.					261,00							
Approved A Stronger A Spranger Chr. 2020	rv	Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulatec multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc.				985		1,80,000.00		30		00'000'09
The standard of the standard o							No. Company					
		S. Carper Sarper				\$0. \$0. \$0. \$0. \$0. \$0. \$0. \$0. \$0. \$0.	JULTANZO	Appeared	J	For Ko	evin Electricals	s Pvt. Ltd.

Managing Director

Page 6

						SUPPLY				ERECTION	
ITEM NO.	DESCRIPTION	OTY	Units	800	REVISED	800	REVISED	ВОО	REVISED	ВОО	REVISED
		,		RATE	RATE	AMOUNT	AMOUNT		RATE	AMOUNT	AMOUNT
				RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.
09.02.00	Supplying, installing and connecting a Copper plate of size 600mm.x 600 mm.x 3 mm. at a depth of 3000 mm. in an earth pit of 700 x 700 x 3500 mm. filled with salt and charcoal mixed with sand in alternate layers 150 mm. each upto a height of 3000 mm. from bottom. Two copper flats of 25 x 6mm. shall be braced to this copper plate throughout the overlaping length with the copper plate and brought to the surface of the earthpit. This copper flat shall have provision for connecting wires of flats as the case may be. A suitable size of 40 mm. dia GI Pipe shall be provided uptil the bottom of the earth pit. This GI Pipe shall have provision for watering through a funnel. A masonary strucutre shall be constructed to a depth of 450mm. and a heavy duty CI Cover shall be used to cover the pit. The cost of digging and back filling shall also be included. Sand, salt and charcoal are in the Contractor's scope.	Q	Sets	12,000.00	13,500.00	72,000.00	81,000.00	2500	3500	15,000.00	21,000.00
09.05.00	Supplying, laying and connecting 25 x 6mm. CU Flat laid in open fashion with necessary clamps, screws, interlinks etc. for earthing the Panels / Stabilizer / DG netural	100	Mtrs	810.00	980.00	81,000.00	98,000.00	30	35	3,000.00	3,500.00
09.07.00	Supplying, laying, connecting and commissioning 8 SWG bare enamelled copper wire enclosed in PVC Conduits with necessary clamps, screws etc. for earthing AC Equipments / motors etc.	150	Mtrs	75.00	85.00	11,250.00	12,750.00	15	20	2,250.00	3,000.00
09.08.00	O Supplying, laying & connecting 500mm. long 25x6mm.Copper flat with SMC Insulator in open fashion with necessary clamps, screws,etc. as earth link for UPS	m	Sets	650.00	750.00	1,950.00	2,250.00	150	200	450.00	600.00
00.00.00	Supplying, laying and connecting 500mm long 12 x 3 mm. Copper flat with SMC Insulator in open fashion with necessary clamps, screws,etc. as earth link for Data Earthing	10	Sets	250.00	33	2,500.00	3,500.00	100	150	1,000.00	1,500.00
5	Dames on a				0 7 2 3 4 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	Hoprove Con Constant	and of the same of		For Kevii	For Kevin Electricals Pvt. Ltd.	vt. Ltd.

					(J)	SUPPLY				ERECTION	
ILEM NO.	DESCRIPTION	QΤζ	Units	ВОО	REVISED	ВОО	REVISED	ВОО	REVISED	ВОО	REVISED
				RATE	RATE	AMOUNT	AMOUNT	RATE	RATE	AMOUNT	AMOUNT
				RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.
08.01.00	Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc. including supplying and fixing 6 Amps. Switch in manufacturers mounting box fixed flush with the wall.				2002			•			
08 01 01	One Light Controlled by one Switch	40	Pře	550 00	950 00	22.000.00	38.000.00	06	120	3,600.00	4,800.00
20.00	00 01 07 Came at above item with additional light point	2 2	Dło o	420 00	220.00	27 300 00	33 800 00		06	3.900.00	5.850.00
70.00	סמווכן מז מססעם ובכוון אובן מסמונים ווקור לסוויב	3	3								
00.00.60	EARTHING				490						
09.01.00	Supplying, installing and connecting a 2.5Mtr. long 40mm. dia G.I.Pipe with holes drilled diametrically opposite to each other once every 150mm. in an earth pit of 380x380x3500mm. filled with salt and charcoal mixed with sand in alternate layers 150mm.each upto a height of 3000mm. from bottom. The pipe shall have provision for watering through a funnel.It shall also have provision for connecting 50x6mm.G.I. Flat on two sides. A masonary strucutre shall be onstructed to a depth of 450mm. and a Medium duty CI Cover shall be used to cover the pit. The cost of digging and back filling shall also be included. Sand,salt and charcoal are in the Contractor's scope.	ω	Sets	2,500.00	3,500.00	20,000.00	28,000.00	5000	3000	16,000.00	24,000.00
	D. Ha. Barbar				TATICAL CONS	parando San	joara	(a	For Ker	For Kevin Electricals Pvt. Ltd.	Pot. Ltd.

					0,	SUPPLY				ERECTION	
ITEM NO.	DESCRIPTION	QTY	Units	800	REVISED	800	REVISED	ВОО	REVISED	ВОО	REVISED
		,		RATE	RATE	AMOUNT	AMOUNT	RATE	RATE	AMOUNT	AMOUNT
				RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.
06.01.00	Supplying, laying, connecting & commissioning 4 Runs of 25 Sq.mm. with 2 Runs of 16 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc.for ups	30	Mtrs.	950.00	1,150.00	28,500.00	34,500.00	125	180	3,750.00	5,400.00
06.03.00	Supplying, laying, connecting & commissioning 4 Runs of 10 Sq.mm. with 2 Runs of 4 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc.	30	Mtrs.	425.00	475.00	12,750.00	14,250.00	75	100	2,250.00	3,000.00
07.11.00	07.11.00 Supplying,fixing,connecting and commissioning of 16 AMPS SPN MENNEKES make schuko model of 2 pin and type plug and socket in Manufacturer's mounting box fixed flush with the wall. For music equipment. (german make)	40	Nos.	1,050.00	1,370.00	42,000.00	54,800.00	125	170	5,000.00	6,800.00
07.12.00	Supplying,fixing,connecting and commissioning of 10-16 AMPS SPN MENNEKES make 3 pin and type plug and socket in Manufacturer's mounting box fixed flush with the wall. For music equipment. (indian model)	200	Nos.	900.00	(1,180.00	1,80,000.00	2,36,000.00	100	160	20,000.00	32,000.00
									が 100mm 10		
07.08.00	Supplying, laying, connecting & commissioning 3 core 2.5 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	1200	Mtrs.	68.00	98	81,600.00	1,08,000.00	10	15	12,000.00	18,000.00
08.00.00	08.00.00 LIGHT POINT WIRING										
	•										

(F)

S. Par. Sales

For Kevin Electricals Pvt. Ltd.

						SUPPLY				ERECTION	,
ITEM NO.	DESCRIPTION	QTY	Units	ВОО	REVISED	ВОО	REVISED	ВОО	REVISED	ВОО	REVISED
				RATE	RATE	AMOUNT	AMOUNT	RATE	RATE	AMOUNT	AMOUNT
				RS.		INT RS.	RS.	RS.	RS.	RS.	RS.
	4C x 10 Sq.mm. Al.	300	MTRS.	90.00	(110.00	27,000.00	33,000.00	25	35	7,500.00	10,500.00
	,	000	MTDC		00 00	96	00 000 00		20		000000
	4C × 0 34:11111. At.	200			00:06	110	39,200.00		000		12,000.00
	3C x 2.5 Sq.mm. Cu.	100	100 MTRS.	90.00	(116.00)	00.000,6	11,600.00	15	20	1,500.00	2,000.00
02:03:00	TERMINATION		-								
,	Supplying,terminating,connecting and commissioning the above Underground cables with Double compression type glands. The cost of earthing gland with copper strips/ wires shall also be included. The cables shall be terminated with Al / copper lugs after crimnian	6 P L									
	3 1/2 × 240 Sq.mm. Al.	10	Nos	1,000.00	1,400.00	10,000.00	14,000.00	200	275	2,000.00	2,750.00
	3 1/2 × 185 Sq.mm. Al.	~	Nos	850.00	1,200,00	1,700.00	2,400.00	200	275	400.00	550.00
	× 2/1	1 7	S VON	800 00	1 100 00	12 800 00	17 600 00	150	27.5	2 400 00	3 600 00
	1/2 X	07	202	00.000	1,100.00	12,000.00	17,000.00	130	C77	2,400.00	3,000.00
	3 1/2 × 120 Sq.mm. Al.	ω	Nos		1,000.00		8,000.00		220		1,760.00
	3 1/2 × 50 Sq.mm. Al.	2	Nos	00.009	750.00	1,200.00	1,500.00	125	180	250.00	360.00
	3 1/2 x 35 Sq.mm. Al.	10	Nos	500.00	700.00	2,000.00	7,000.00	125	175	1,250.00	1,750.00
	3 1/2 × 25 Sq.mm. Al.	ω	Nos	500.00	650.00	4,000.00	5,200.00	100	155	800.00	1,240.00
	4C x 16 Sq.mm. Al.	10	Nos	500.00	00.009	5,000.00	00.000,9	100	150	1,000.00	1,500.00
	4C x 10 Sq.mm. Al.	ω	Nos	450.00	550.00	3,600.00	4,400.00	100	150	800.00	1,200.00
	4C x 6 Sq.mm. Al.	16	Nos		450.00		7,200.00		125		2,000.00
	3C x 2.5 Sq.mm. Cu.	16	Nos	150.00	200.00	2,400.00	3,200.00	20	65	800.00	1,040.00
	4C × 2.5 Sq.mm. Cu.	10	Nos	175.00	225.00	1,750.00	2,250.00	09	65	00.009	650.00
00.00.90	MAINS WIRING										

3300

For Kevin Electricals Pvt. Ltd.

Page 2

BILL OF QUANTITIES / SCHEDULE OF WORKS FOR ELECTRICAL INSTALLATION TO BE CARRIED OUT FOR PROPOSED FOR M/S. KALAKSHETRA AT CHENNAI

					S	SUPPLY				ERECTION	
ITEM NO	DESCRIPTION	OTY	Units	ВОО	REVISED	800	REVISED	ВОО	REVISED	B00	REVISED
				RATE	RATE	AMOUNT	AMOUNT	RATE	E RATE	AMOUNT	AMOUNT
				RS.	RS.	RS.	RS.	RS.	5. RS.	RS.	RS.
02.00.0	05.00.00 CABLES/TERMINATIONS										
	Supplying, laying, connecting & commissioning the following 1.1 KV Grade AYFY/AYWY (or)YWY /YFY Under ground cables with XLPE Insulation with necessary clamps, screws, etc. in the following methods:-				•						
05.01.00					310						
	3 1/2 × 240 Sq.mm. Al.	100	MTRS.	650.00	000	65,000.00	00.006,26	200	225	20,000.00	22,500.00
	3 1/2 x 150 Sq.mm. Al.	400	MTRS.	415.00	550.00	1,66,000.00	2,20,000.00	170	190	68,000.00	76,000.00
	3C x 2.5 Sq.mm. Cu.	400	400 MTRS.	90.00	116.00	36,000.00	0 46,400.00	120	130	48,000.00	52,000.00
	4C x 2.5 Sq.mm. Cu.	250	MTRS.	110.00	(145.00	27,500.00	36,250.00	120	130	30,000.00	32,500.00
	4C x 16 Sq.mm. Al.	150	150 MTRS.	115.00	(133.00)	17,250.00	19,950.00	145	150	21,750.00	22,500.00
05.02.0	05.02.00 CLAMPED ALONG WALL/CEILING										
-	NOTE: Supply of Anchor Fastners and necessary 1.5 mm. thick GI Flat, clamps shall be included in the cost.	>			tt d	35					
	3 1/2 x 185 Sq.mm. Al.	175	MTRS.	525.00	742.00	91,875.00	1,29,850.00	40	55	7,000.00	9,625.00
	3 1/2 × 150 Sq.mm. Al.	100	MTRS.	415.00	\$50.00	41,500.00	00.000,00	40	55	4,000.00	5,500.00
	3 1/2 × 120 Sq.mm. Al.	250	MTRS.		506.00	499	1,26,500.00		20		12,500.00
	3 1/2 × 50 Sq.mm. Al.	100	MTRS.	210.00	245.00	21,000.00	24,500.00	35	45	3,500.00	4,500.00
	3 1/2 x 35 Sq.mm. Al.	300	MTRS.	165.00	206.00	49,500.00	0 (1,800.00	30	40	00.000,6	12,000.00
	3 1/2 x 25 Sq.mm. Al.	200	200 MTRS.	130.00	150.00	26,000.00	30,000.00	30	40	6,000.00	8,000.00
	4C x 16 Sq.mm. Al.	400	400 MTRS.	115.00	133.00	46,000.00	46,000 00 ALEGANO.00	30	40	40 12,000.00 16,000.00	16,000.00
13	3					24	The February St.		For Kevi	h Electricals I'v	t. Lta.
$\left(\cdot \right)$	136.					3 \$	いる			-	

Page 1





Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/KF/644/2011-12/597

23.02.2012

To The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Through: M/s. CARD

Dear Sir.

SUB: - Electrical Installation to be carried out for M/s. Kalakshetra Chennai -Submission of revised rate - Request for approval - Reg.

REF: - Your Order No: C:/2009-2010/V.Admin/2.Engineering / i Plan Koothambalam /Electrical Installation work.doc. Dt: 28.09.2010

With reference to the above, we are herewith submitting the revised rates for the items which are to be executed able for the excess qty for your kind approval.

We request you to kindly arrange to approve the same to enable us to execute the work & oblige.

Thanking You,

Yours faithfully, For Kevin Electricals Pvt Ltd,

L. Wilson Susai Rai (Managing Director)

Cc: M/s. CARD

Cc: M/s. Madras Electrical Consultants

Branch Office:

: # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road, Bangalore

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in



M/s. Kalakshetra Foundation Thiruvanmiyur, Chennai – 600 041.

OUR REF # 1744-02/MSR/2010

April 07, 2012

CERTIFICATE OF PAYMENT ELECTRICAL WORKS FOR M/s. KALAKSHETRA FOUNDATION, CHENNAI.

Dear Sir,

This has reference to the Running bill - 2 submitted by M/s. Kevin Electricals Pvt. Ltd., for the above mentioned project, we are recommending for payment a sum of Rs.8,55,132.00 (Rs. Eight Lac Fifty Five Thousand One Hundred and Thirty Two Only) as per the enclosed Certificate of Payment dt.07.04.2012.

Kindly acknowledge.

Regards,

For Madras Electrical Consultants

M.S. Ramesh

Madras Electrical Consultants

No.6, Park Avenue 1st Cross Street, Velachery, Chennai - 600 042. Phone: 044 - 29728201 / 03

Email: mecramesh@eth.net/msramesh@mec-india.com



Item No.	Description	Amount
	Cost of UP TO 7 Mtr Heavy duty PVC conduit with necssery bend clamp Etc. (1run X 28/-)	196.00
7-	Total	448.00
2		. v
	Cost Of MK make 3 module back box	77.00
	Cost OF 6Amps Switch	109.00
	Cost OF 1 Module front plate	88.00
	Total	274.00
	Discount -40%	109.60
= 17	Total	164.40
	(448+164.40)	612.40
	Cost Of Plantaring material	100.00
	Cost Of Plastering meterial Total	712.40
	lotai	7221-10
	Vat @ 14.5%	103.30
	Total	815.70
-		
	Transport 3%	24.47
	Total	840.17
7.		126.02
	Margin 15%	126.03
	Grand Total	966.19
	Claimed only Rs 950/-	
8	Cost of 3R x 1.5 Sq.mm Frls wire (1run X 12/-) Up to 5 mtr	180.00
	Cost of UP TO 5 Mtr Heavy duty PVC conduit with necssery bend clamp Etc. (1run X 28/-)	140.00
-	Total	320.00
	Vat @ 14.5%	46.40
	Total	366.40
<u>}</u>		10.00
	Transport 3%	10.99
	Total	377.39
	Margin 15%	56.61
	Grand Total	434.00
	Claimed only Rs 430/-	

For KEVIN ELECTRICALS PVT. LTD.,

Managing Director

0,47

Item No.	Description	Amount
4	COST OF Wall mounted connector Boxes Size 450 X 300 X 150mm	1250.00
	COST OF clip on type terminal block connector with necessry clamp screws etc-60 Nos (1 x 10/-)	600.00
		1850.00
	Vat @ 14.5%	268.25
7	Total	2118.25
	Transport 3%	63.55
	Total	2181.80
	Margin 15%	327.27
	Grand Total	2509.07
	Claimed only Rs 2500/-	
5	Cost of 3R x 1.5Sq.mm Frls wire (1run X 12/-)	36.00
	Cost of 1 Mtr Heavy duty PVC conduit with necssery bend clamp Etc.	28.00
	Total	64.00
	Tax 14.5%	9.28
	Total	73.28
	T 1 20/	2.20
	Transport 3%	75.48
	Total	75.46
	Margin 15%	11.32
	Total	86.80
	Claimed only Rs 80/-	
		A
6	Cost of 3c x 2.5 Sq.mm Frls cu wire	68.00
	Tax 14.5%	9.86
	Total	77.86
	Transport 3%	2.34
	Total	80.20
	Margin 15%	12.03
	Total	92.23
	Claimed only Rs 90/-	
7	Cost of 3P v 1 5 Sq mm Frls wire (1run V 12/-) Un to 7 mtr	252.00
7	Cost of 3R x 1.5 Sq.mm Frls wire (1run X 12/-) Up to 7 mtr	252.

For KEVIN ELECTRICALS PVT. LTD.,

Name	of Work:- Electrical Installation work for M/s. Kalashetra Foundation at	Chennai.	
	Cost Analysis for Kalakshetra Projects		
,			
Item No.	Description	Amount	
1	COST OF MK make Foot lamp back box, Holder, Lamp with Front plate		
	Discount -30%	137.40	
5	Total	320.60	
	Cost Of Plastering material	100.00	
	Total	420.60	
	Vat @ 14.5%	60.99	
	Total	481.59	
A.	Transport 3%	14.45	
	Total	496.03	
	Margin 15%	74.41	
	Grand Total	570.44	
	Claimed only Rs 570 /-		
) 2	COST OF Brass coating ceiling mounted 4 way fan boxe Size of 150 x 75 mm with supporting clamp screws etc.	125.00	
	Vat @ 14.5%	18.13	
	Total	143.13	
	Transport 3%	4.29	
	Total	147.42	
	Margin 15%	22.11	
	Grand Total	169.53	
	Claimed only Rs 170 /-	,	
3	COST OF Floor power trunking Boxes Size 250 X 250 X 200mm	2160.00	
	32 Amps 3pin metal clade plug and Top	375.00	
	Discount -25%	93.75	
}	Total	281.25	
	Cost Of Plastering material	250.00	
	Total	2691.25	
	Vat @ 14.5%	390.23	
	Total	3081.48	
	Transport 3%	92.44	
	Total	3173.93	
	Margin 15%	476.09	
	Grand Total	3650.01	
	Claimed only Rs 3650/-		

FOR KEVIN ELECTRICALS PVT. LTD.,

TEM NO.	DESCRIPTION			SUPI	PLY (Rs.)	ERECTION (Rs.)		
	ř	Qty	Unit	RATE	AMOUNT	Qty	RATE	AMOUNT
•	Charges of core cutting for speaker cabling		\vdash					
9	Lengh of 250mm X 75mm Dia					6	937.50	5,625.00
a b	Lengh of 650mm X 50mm Dia					11	2,275.00	25,025.00
C	Lengh of 250mm X 50mm Dia					10	875.00	8,750.00
C	Length of 230mm X 30mm Dia		\vdash					
10	EMPTY PVC CONDUITS							
	Supplying, laying of Heavy duty PVC conduit laid in floor / concealed in wall / partitions with accessories, necessary clamps, screws etc.							
а	25 mm. dia PVC Conduits	300	Mts	35.00	10,500.00	200	15.00	3,000.00
11	Charges of laying for speaker cable in Tray / heavy duty PVC conduits concealed in wall / ceiling or open above false ceiling with necessray clamps screws etc.							
а	12 core balanced audio cable (mistral mcf 12)					350	50.00	17,500.00
b	8 core balanced audio cable (Planet fmc 08)					200	40.00	8,000.00
С	6.0 sqmm speaker cable (meridian sp 260)					375	35.00	13,125.00
d	1core balanced audio cable (sc - source mkii)					700	35.00	24,500.00
е	4 sqmm speaker cable (NYFAZ)					350	35.00	12,250.00
f	Binary 434 cable					300	30.00	9,000.00
	TOTAL				4,25,440.00			2,70,100.00
	Add: Service Tax 10.3% on Erection							27,820.30
					4,25,440.00			2,97,920.30
	Grand Total					-		7,23,360.30

For KEVIN ELECTRICALS PVT. LTD.,



	Name of Work:- Electrical Installation world	c for l	M/s. 1	Kalashetı	a Foundation	at Cl	nennai.	
	DECENTRACY.			CLID	DIV/Da		EDECT	ION (Rs.)
ITEM NO.	DESCRIPTION	Qty	Unit		PLY (Rs.) AMOUNT	Qty	RATE	AMOUNT
	ADDITIONAL ITEMS	Qty	Oilit	KAIL	AWOUNT	Qty	KAIL	AWOUNT
1	Supplying, fixing of Foot lamp box with front plate and necessary clamps, screws etc.	9	Nos	570.00	5,130.00	9	150.00	1,350.00
2	Supplying, fixing of Ceiling fan box with necessary clamps, screws etc.	58	Nos	170.00	9,860.00	58	75.00	4,350.00
3	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated door type POWER TRUNKING BOX. (250 X 250 X 200 mm) With 32 Amps 3pin metal clade socet with top. necessary support, clamps screws and all accessories etc.	20	Nos	3,650.00	73,000.00	20	650.00	13,000.00
4	Supplying, Erecting, Testing & commissioning FLOOR/WALL MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated door type cable connector box. (450 X 300 X 150 mm) With 25 Amps clip on type terminal block connector necessary support, clamps screws and all accessories etc.	8	Nos	2,500.00	20,000.00	4	550.00	2,200.00
5	Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc.	2000	Mts	80.00	1,60,000.00	1539	30.00	46,170.00
6	Supplying, laying, connecting & commissioning 3 core 2.5 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	900	Mts	90.00	81,000.00	185	20.00	3,700.00
	and the state of t							
7	Charges of Removing, Relaying and Damaged GI trunking box with 1.6mm cable trays. with including of L shape, Tshape and necessary sopports, clamps and all accessories etc.			3				2
а	100 x 45 mm					63 .	320	20,160.00
	150 45				-	47	360	16,920.00
b	150 x 45 mm	-				1/	300	10,720.00
С	200 x 45 mm.					65	415	26,975.00
8	Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc. including supplying and fixing 6 Amps. Switch in manufacturers mounting box fixed flush with the wall.							
а	One Light Controlled by one Switch	40	Pts.	950	38,000.00	10	250.00	2,500.00
b	Same as above item with additional light point.	65	Pts.	430	27,950.00	40	150.00	6,000.00

FOR KEVIN ELECTRICALS PVT. LTD.,

2151



Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/KF/644/2011-12/595

09.01.2012

To Ti

The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Through M/s. CARD

Dear Sir,

SUB: - Electrical Installation to be carried out for M/s. Kalakshetra Chennai – Submission of Additional Work Rates – Request for approval - Reg.

REF: - Your Order No: C:/2009-2010/V.Admin/2.Engineering / i Plan Koothambalam /Electrical Installation work.doc. Dt: 28.09.2010

With reference to the above, we are herewith submitting the additional items rates for the above mentioned work.

We request you to kindly approve the same.

Thanking You,

Yours faithfully, For Kevin Electricals Pvt Ltd,

L. Wilson Susai Raj (Managing Director)

Cc: M/s. MEC

Branch Office:

Bangalore: # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

252)





KALAIVAANI ENTERPRISESS

Mobile: 98402 63881 99401 90732



Civil Contractor, Power Demolition, Concrete Cutting, Core Cutting, Chipping

Date: 23.09.2011

To

M/s Kevin Electrical Private Limited,

Adyar, Chennai-20

QUOTATION

Sub: RCC Floor cutting work 150mm diameter and 1mm depth Rs-4.50/-, 125mm diameter and 1mm depth Rs-4.00/-, 75mm diameter and 1mm depth Rs-3.75/-, 50mm diameter and 1mm depth Rs-3.50/-

	4	RATES FOR CORE CUTT	ING		TWEST
S.NO	LOCATION	DESCRIPTION	QTY	RATE	AMOUNT
1	Green room	Length of 250mm x 75mm diameter	6	937.00	5,622.00
2	Balcony Floor (Auditorium)	Length of 650mm x 50mm diameter	11	2,275.00	25,025.00
3	Balcony First level Beam	Length of 250mm x 50mm diameter	10	875.00	8,750.00
		TOTAL			39,397.00

Thanking you,

Yours Faithfully,

(C.P. SACHITHANANDAM)

U. R. Nagarojan. MEC

2155

Zun militarilar



Engineers and Government Licenced 'A' Grade Contractors'

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

To

The Director,

Kalakshetra Foundation,

Thiruvanmiyur,

Chennai - 600 041.

Dear Sir,

SUB: -Electrical Installation to be carried out for M/s. Kalakshetra at Chennai -Submission of Rate Approval Reg.

REF: - Your Order No: C:\2009-2010\V.Admin\2.Engineering\i.Plan\ Koothambalam \ Electrical Installation work.doc. Dt.28.09.2010.

With Reference to the above, we like to inform you that the core cutting has to be made Due to site condition for the purpose of network cabling system at the various location in the Koothambalam area and the rate for the same is submitted herewith for your kind approval. A This is a Extra work her covered in the tender.

The quotation received from the principles is attached herewith for your kind reference

Awaiting for your kind confirmation

		Rates for core cutting		A 11 / FREE	
SI.No.	Location	Description	Qty.	Rate	Amount
1	Green Room	Lenth of 250mm X 75mm Dia.	6	1078.00	6,468.00
2	Balcony Floor (Additorium)	Lenth of 650mm X 50mm Dia.	11	2616.00	28,776.00
3	Balcony First Level Beam	Lenth of 250mm X 50mm Dia.	10	1006.25	10,062.50
			Т	OTAL	45,306.50

Thanking You,

Yours faithfully,

For Kevin Electricals Pvt Ltd

Wilson Susai Raj (Managing Director) APPROVED

VELACHER'

27.10.2011.

ME

Branch Office:

: # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road, Bangalore

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank) Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

ELECTRICAL INSTALLATION WORK AT KOOTHAMABALAM - Additional items

Annexure (c)

										Balance Amount Payable	
										B-1	
										Payment made	
									ng	5% Testing and Commissioning	
										5% Retention	
										Less 15% On Advanced	
										Grand Total	
										Add S.T 10.3% On Erection	
										Sub Total	
										Discount On 3%	
442840.00	442840.00 227702.5										
6,70,547.50	6,70,547.50	6,70,542								Grand total	
2,27,702.50		2,27,702.50			4,42,840.00					Total	
/							-				
22,021.000	-	22,021.30	. 0	0					LE (NYFAZ)	4.0 SQMM SPEAKAR CABLE (NYFAZ)	11.6
+	+	22 627 50	35 00	+		1					+
3,745.00	3,745.00	3,745.00	35.00	+				1	TO CARI H		+
10,290.00	10,290.00	10,290.00	35.00	294.00					H.		58 11.c
2,360.00		2,360.00	40.00	59.00					IO CABLE		57 11.b
12,875.00	12,875.00	12,875.00	50.00	257.50					DIO CABLE		56 11.a
2,000.00	2,000.00	2,000.00	10.00	200.00	10,500.00	00 35.00	300.00		ľ		55 10.a
8,750.00	8,750.00	8,750.00	875.00	10.00					UTTING		54 9
25,025.00	5,025.00	5,025.00	2,275.00 2	11.00 2					JTTING		53 9
5,625.00	625.00	625.00	937.50 5,	6.00				,	JITING		52 9
3,600.00	,600.00	,600.00	90.00 3	40.00	31,850.00	00 490.00	65.00		ĪNT	ADDITIONAL LIGHT POINT	51 8.b
1,200.00	1,200.00	1,200.00	120.00	10.00	37,000.00	00 925.00	40.00		BY ONE SWITCH		50 8.a
25,350.00	25,350.00	25,350.00	390.00	65.00						200 x 45MM CABLE TRAY	49 7.c
15,510.00	15,510.00	15,510.00	330.00	47.00							48 7.b
18,900.00	18,900.00	18,900.00	300.00	63.00							47 7.a
2,775.00	2,775.00	2,775.00	15.00	185.00	76,500.00	.00 85.00	900.00			3C X 2.5 SQMM CU WIRE	46 6
46,170.00	46,170.00	46,170.00	30.00	1,539.00	1,70,000.00	0.00 85.00	2,000.00				45 5
2,200.00	2,200.00	2,200.00	550.00	4.00	20,000.00	2,500.00	8.00		450X300X150)		44 4
13,000.00	13,000.00	13,000.00	650.00	20.00	82,000.00	20.00 4,100.00	20		(250X250X200MM)	FLOOR MOUNTED BOX (250X250X200MM)	43 3
4,350.00	4,350.00	4,350.00	75.00	58.00	9,860.00	00 170.00	58.00			CEILING FAN BOX	42 2
1,350.00	1,350.00	1,350.00	150.00	9.00	5,130.00	570.00	9.00			FOOT LAMP BOX	41 1
										ADDITIONAL ITEMS	40
Total Qty Rate Total Qty	Qty Rate Total	Total	Rate	Qty	Total	ty Rate	Total Qty	Qty Rate			
		to Date)	ement up	(Measur	up to Date)	(Measurement up to Date)		11 Lender Quantry			NO
Material supply for		TABOTO	ווווו כו	A I AOS	CI IDDI V	MATERIAL SIDDLA		Tandar	DESCRIPTION		_

ELECTRICAL INSTALLATION WORK AT KOOTHAMABALAM - BOO izems

Gn Les 5% 5% Pay	Gn Les 5% 5% Pay	Gri Les 5% 5% Pay	Les 5% 5% Paj	Gn Les 5% 5%	Gn Les	Gn	Gr	Gr	Gr				Λo	Su	Di			NO NO
Dalance Amount Payable				Payment made	5% Testing and Commissioning	5% Retention		Less 15% On Advanced		Grand Total			Add S.T 10.3% On Erection	Sub Total	Discount On 3%			DESCRIPTION
																	+	TINU
		1	-														Qıy	
									-								Rate	Tender Quantity
																	Total	núty
				1			1	1		1		1					Qy	2nd MATER
																	Rate	part bill paymen LIAL SUPPLY () up to Date)
				1		1				1							Total	2nd part bill payment - FOR 2nd PART BILL PAYMENT Tender Quantity ANTERIAL SUPPLY (Measurement FOR LABOUR CHARGES (Measurement up to Date) (Measurement up to Date) Anterial supply for Deduct previous measurement - up to 1st and part bill 1st and part bill 1st and part bill
				1		1	1				-						Qy	2nd P. Port FOR
			-			-	1	1	T			1	1	1			Rate	2nd PART BILL PAYMEN' FOR LABOUR CHARGES (Measurement up to Date)
																	Total	2nd PART BILL PAYMENT FOR LABOUR CHARGES (Measurement up to Date)
																	Qty	Material
																3415950.00	Rate	supply for E
			Ī		Ī										-	0	Total	Material supply for Deduct previous measurement -up to 1st and part bill
_	+	-	-					T	1								Qıy	Labo bill previ
								t								92818.0	Rate	Labour Amount for Deduct previous measurement - up to 1st and part bill
				1		l	T		-		T					_	Total	for Deduct
				İ	T		-	T									Qty	
													ľ				Rate	rial supply f
	1,537,476.24		1,067,909.00	93,913.45	93,913.45		281,740.34				1,794,839.50		1,794,839.30	70.010.0	55 510 50		Total	Material supply for Since last measucement - in this bill value
	4		0				Ī				Č		č				Qty	
																	Rate	Labour Amount for since last measuremnt - in this bill value
340,792.71									1,878,268.94		83,429.44	7,790.78	75,638.66	4.0.7.00	222021		Total	or since last



										3	Lowow		1	Ridgins						ŀ			ŀ	-
77.978.00		1.850.350.00								>		-	1	Table Com	7					1	Grand total	G	+	i
63,138.00	+	2,84,750.00			14,840.00			15,65,600.00			77,978.00		0.00	18,50,350.00		0.00	19,83,050.00		1	1	Total	To	-	_
X								4,800.00	120.00	40.00	630.00	25.00	00 25.20	-	0 120.00	00 40.00		120.00	500.00	sqft	supply crection 14 swg thick junction box with cover	16.01.00 sup	-	
630.00	25.2 25.00																				JUNCTION BOXES	16.00.00 JUI		
\vdash	55 20.00	3,750.00	75.00	50.00	600.00	20	30	3,750.00	75.00	50.00	1,700.00	21	_	-	7	_	7,500.00	7	_	Mtr	60 MM DIA PVC CONDUIT	13.01.04 60	37 13	
0 2,000.00	200 10.00	+	+	200.00							2,000.00	10	00 200	6,000.00	30	0 200	6,000.00	30	200	Mtr	25 MM DIA PVC CONDUIT	13.01.01 25		1:
+	-	\vdash	-								Н					Н	Н		\vdash		Empty pvc conduit	13.00.00 En		
		57,000.00 9	475.00	120.00				23,750.00	475.00		0	-	-			-	+		-	Mtr	200 X 45 MM	200	33	
3,450.00	46 75.00	_	-					21,250.00	425.00	50.00	_	75.00	.00 46.00	0 63.750.00	00 425.00	00 150.00	42 500.00	425.00	100.00	M R	100 X 45 MM 150 Y 45 MM	150	3 3	_
+	1192 600							00 000 00	350.00		,	+	+	+	+	+	-	+	-	-	GI TRUNKING BOX	11.00.00 GI		
5,000.00	100 50	50.00						48,000.00	160.00	300.00	5,000.00	0 50.00	.00 100.00	3 48,000.00	00 160.00	00 300.00	48,000.00	160.00	300.00	Mtr	SUPPLY ERECTION CONNECTING AND COMMISSIONING OF 6 MM THREAD RODWITH SLOTTED CHANNEL	10.03.00 SU	29 10	
0 1,430.00	14.3 100			L				13,750.00	550.00	25.00	1,430.00	0 100.00	.00 14.30	0 13,750.00	550.00	00 25.00	55,000.00	550.00	100.00	Mtr	300 MM (W) X 50 MM (h)	10.02.00 300	28 10	_
+	+										†	+	+			-	-			t	CABLE IRAY	10.00.00 CA	-	_
3,840.00	96 40.00	19,000.00									3,840.00	0 40.00	.00 96.00	0 19,000.00	00 190.00	+	19,000.00	190.00		1- 1	1C X 25 SQMM CU WIRE		26 09	
		60,000.00	12,000.00	5.00				19,200.00	960.00	20.00		150.00	.00 20.00		7	00 20.00	_	1	20.00	Mu Pts	SAME AS ITEM 8.01.00 BUT FOR CEILING FAN POINT	08.03.00 SA		_
4,200.00	70 60							29,400.00	420.00		4,200.00		_		0 420.00		29,400.00	420.00		Pts	SAME AS ABOVE ITEM WITH ADDITIONAL LIGHT POINT Reyof.	08.01.02 SA	23 08	
9,000.00	100 90	27,500.00	550.00	50.00				27,500.00	550.00	50.00	9,000.00	90.00	.00 100.00	0 55,000.00	00 550.00	00 100.00	55,000.00	550.00	100.00	Pts	ONE LIGHT CONTROL WITH ONE SWITCH	08.01.01 Or	22 01	
4											2										SUPPLY WIRING CONNECTING AND COMMISSIONING THE LIGHT POINT WITH 3 RUN OF 1.5 SQMM WITH PVC CONDUIT	08.01.00 SU	21 0	
																					LIGHT POINT WIRING	08.00.00 LI	20 01	
		3,800.00	38.00	100.00	0.00								00	3,800.00	00 38.00	100.00	3,800.00	38.00	100.00	Mtr	32 MM PVC CONDUIT	07.14.00 32	19 0	
					0.00			9,000.00	30.00	300.00		10.00	00 600.00	9,000.00	00 30.00	00 300.00	18,000.00	30.00	600.00	Mu	SUPPLYING AND LAYING OF 25 MM DIA PVC CONDUIT	07.13.00 St	18 0	
12,528.00	1044 12				0.00			2,04,000.00	85.00	2,400.00	12,528.00	00 12.00	0.00 1,044.00	2,04,000.00	35.00	2,400.00	2,38,000.00	0 85.00	2,800.00	Mtr	SUPPLYING AND LAYING CONNECTING AND COMMISSIONING OF 3 CORE 4 SQMM	07.09.00 SL	17 0	
		01,200.00	00.00	200.00	12,000.00	10.00	1,200.00	20,400.00	08.00	300.00	12,000.00	00.00	.00.002,1	81,000.00	00.80	00.000,1	00.000,18	0 68.00	1,200.00	Mtr	OF 3 CORE 2.5 SQMM	O7.08.00 OI	16 0	
		61 200 00	68.00	000 000	12 000 00		1 200 00	20 400 00	68 00		1			-		-			_	-	SUPPLYING AND LAYING CONNECTING AND COMMISSIONING			
3,410.00	341 10	422			0.00			44,000.00	55.00	800.00	3,410.00	10.00	.00 341.00	44,000.00	00 55.00	00 800.00	44,000.00	55.00	800.00	Mtr	SUPPLYING AND LAYING CONNECTING AND COMMISSIONING	07.07.00 SL	15 0	
	3				0.00			46,800.00	130.00	360.00		00 25.00	.00 450.00	0 46,800.00	00 130.00	00 360.00	58,500.00	130.00	450.00	Mtr	SUPPLYING AND LAYING CONNECTING AND COMMISSIONING OF 2 RUN OF 6 SQMM WITH 1 RUN OF 2.5 SQM	07.04.00 SL	14 0	
					0.00			75,000.00	75.00	1,000.00		00 10.00	1,500.00	75,000.00	0.00 75.00	1,000.00	1,12,500.00	0 75.00	1,500.00	Mtr	SUPPLYING AND LAYING CONNECTING AND COMMISSIONING OF 2 RUN OF 4 SQMM WITH 1 RUN OF 2.5 SQM	07.01.00 SL	13 0	
					0.00									-							RAW / UPS POWER WIRING	07.00.00 R	12 0	
					0.00			17,000.00	8,500.00	2.00		700.00	.00 2.00	00 17,000.00	0 8,500.00	.00 2.00	0 17,000.00	8,500.00	2.00	set	UPS MAIN VERTICAL DB	03.06.00 U	_	
					0.00			16,500.00	16,500.00	1.00	-		-			_		_		set			_	
					0.00	00000	2100	8,000.00	8,000.00)		+		-		+	8,000.00	1.00	set		03.04.00 E		
					1,120.00	560.00	2.00	16,000.00	8,000.00	2.00		560.00	00 2.00	00 16,000.00	00.000.00	.00 2.00	0 16,000.00	8,000.00	+	set	LDB - 8 WAY TPN MCB DB		6 0	
										\vdash					-	-	-				MCB DBs	03.00.00 M		_
							72	1,38,000.00	1,38,000.00	1.00	0	4,000.00	0.00 1.00	0.00 1,38,000.00	1,38,000.00	1.00	.00 1,38,000.00	1,38,000.00	ь 1.00	each	AC Panel (Out door type)- Cable etnry bottom, incomer and outgoing	02.04.00 A	4 0	
								2,65,000.00	2,65,000.00	1.00	0	5,000.00	0.00 1.00	2,65,000.00	2,65,000.00	0.00 1.00	.00 2,65,000.00	2,65,000.00	h 1.00	ıs each	DG panel - Cable entry: top and bottom, DG incomer 1, DG Incomer 2, Bus coupler and out going	02.03.00 D	3 0	
								2,30,000.00	2,30,000.00	1.00	0	5,000.00	0.00 1.00	2,30,000.00	2,30,000.00	0.00 1.00	.00 2,30,000.00	2,30,000.00	1.00	set	LT panel - MAIN PANEL - 2 Cable Entry: Top/Bottom and EB&DG Incomer and connecting Out going	02.02.00 L	2 0	
								2,16,000.00	2,16,000.00	1.00	0	5,000.00	0.00 1.00	0.00 2,16,000.00	2,16,000.00	0.00 1.00	.00 2,16,000.00	2,16,000.00	1.00	set	LT panel - MAIN PANEL 1 Cable Entry : Top/Bottom and EB&DG Incomer and connecting Out going	02.01.00 L	-	
te Total	Qty Rate	Total	Rate	Qıy	Total	Rate	Qıy	Total	Rate	Qıy	Total	Rate	al Qty	Total	ty Rate	1 Qŋ	Total	Rate	Qıy					
Labour Amount for since last measuremnt - in this bill value	Labour Amou measuremnt -		Material supply for Since last measurement - in this bill value	1-5	or Deduct ent - up to bill	Labour Amount for Deduct previous measurement - up to 1st and part bill		Material supply for Deduct previous measurement -up to 1st and part bill	supply for D ment -up to 1		2nd PART BILL PAYMENT FOR LABOUR CHARGES (Measurement up to Date)	ART BILL LABOUR	ment FOF	2nd part bill payment - FOR MATERIAL SUPPLY (Measurement up to Date)	2nd part bill paymen ERIAL SUPPLY (1 up to Date)	MAT	Quantity	Tender Quantity	=	TINU	DESCRIPTION	NO	ON	
E O	Annexuse (A)	An		1 tems		BOQ	1	KOOTHAMABALAM	1MAB.	THIC	[KO(W A	IOM I	INSTALLATION WORK AT	[ALL	NS	ELECTRICAL	ECT	E	-				/

Specification for Electrical

S.No.	ISI Codes	Description
(1)	(2)	(3)
01.	IS:3072-1975	Code of Practice for Installation and
02.	IS:732-1963	Maintenance of Switch gear. Code of Proactive for electrical wiring Installations (Systems Voltage not exceeding 1100V)
03.	IS:2274-1963	Code of Practice for Electrical wiring Installation (System Voltage exceeding 1100V)
04.	IS:3043-1966	Code of Proactive for Earthing Ceiling fan
05.	IS:374	Aluminum Bus bar
06.	IS:375	Paints
07.	IS:631	Wires
08. 09. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19.	IS:694 IS:732 IS:1293 IS:1897/2927 IS:1951 IS:2551 IS:4064/1978 IS:5077 IS:5216/1982 IS:7752/1975 PART I IS:8623 IS:8828 IS:13947 PART II	Wires Wiring Installation 5A & 15A Switches & Sockets Lugs & Sockets PVC Pipes Specifications for Danger Plates Four Pole Switches & Sockets Light Fittings Safety in Electrical work general Guide for PF Improvement (L.V. & M.V.) MCB DBs MCBs. Air Circuit Breaker / Fuse Switch Units /
21.	IC:12047 DADT IV	Module case Circuit Breaker.
22.	IS:13947 PART IV IS: 722	Contractor / Over load Relays
23.	IS 2705	AC Electric Meters Current Transformers
24.	IS 3156	Voltage Transformer
25.	IS 3231	Electrical Relays for Power System Production
26.	IS 5578	Guide for making of insulated conductors
27.	IS 10118	Code of Practice for selection, installation and
		Maintenance of Switchgear and controlgear.
28.	IS 11353	Conductors and apparatus terminals.
29.	IS 13947(Part -1)	Low Voltage Switch-gear - General Rules

S.No.	ISI Codes	Description
(1)	(2)	(3)
30.	IS 13953	Low Voltage Switch-gear - General Rules
31.	IS 13947 (Part 2)	Low Voltage Switch-gear - Circuit Breakers
32.	IS 13947 (PART 3)	Low Voltage Switch-gear and Control gear – Switches Disconnectors, Switch Disconnectors, and Fuse Combination Switches.
33.	IS 13947(PART 4)	Low Voltage Switch-gear and controlgear – Contactors and Motor Starters

All electrical equipment and installation shall also conform to the latest Indian Electricity Rules as regard Safety, earthling and other essential provisions specified therein for installation and operation of electrical plants.

02. DESIGN

SITE CONDITIONS

All equipment shall be designed for operation in tropical climate for 35 Deg. C ambient as a 24 hours average with a short time of maximum of 45 Deg. C and relative humidity of 100%. Maximum temperature and maximum humidity however are not likely to occur simultaneously. The derating of all equipment shall be done for if specifically mentioned in the Technical Specification. The equipment to be installed outdoor subject to direct incidence of sun rays shall be deigned for operation at a maximum ambient temperature of 50 Deg.C and shall be weather proof design.





CITY UNION BANK LIMITED 67.Mandaveli Street Mandaveli,Chennai 28

Date: 08.06.2013 Place: Chennai

To

Kalakshetra Foundation, Kalakshetra, Tiruvanmiyur Chennai 600041

Dear Sir,

Sub:Bank Guarantee No: 37351 dated: 16.11.2012

For: Rs 5,25,545/- (Rupees Five lakhs Twenty five tousand five hundred and forty five only)

Issued on behalf of: M/s Kevin Electricals P LTd

Date of expiry of the Bank Guarantee: 15.05.2013

With reference to the above, we have to inform that the Bank Guarantee bearing no 37351 dated 16.11.2012 issued for Rs 5,25,545/- on behalf of M/s Kevin Electricals P LTd expired on 15.05.2013. We have not yet received the expired bank guarantee for cancellation and reversal of the liability entries in our books of accounts, even after a lapse of almost one month.

We therefore request you to kindly arrange to send back the expired original bank guarantee immediately. Please note that our liability under the said expired bank guarantee has already ceased effective from 15.05.2013 and no legal claim under the bank guarantee can be preferred by you from the date viz., as a holder of the expired bank guarantee.

Please treat this as urgent and return back the expired bank guarantee at the earliest.

Thanking you,

Yours faithfully,

Copy to:

1 Central Office, Kumbakonam.

2 Kevin Electricals P Ltd

No7, Old no 1-B, Arunachalapuram II Street, Adyar, Chennai 20.

659

C:\ 2009-2010-2013\V.Admin\2. September 5, 2013
Engineering\i.Plan\Koothambalam\ Electrical installation work.doc

M/s. Kevin Electricals Pvt Ltd., Engineers and Government Licensed A Grade Contractors, No 7, (Old No1 –B) Arunachalapuram, II street, Adyar, Chennai 600 020

Sir/s,

Sub: Koothambalam -Kalakshetra Foundation – Termination of contract with M/s.CARD intimation – Reg.

This is to inform you that M/s.CARD is now no longer the architect for the Kalakshetra Foundation project as his service has been terminated.

It is requested that you should present on 30.09.2013 at 11.00 am in the Koothambalam site / Kalakshetra Foundation along with M/s.CARD to record the joint inspection and measurement for assessing the status / value of work that have therefore been executed by you.

This issues with the approval of competent authority

Yours faithfully

S.Ramachandran.

Administrative Officer.



BILL

TEM NO.	DESCRIPTION			SUPPI	Y (Rs.)	ERECT	ION (Rs.)
		Qty	Unit	RATE	AMOUNT	RATE	AMOUNT
	Supplying, erecting 14 G thick Junction boxes with cover of 40 mm. height of suitable sizes as per Site conditions. The Junction boxes shall be fixed flush with the floor (powder coated)	40	SQ.FT	120.00	4,800.00		AMACONT
	Total 250 10 10 10 10				1,857,800.00		24,400.00
	Discount 3%				55,734.00		732.00
	Total				1,802,066.00		23,668.00
	Add: Service Tax 10.3% on Erection						2,438.00
					1,802,066.00		26,106.00
	Grand Total (Rupees Eighteen Lakhs Twenty Eight Thousand One Hundre						1,828,172.00

FOR KEVIN ELECTRICALS PVI

	DESCRIPTION			SUPF	LY (Rs.)	EREC	ΓΙΟΝ (Rs.)
00.01.0		Oty	Unit	RATE	AMOUNT	RATE	AMOUNT
08.01.00	Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Eartl) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc. including supplying and fixing 6 Amps. Switch in manufacturers mounting box fixed flush with the wall.	1 F-	270-3	D - 180 49	30-2 B		TAVIC CIVI
	A2	50				-	
08.01.01	One Light Controlled by one Switch	100	Pts.	550.00	55,000.00		
08.01.02	Same as above item with additional light point.	V70	Pts.	420.00	29,400.00		
08.03.00	Same as the Item No. 08.01.00 but for Ceiling Fan points including supplying, and fixing concealed type fan hook box and electronic regulator.	20	Pts.	1,200.00	24,000.00		
10.00.00	CABLE TRAY	10				/	
10.02.00	Supplying, fabricating, erecting, connecting & commissioning of the Perforated type GI Cable Trays with necessary Angle irons for cable supports and other allied fabrication works. Fixing to concrete surfaces shall be done with the help of expandable type anchor fastners capable of bearing a weight of 500 Kgs. Fixing to brick walls shall be done with grouting. The distance between two supports shall be 2000mm. Thematerials and labour for grouting, cable supportsand Provision for fixing allied fabrication work shall supplied by the contractor with provision for fixing Gi flats Throughout with connection point once every mtrs. on both sides all supports shall be with threaded rods once every 1500mm.	95	25				
	300 mm (w) x 50 mm (H)	(30	Mtrs	550.00	16,500.00)	
	Supplying, erecting, connecting & commissioning of the 6 mm thread rod with slotted channel supports and welded in the stress supports for the GI trunking and related to all accessories etc.	300	Mtrs	160.00	48,000.00	/	-
1.00.00	G I TRUNKING						
	Supplying, fabricating, laying and connecting the following GI TRUNKING with cover of 1.6 mm. Thick embedded in the floor (or) open in ceiling / laid in below false flooring with thread rod and rail supports including of L shape,T shape and necessary support,clamps screws and all accessories etc.	. v			9		
	100 x 45 mm	150)	MTS	350.00	52,500.00	60.00	9,000.00
	150 x 45 mm	100	MTS	425.00	42,500.00	75.00	7,500.00
	200 x 45 mm.	(50)	MTS	475.00	23,750.00	90.00	4,500.00
3.00.00	EMPTY PVC CONDUITS	9				7	F
	Supplying, laying of Heavy duty PVC conduit laid in floor/concealed in wall / partitions with accessories, necessary clamps, screws etc.	-				1	
3.01.04	60 mm. dia PVC Conduits	50	Mts	75.00	3,750.00	1	_
1		1	-				
3.01.04	60 mm. dia PVC Conduits	30	Mts			20.00	600.00

50 ruis

FOR KEVIN ELECTRICALS PVT. LTU.,

Page 6 of 7

ITEM NO	D. DESCRIPTION			SUF	PPLY (Rs.)	FRECT	ΓΙΟΝ (Rs.)
		Oty	Unit	RATE	AMOUNT	RATE	AMOUNT
	8 Way TPN VERTICAL MCB DB					MILE	AMOUNT
	Y (2) 1						
	Incomer: 63 Amps TP2N MCB 1 No.	_		/	/	/	
	Outgoing: 10-32 Amps SP MCB 18 Nos	-	o Cour	0.500.0		1	
	sugarig. 10 027 mips of Wieb 10 Nos	-	2 Sets	8,500.0	0 17,000.00)	-
07.00.00	RAW/UPS POWER WIRING	-			-		
07.01.00	Try-6, my mb connecting a continuosioning 2 Kuns of 4		0 5	Johnya.	-		
	Sq.mm. with 1 Run of 2.5 Sqmm. PVC Insulated stranded single		4.5	100			
	core copper conductor FRLS wire for continuous earthing in already laid PVC Conduits open above false ceiling, or concealed		8-	5	= 90	"I	
	in wall / ceiling with necessary lamps scrows at them DR to			1-9	95		
	Power Points.	150	0 Mts.	1	112 500 0		
		150	U IVILS.	75.00	112,500.00		-
07.04.00	Supplying, laying, connecting & commissioning 2 Runs		0.5				
	of 6 Sq.mm. with 1 Runs of 2.5 Sqmm. PVC Insulated	-	0.				
	stranded single core copper conductor FRLS wire for continuous earthing in in PVC Conduits open above false		4-	1			
	ceiling or concealed in wall / ceiling with necessary	180	Black		1		
	lamps, screws etc. 36 Spry.	450	Mts.	130.00	58,500.00		_
05 05 00	- 0		8//	-			
07.07.00	Supplying, laying, connecting & commissioning 3 Runs of 2.5	P	1500/	200 %-	240-3		R - 180
	Sq.mm.PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in already laid PVC Conduits	/	24	0-	140-5		24
	open above false ceiling or concealed in wall / ceiling with	Men	W-AP	-	1	& 130m	90
	necessary lamps, screws etc from DB to Power Points.	10 11.			Jun grun		
		800	Mts.	55.00	44,000.00		
07 00 00							
07.08.00	Supplying, laying, connecting & commissioning 3 core 2.5						-
	Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) open in ceiling or concealed in wall / ceiling with		1				
	necessary lamps, screws etc from DB to stage focus light point.	90		/			
	Quality (C)	1	Mts.	68.00	81,600.00		
		1200	ivits.	08.00	81,000.00	/	-
07.09.00	Supplying, laying, connecting & commissioning 3 core 4						
	Sq.mm.PVC Insulated flexiable copper cable in already laid PVC						
	Conduits (or) GI tray open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus	LACIO	CAR				
	light point.	2000	Mts.	07.00			
	244	2800	Mts.	85.00	238,000.00)	-
07.10.00	Supplying, laying, connecting & commissioning 3 core 6					/	
	Sq.mm.PVC Insulated flexiable copper cable in already laid PVC						
	Conduits (or) GI tray open in ceiling or concealed in wall /	4					
	ceiling with necessary lamps, screws etc from DB to stage focus light point.	(A)	Mts.			1	
	agree point.	(300	Mts.	135.00	40,500.00)	
7.11.00	Supplying, fixing, connecting and commissioning of 16					/	
	AMPS SPN MENNEKES make schuko model of 2 pin and						
700 1210	type plug and socket in Manufacturer's mounting box fixed flush with the wall. For music equipment.(german		V				2,4
	make)	60	Nos.	1 050 00	42 200 00	\	
		(40	NOS.	1,050.00	42,000.00	}	-
7.13.00	Supplying and laying of 25mm. Dia Heavy duty PVC				1		
	Conduits concealed / open in wall / ceiling etc. with						
	necessary clamps, screws etc. with 1 Run of 16 SWG	300		/	1		*
	G.I. Fish wire.	600	Mtrs	30.00	18,000.00		-
08.00.00	LIGHT POINT WIRING	30)				
		-					

FOR KEVIN ELECTRICALS PVT. LTD.,

2163)

ITEM NO	DESCRIPTION			SUPP	LY (Rs.)	ERECTI	ON (Rs.)
	BUSBAR : ALUMINIUM	Oty	Unit	RATE	AMOUNT	RATE	AMOUNT
	DUSDAR: ALUMINIUM						
	RATING: 250 AMPS		,				
	The Dhace Pure househall be 40 a 10 areas and the Nove 11						
	The Phase Bus bar shall be 40×10 mm. and the Neutral bar shall be 25×6 mm. The Earth Bus bar shall be $2 \text{ Runs of } 25 \times 3$ mm.						
	There shall be ONE set of Metering Compartment incorporated with the following:-				,		
	i) CTs of ratio 250/5A and Class 0.5 for metering and burden 10 VA.						
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 250 A) with Inbuilt Selector Switch.						
	iii) RYB LED Cluster type Indicating Lamps and Control			/			
	fuses shall be provided.	1	/	138,000.00	138,000.00		-
03.00.00	MCB DBs	/					
	Part Indiana. National American						
	Supplying, fixing, connecting & commisioning the following MCB DISTRIBUTION BOARDS fixed flush with the wall. All DBs shall have Double door. Lighting and Power DB - C curve and UPS DB - D curve						
03.01.00	LDB						
	8 Way TPN MCB DB						
	oving arranged by						
	Incomer: 63 Amps 4P ELMCB,30mA 1 No.				/		
	Outgoing: 6-16 Amps SP MCB 24 Nos.	2	Sets	8,000.00	16,000.00	700.00	1,400.00
02.02.00	1	/		0,000,00	10,000.00	700.00	1,100.00
03.03.00	PDB						
	8 Way TPN MCB DB						
	Incomer: 63 Amps 4P ELMCB,30mA 1 No.	i i					
	Outgoing: 6-16 Amps SP MCB 24 Nos.	2	Sets	8,000.00	16,000.00	700.00	1,400.00
03.04.00	External LDB						
03.04.00	8 Way TPN MCB DB						
	Incomer: 63 Amps 4P ELMCB,100mA 1 No.			1	/	1	
	Outgoing: 6-16 Amps SP MCB 24 Nos.	1	Set	8,000.00	8,000.00		-
03.05.00	AHU Vertical DB						
	8 Way TPN VERTICAL MCB DB						
	Incomer: 125 Amps 4P MCCB with 25 Ka Ics with standing capacity 1 No.						
	Outgoing: 63 Amps TP MCB 1 No.						
	Outgoing: 32 Amps TP MCB 7 Nos.	1	Set	16,500.00	16,500.00		
03.06.00	UPS Main Vertical DB						

FOR KEVIN ELECTRICALS PVT. LTD

069

ITEM NO.	DESCRIPTION			SUPP	LY (Rs.)	ERECT	ION (Rs.)
		Qty	Unit	RATE	AMOUNT	RATE	AMOUNT
	DG INCOMER 1: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.						
	DG INCOMER 2: 315 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.						
	BUS COUPLER: 315 AMPS 4P MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.						
	Note: All the incomer and Buscoupler are electrical and mechanical interlock with auto/manual selector switch.			·			
	OUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays4 Nos.						
	BUSBAR : ALUMINIUM						
	RATING: 315 AMPS						
	The Phase Bus bar shall be 50×10 mm. and the Neutral bar shall be 25×06 mm. The Earth Bus bar shall be 2 Runs of 25×6 mm.						
	There shall be TWO set of Metering Compartment incorporated with the following:-						
	i) CTs of ratio 250 & 315 /5A and Class 0.5 for metering and burden 10 VA.						
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 & 315 A) with Inbuilt Selector Switch.	e					
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.		1	265,000.00	265,000.00		
02.04.00	AC PANEL (OUTDOOR TYPE)						
	CABLE ENTRY: BOTTOM						
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated AC PANEL (outdoor type). The Board shall be incorporated with the following:-				,		
	INCOMER: 250 AMPS 4P MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.						
	OUTGOING: 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays2 Nos.						
	100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos.						Y
	32 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays5 Nos.						

265

FOR KEVIN ELECTRICALS PVT. LTD.,

ITEM NO.	DESCRIPTION			SUPP	LY (Rs.)	ERECT	TION (Rs.)
		Oty	Unit	RATE	AMOUNT	RATE	AMOUNT
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch.			11112	7117100111	MIL	AMOUNT
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.		1 Set	216,000.00	216,000.00		-
02.02.00	MAIN PANEL - 2						
	CABLE ENTRY: TOP/BOTTOM						
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated MAIN PANEL -2. The Board shall be incorporated with the following:-						
	EB & DG INCOMER: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos.						
	OUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays1 No. 125 AMPS TPN MCCB with 25 KA (Ics)						
	125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos.	٠					
	100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos.						
	BUSBAR : ALUMINIUM						
	RATING: 250 AMPS						
	The Phase Bus bar shall be 40×10 mm. and the Neutral bar shall be 25×6 mm. The Earth Bus bar shall be 2 Runs of 25×3 mm.						
	There shall be TWO set of Metering Compartment incorporated with the following:-						
	i) CTs of ratio 200/5A and Class 0.5 for metering and burden 10 VA.				9		
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch.						
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.	1	(230,000.00	230,000.00		_
02.03.00	DG PANEL						
	CABLE ENTRY: TOP/BOTTOM						
	Supplying,Erecting,Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated DG PANEL. The Board shall be incorporated with the following:-						

Qsbb Cork

FOR KEVIN ELECTRICALS PVT. LTD.,

Page 2 of 7



Engineers and Government Licenced 'A' Grade Contractors No. 7, (O. No. 1-B) Arunachalapuram, Ilnd Street, Adyar, Chennai - 600 020. ②: 24466938, Telefax: 24912704

E-mail: kevinelectrical@yahoo.co.in Web: www.kevinelectricals.com TIN No.: 33680862581

TNGST No.: 0862581 / 2003-2004

CST No.: 794079 / Dt. 13-10-2003

Area Code No.

0 4 4

To

The Director, Kalakshetra Foundation Thiruvanmiyur, Chennai - 600 041. Bill.No:134 Date:28.03.2011

Name of Work:- Electrical Installation work for M/s. Kalashetra Foundation at Chennai.

ITEM NO.	DESCRIPTION			SUPI	PLY (Rs.)	ERECT	ON (Rs.)
		Oty	Unit	RATE	AMOUNT	RATE	AMOUNT
	1						
2.00.00	LT PANEL						•
2.01.00	MAIN PANEL - 1					,	
	CABLE ENTRY: TOP/BOTTOM						
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet					1	
	compartmentalised modular type with powder coated MAIN PANEL -1. The Board shall be incorporated with the following:-					3	i i
	TR 4 DO 11/2017 TR 4 TR						
	EB & DG INCOMER: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos.						
		2 - 22					
	OUTGOING: 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and					,	
	Fixed short circuit relays1 No.						
	100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays1 No.						/
	63 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos.					-	
	32 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays4 Nos.	0.				- (_ ,	
a	Shorteneur realys 1405.						7
	BUSBAR : ALUMINIUM						
	DOOD IN THE OWN						
	RATING: 250 AMPS					-	
	KATIIVG. 250 AWI 5						,
	The Phase Bus bar shall be 40 x 10 mm, and the Neutral bar						
	shall be 25 x 6 mm. The Earth Bus bar shall be 2 Runs of 25 x 3 mm.						-:
	There shall be TWO set of Metering Compartment incorporated with the following:-						
	i) CTs of ratio 200 /EA and Class 0.5 (-				
	i) CTs of ratio 200/5A and Class 0.5 for metering and burden 10 VA.						



For KEVIN ELECTRICALS PVT. LTD.,

Page 1 of 7





Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. REF: KE/KF/644/2011/890 : 24466938, 24468401. Fax : 24912704 E-mail : kevinelectrical@yahoo.co.in

28.03.2011

To

The Director, Kalakshetra Foundation, Thiruvanmiyur, Chennai - 600 041.

Dear Sir.

SUB: - Electrical Installation to be carried out for M/s. Kalashetra at Chennai - Submission of RA.Bill - 1- Reg.

REF: - Your Order No: C:\2009-2010\V.Admin\2.Engineering\ i.Plan \ Koothambalam \ Electrical Installation work.doc Dt.28.09.2010.

With reference to the above, we are herewith submitting the RA.Bill - 1 for the above mentioned work

Bill Value (Bill.No:134 Dt.28.03.2011)

Rs.18,28,172.00

Less:

15% Advance Adjusted prorata Basis

Rs.2,74,225.80

5% Retention

Rs. 91,408.60

5% Commissioning

91,408.60

Amount to be payable

Rs. 4,57,043.00

Rs.13,71,129.00

We request you to kindly arrange to release the Payment of at the earliest & oblige.

Thanking you, Yours faithfully,

for Kevin Electricals Pvt Ltd,

ilson Susai Raj

Branch Office:

Bangalore : # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank)

Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in

TEM NO.	DESCRIPTION	LL		SUF	PPLY (Rs.)		ERECTION (I	Rs.)
		Qty	Unit	RATE	AMOUNT	Qty	RATE	AMOUNT
	Supplying, laying of Heavy duty PVC conduit laid in floor / concealed in wall / partitions with accessories, necessary clamps, screws etc.		,		/			
а	25 mm. dia PVC Conduits	300	Mts	35 _	10,500.00	200	10	2,000.0
11	Charges of laying for speaker cable laying in Tray /wall / ceiling or open above false ceiling with necessray clamps screws etc.				in the second			
а	12 core balanced audio cable (mistral mcf 12)					257.5	50	12,875.0
b	8 core balanced audio cable (Planet fmc 08)					59	40	2,360.0
С	6.0 sqmm speaker cable (meridian sp 260)					294	35	10,290.0
d	1core balanced audio cable (sc - source mkii)					107	35	3,745.0
е	4 sqmm speaker cable (NYFAZ)					646.5	35	22,627.5
f	Binary 434 cable						30	-
				230,6	190			
	Total				23,21,490.00		307680	5 (3,07,620.5
	Discount 3 %			69,185.	7 (69,644.70)		9170	42 9,228.6
	Total		2	237004	22,51,845.30		296510.	2,98,391.8
	Add: Service Tax 10.3% on Erection						30540	30,734,0
			2	2,37,004	22,51,845.30		327050	64 3,29,125.8
(Grand Total		-					25,80,971.19

FOR KEVIN ELECTRICALS PVT. LTD.,



Erecetton

Amount

6,99,790.00

3,02,840.50

Discount 31.

20,993.70

9085.21

2,93,755,29

total

6,78,796.3 -1

30256.79

Add 10.3% on Errest

324012.08 -B

1002808.38/ Grand lotal (A+B) Advance Adjornable on :154. 852387.17/-

TEM NO.	DESCRIPTION	LL		SUF	PPLY (Rs.)			ERECT	TION (F	ks.)
		Qty	Unit	RATE	AMOUNT	Qty	/	RATI	3	AMOUNT
2	Supplying, fixing of Ceiling fan box with necessary clamps, screws etc.	58	Nos	170 -	9,860.00	58		75		4,350.0
3	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated door type POWER TRUNKING BOX. (250 X 250 X 200 mm)With 32 Amps 3pin metal clade socet with top. necessary support, clamps screws and all accessories etc.	20	Nos	4,100	82,000.00	20		650	_	13,000.0
4	Supplying, Erecting, Testing & commissioning FLOOR/WALL MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated door type cable connector box. (450 X 300 X 150 mm)With 25 Amps clip on type terminal block connector necessary support, clamps screws and all accessories etc.	8	Nos	2,500	20,000.00	4	/	550	(2,200.0
5	Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc.	2000	Mts	85	1,70,000.00	1539	_	30		46,170.0
6	Supplying, laying, connecting & commissioning 3 core 2.5 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	900	Mts	85	76,500.00	-185		15		2,775.0
7	Charges for laying, Removing and Reerecting the following GI TRUNKING with cover of 1.6 mm. Thick embedded in the floor (or) open in ceiling / laid in below false flooring with thread rod and rail supports including of L shape,T shape and necessary support,clamps screws and all accessories etc.			,						
a	100 x 45 mm					63	/	300		18,900.0
									-	10,700.0
b	150 x 45 mm					47	/	330	-	15,510.0
						~	and the same of th			
С	200 x 45 mm.					65	/	390	-	25,350.0
8	Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc. including supplying and fixing 6 Amps. Switch in manufacturers mounting box fixed flush with the wall.									
						1				V
a	One Light Controlled by one Switch	40	Pts.	925	37,000.00	10	/	120	-	1,200.0
b	Same as above item with additional light point.	65	Pts.	490	31,850.00	40	PA	90	/	3,600.00
~										
						1	~		937	1
9	Charges of core cutting for speaker cabling					-		-		-
9	Lengh of 250mm X 75mm Dia					6.	0	938		
9	Lengh of 250mm X 75mm Dia Lengh of 650mm X 50mm Dia					11		938 2,275		5,625.0 25,025.0
9	Lengh of 250mm X 75mm Dia							938	(

J. Na . Bonker

FOR KEVIN ELECTRICALS PVT. LTD.

TEM NO.	DESCRIPTION	LL		SUI	PPLY (Rs.)			ERECTION (Rs.)
		Qty	Unit	RATE	AMOUNT	Qty		RATE	AMOUNT
10.02.00	Supplying, fabricating, erecting, connecting & commissioning of the Perforated type GI Cable Trays with necessary Angle irons for cable supports and other allied fabrication works. Fixing to concrete surfaces shall be done with the help of expandable type anchor fastners capable of bearing a weight of 500 Kgs. Fixing to brick walls shall be done with grouting. The distance between two supports shall be 2000mm. Thematerials and labour for grouting, cable supportsand Provision for fixing allied fabrication work shall supplied by the contractor with provision for fixing Gi flats Throughout with connection point once every mtrs. on both sides all supports shall be with threaded rods once every 1500mm.								
	300 mm (w) x 50 mm (H)	25 <	Mtrs	550	13,750.00	14.3		100	1,430.0
	Supplying, erecting, connecting & commissioning of the 6 mm thread rod with slotted channel supports and welded in the stress supports for the GI trunking and related to all accessories etc.	300	Mtrs	160	48,000.00	100		50	5,000.0
11.00.00	G I TRUNKING								
	Supplying, fabricating, laying and connecting the following GI TRUNKING with cover of 1.6 mm. Thick embedded in the floor (or) open in ceiling / laid in below false flooring with thread rod and rail supports including of L shape,T shape and necessary support,clamps screws and all accessories etc.							1	
	100 x 45 mm	150	Mts	350	52,500.00	119.2	1=	60	7,152.0
	150 x 45 mm	(150)	Mts	425	63,750.00	46	2	75	3,450.0
	200 x 45 mm.	170	Mts	475	80,750.00	97.2	7	90	8,748.0
13.00.00	EMPTY PVC CONDUITS				57000				
13.01.00	Supplying, laying of Heavy duty PVC conduit laid in floor / concealed in wall / partitions with accessories, necessary clamps, screws etc.	2	00		7000.	a	00		200
13.01.01	25 mm. dia PVC Conduits	500	Mts	35 /	17,500.00	338	-	10 -	(3,380.0
3.01.02	32 mm. dia PVC Conduits	100	Mts	40	4,000.00	65	7	10 –	650.0
3.01.04	60 mm. dia PVC Conduits	100	Mts	75	7,500.00	(85)	_	20	(1,700.0
6.00.00	JUNCTION BOXES				3150	55			1100
6.01.00	Supplying, erecting 14 G thick Junction boxes with cover of 40 mm. height of suitable sizes as per Site conditions. The Junction boxes shall be fixed flush with the floor (powder coated)	40	SQ.FT	120	4,800.00	25.2		25	630.0
	·		-						
	ADDITIONAL ITEMS Supplying, fixing of Foot lamp box with front plate and necessary clamps, screws etc.	9	Nos	570	5,130.00	9	pA.	150	1,350.0

C. Or. Bought

FOR KEVIN ELECTRICALS PVT. LTD.,

ITEM NO.	DESCRIPTION	LL		SUP	PLY (Rs.)		ERECTION (F	s.)
		Qty	Unit	RATE	AMOUNT	Qty	RATE	AMOUNT
07.14.00	Supplying and laying of 32 mm. Dia Heavy duty PVC Conduits concealed / open in wall / ceiling etc. with necessary clamps, screws etc. with 1 Run of 16 SWG G.I. Fish wire.	100	Mtrs	38	3,800.00	~ 7	12	-
08.00.00	LIGHT POINT WIRING		-					
08.01.00	Supplying, wiring, connecting and commissioning the light points with 3 Runs of 1.5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / ceiling or open above false ceiling with necessary clamps screws etc. including supplying and fixing 6 Amps. Switch in manufacturers mounting box fixed flush with the wall.	50			27500	G0	7	
		100)	Pts.	550	55,000.00	(100)	90	9,000.0
08.01.01	One Light Controlled by one Switch				(20,000,00	100	70	2,000.0
		70	Pts.	420	29,400.00	70	60	4,200.0
08.01.02	Same as above item with additional light point.							
08.03.00	Same as the Item No. 08.01.00 but for Ceiling Fan points including supplying, and fixing concealed type fan hook box and electronic regulator.	20	Pts.	1,200	24,000.00			
09.00.00	EARTHING			. 001.				
09.00.00	EARTHING							
09.02.00	Supplying, installing and connecting a Copper plate of size 600mm.x 600 mm.x 3 mm. at a depth of 3000 mm. in an earth pit of 700 x 700 x 3500 mm. filled with salt and charcoal mixed with sand in alternate layers 150 mm. each upto a height of 3000 mm. from bottom. Two copper flats of 25 x 6mm. shall be braced to this copper plate throughout the overlaping length with the copper plate and brought to the surface of the earthpit. This copper flat shall have provision for connecting wires of flats as the case may be. A suitable size of 40 mm. dia GI Pipe shall be provided uptil the bottom of the earth pit. This GI Pipe shall have provision for watering through a funnel. A masonary strucutre shall be constructed to a depth of 450mm. and a heavy duty CI Cover shall be used to cover the pit. The cost of digging and back filling shall also be included . Sand, salt and charcoal are in the Contractor's scope.	5	Sets	13,000	65,000.00	1	2,500	-
	Supplying, laying and connecting 25 Sq.mm.PVC Insulated copper conductor wires in PVC Conduits laid open fashion with necessary clamps, screws, interlinks etc.	100-	Mtr	260	26,000.00	96 .	40 ~	3,840.00

J. Va. Bakes

FOR KEVIN ELECTRICALS PVT. LTD.,

Managing Director

(272

TEM NO.	DESCRIPTION	LL		SUP	PLY (Rs.)		ERECTION (I	Rs.)
		Qty	Unit	RATE	AMOUNT	Qty	RATE	AMOUNT
	8 Way TPN VERTICAL MCB DB							
	o may irin ventrere mee ee							
	Incomer: 125 Amps 4P MCCB with 25 Ka Ics with standing capacity 1 No.							
	Outgoing: 63 Amps TP MCB 1 No.		-					
	Outgoing: 32 Amps TP MCB 7 Nos.	1 .	Set	16,500	16,500.00	_		
03.06.00	UPS Main Vertical DB							
	8 Way TPN VERTICAL MCB DB							
	Incomer: 63 Amps TP2N MCB 1 No.							
	Outgoing: 10-32 Amps SP MCB 18 Nos	2	Sets	8,500	17,000.00			
07.00.00	RAW/UPS POWER WIRING							
07.01.00	Supplying, laying, connecting & commissioning 2 Runs of 4 Sq.mm. with 1 Run of 2.5 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in already laid PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to Power Points.	1000,	Mts.	75	75,000.00			
07.04.00	Supplying, laying, connecting & commissioning 2 Runs of 6 Sq.mm. with 1 Runs of 2.5 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in in PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc.	360	_Mts.	130	46,800.00			
07.07.00	Supplying, laying, connecting & commissioning 3 Runs of 2.5 Sq.mm.PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in already laid PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to Power Points.	800	Mts.	55	44,000.00	341	10	3,410.00
7.08.00	Supplying, laying, connecting & commissioning 3 core 2.5 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	300 1200		68	20 40 0	1200	10 /	12,000.00
07.09.00	Supplying, laying, connecting & commissioning 3 core 4 Sq.mm.PVC Insulated flexiable copper cable in already laid PVC Conduits (or) GI tray open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	2400	Mts.	85	2,04,000.00	1044	12	12,528.00
7.13.00	Supplying and laying of 25mm. Dia Heavy duty PVC Conduits concealed / open in wall / ceiling etc. with necessary clamps, screws etc. with 1 Run of 16 SWG G.I. Fish wire.	300 4	Mtrs	30	9,000.00	,	10	-

J. Pa. Togone

FOR KEVIN ELECTRICALS PVT. LTD.,

TEM NO.	DESCRIPTION	ILL		SU	PPLY (Rs.)		ERECTION (Rs.)
		Qty	Unit	RATE	AMOUNT	Qty	RATE	AMOUNT
	OUTGOING: 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays2 Nos.							
	100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos.							
	32 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays 5 Nos.							
	BUSBAR : ALUMINIUM							
	RATING: 250 AMPS							
	The Phase Bus bar shall be 40×10 mm. and the Neutral ba shall be 25×6 mm. The Earth Bus bar shall be 2 Runs of 25×3 mm.							
	There shall be ONE set of Metering Compartment incorporated with the following:-							
	i) CTs of ratio 250 /5A and Class 0.5 for metering and burden 10 VA.							
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 250 A) with Inbuilt Selector Switch.							
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.	1		1,38,000	1,38,000.00	-1		-
03.00.00	MCB DBs							
	Supplying, fixing, connecting & commissioning the following MCB DISTRIBUTION BOARDS fixed flush with the wall. Al DBs shall have Double door. Lighting and Power DB - C curve and UPS DB - D curve							
03.01.00	LDB							
	8 Way TPN MCB DB							
	Incomer: 63 Amps 4P ELMCB,30mA 1 No.						MA	1,00
·/	Outgoing: 6-16 Amps SP MCB 24 Nos.	2	Sets	8,000 -	16,000.00	2	(700)	1,400.00
03.03.00	PDB	-	- CCLS	0,000	10,000.00		80%	1,400.00
	8 Way TPN MCB DB							,
	Incomer: 63 Amps 4P ELMCB,30mA 1 No.						560	11.00
	Outgoing: 6-16 Amps SP MCB 24 Nos.	2	Sets	8,000 =	16,000.00	/2	700	1,400.00
03.04.00	External LDB						801.	
	8 Way TPN MCB DB							
	Incomer: 63 Amps 4P ELMCB,100mA 1 No.							
	Outgoing: 6-16 Amps SP MCB 24 Nos.	1-	Set	8,000	_ 8,000.00			
03.05.00	AHU Vertical DB							

J. Ro. Before

FOR KEVIN ELECTRICALS PVT. LTD.

ITEM NO.	DESCRIPTION	ILL		SUF	PPLY (Rs.)		ERECTION	(Rs.)
		Oty	Unit	RATE	AMOUNT	Qty	RATE	AMOUNT
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated DG PANEL. The Board shall be incorporated with the following:-					2.9		
	DG INCOMER 1: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.							
	DG INCOMER 2: 315 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.							
	BUS COUPLER: 315 AMPS 4P MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.						y	
	Note: All the incomer and Buscoupler are electrical and mechanical interlock with auto/manual selector switch.							
	OUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays. 4 Nos.							
	BUSBAR : ALUMINIUM							
	RATING: 315 AMPS							
	The Phase Bus bar shall be 50×10 mm, and the Neutral bar shall be 25×06 mm. The Earth Bus bar shall be 2 Runs of 25×6 mm.							
	There shall be TWO set of Metering Compartment incorporated with the following:-							
	i) CTs of ratio 250 & 315 /5A and Class 0.5 for metering and burden 10 VA.						10	
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 & 315 A) with Inbuilt Selector Switch.							
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.	1	/	2,65,000	2,65,000.00	/		-
02.04.00	AC PANEL (OUTDOOR TYPE)							
	CABLE ENTRY: BOTTOM							
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated AC PANEL (outdoor type). The Board shall be incorporated with the following:-							
	INCOMER: 250 AMPS 4P MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays 1 No.							

B. Re. Toyour

FOR KEVIN ELECTRICALS PVT. LTD.,

ITEM NO.	DESCRIPTION	LL		SU	PPLY (Rs.)		ERECTION	(Rs.)
		Qty	Unit	RATE	AMOUNT	Qty	RATE	AMOUNT
	i) CTs of ratio $200/5A$ and Class 0.5 for metering and burden 10 VA.					2.5	2	TAMOUNT
	ii) 1 No. Class 0.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch.							
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.	1	Set	2,16,000	2,16,000.0	0		-
02.02.00	MAIN PANEL - 2							
	CABLE ENTRY: TOP/BOTTOM							
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated MAIN PANEL -2. The Board shall be incorporated with the following:-							
	EB & DG INCOMER: 250 AMPS 4P motorized MCCB with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos.						4	
	OUTGOING: 250 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable overload and short circuit relays1 No.							
	125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos.							
	100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos.							
	BUSBAR : ALUMINIUM							
	RATING: 250 AMPS							
	The Phase Bus bar shall be 40×10 mm. and the Neutral bar shall be 25×6 mm. The Earth Bus bar shall be 2 Runs of 25×3 mm.							
	There shall be TWO set of Metering Compartment incorporated with the following:-							
	i) CTs of ratio 200/5A and Class 0.5 for metering and burden 10 VA.							10.7
	ii) 1 No. Class Q.5, 96 Sq.mm. Digital multifuntional meter (0 - 200 A) with Inbuilt Selector Switch.							
	iii) RYB LED Cluster type Indicating Lamps and Control fuses shall be provided.	1		2,30,000	2,30,000.00	/		_
02.03.00	DG PANEL							
	CABLE ENTRY: TOP/BOTTOM							

J. Na. Buges

FOR KEVIN ELECTRICALS PVT. LTD.,



The Director,

Kalakshetra Foundation

Kevin Electricals Pvt. Ltd.,

Engineers and Government Licenced 'A' Grade Contractors No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ②: 24466938, Telefax: 24912704

E-mail : kevinelectrical@yahoo.co.in Web : www.kevinelectricals.com

TIN No.: 33680862581

TNGST No.: 0862581 / 2003-2004

CST No.: 794079 / Dt. 13-10-2003

Area Code No.

0 4 4

Bill.No: 107 Date: 12.03.2012 RA Bill : 2

Thiruvanmiyur, Chennai - 600 041.

Name of Work:- Electrical Installation work for M/s. Kalashetra Foundation at Chennai.

ITEM NO.	DESCRIPTION			SUP	PLY (Rs.)		ERECTION ((Re)
		Qty	Unit	RATE	AMOUNT	Qty	RATE	AMOUNT
02.00.00	LT PANEL							
02.00.00	LIPANEL							
02.01.00	MAIN PANEL - 1							
	CABLE ENTRY: TOP/BOTTOM							
	CADD DATA TOTAL DOTTON							
	Supplying, Erecting, Testing & commissioning FLOOR MOUNTED CUBICLE TYPE 14 SWG thick CRCA sheet compartmentalised modular type with powder coated MAIN PANEL -1. The Board shall be incorporated with the following:-						×	
	EB & DG INCOMER: 250 AMPS 4P motorized MCCB							
	with 25 KA Withstanding Capacity Adjustable overload and short circuit relays and mechincal interlock between incomers 2 Nos.							
	OUTGOING: 125 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays1 No.							
	100 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays1 No.							
	63 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays3 Nos.							
	32 AMPS TPN MCCB with 25 KA (Ics) Withstanding Capacity Adjustable/Fixed overload and Fixed short circuit relays4 Nos.							
	BUSBAR : ALUMINIUM							
	BODIN. ABOMINION							
	RATING: 250 AMPS							
	The Phase Bus bar shall be 40 x 10 mm. and the Neutral bar shall be 25 x 6 mm. The Earth Bus bar shall be 2 Runs of 25 x 3 mm.							
	There shall be TWO set of Metering Compartment							
	incorporated with the following:-							

T. Ra . Tage

For KEVIN ELECTRICALS PVT. LTD.,



Engineers and Government Licenced 'A' Grade Contractors

No. 7, (O. No. 1-B) Arunachalapuram, IInd Street, Adyar, Chennai - 600 020. ©: 24466938, 24468401. Fax: 24912704 E-mail: kevinelectrical@yahoo.co.in

REF: KE/KF/644/2011-12/724

12.03.2012

To
The Director,
Kalakshetra Foundation,
Thiruvanmiyur,
Chennai - 600 041.

Dear Sir,

SUB: Electrical Installation to be carried out for M/s. Kalashetra at Chennai - Submission of RA.Bill - 2- Reg.

REF: Your Order No:C:\2009-2010\V.Admin\2.Engineering\i.Plan\Koothambalam\Electricalinstallationwork.doc

Dt.28.09.2010.

With reference to the above, we are herewith submitting the RA.Bill - 2 for the above mentioned work

Bill Value (Bill.No:105 Dt.09.03.2012)

Rs.25, 80,971.19

Less:

 15% Advance Adjusted prorata Basis
 Rs.
 3, 80,607.01

 5% Retention
 Rs.
 1, 26,869.00

Received through RTGS dated 04.10.11 Rs. 10, 67,909.00

Amount to be payable

Rs. 15, 75,385.01
Rs. 10, 05,586.18

We request you to kindly arrange to release the Payment of at the earliest & oblige.

Thanking you,

Yours faithfully, For Kevin, Electricals Pvt Ltd,

L.Wilson Susai Raj (Managing Director) S. Pa. Sayard

O VELACHERY SO

(2-78)

Branch Office:

Bangalore: # 3, (Old No. 38), N.R. Layout, Konena Agrahara, HAL Post, Airport Road,

(Behind Rejeswari Theatre), Bangalore - 17. Ph : 51258794 Email : kevinelectricalsblr@yahoo.co.in

Secunderabad: No. 10-1-640, Lane No. 3, Nehru Nagar, West Marredpally (Near Canara Bank) Secunderabad - 26. Ph : 040-27804680 E-mail : kevinelectricalshyd@yahoo.co.in



M/s. Kalakshetra Foundation Thiruvanmiyur, Chennai – 600 041.

OUR REF # 1744-02/MSR/2010

April 07, 2012

CERTIFICATE OF PAYMENT ELECTRICAL WORKS FOR M/s. KALAKSHETRA FOUNDATION, CHENNAI.

CERTIFICATE OF PAYMENT # 01

Name of the work

Electrical works for M/s Kalakshetra Foundation.

Thiruvanmiyur, Chennai.

Name of the contractor

M/s.Kevin Electricals Pvt. Ltd.,

No.07(old No.1-B) Arunachalapuram II street,

Adyar,

Chennai - 600 020.

Work order value

Rs.49,08,773.27

Contractor Bill & Date

·\

•

REF: KE/KF/644/2011-12/724

Contractor Bill Value

Rs.25,64,055.00

DEDUCTIONS AS PER TERMS OF PAYMENT:-

01. 15% Advance

Rs. 3,84,608.25 (To be checked)

02. 5% Retention

Rs. 1,28,202.75

03. 5% Testing and

Commissioning

Rs. 1,28,202.75

04. Payment made

Rs. 10,67,909.00

Rs.17,08,923.00

Balance amount payable

Rs. 8,55,132.30

Round off to

Rs. 8,55,132.00

(Rs. Eight Lac Fifty Five Thousand One Hundred and Thirty Two Only)

Regards,

For Madras Electrical Consultants

M.S.Ramesh

Madras Electrical Consultants

No.6, Park Avenue 1st Cross Street, Velachery, Chennai - 600 042. Phone: 044 - 29728201 / 03

Email: mecramesh@eth.net/msramesh@mec-india.com

279



M/s. Kalakshetra Foundation Thiruvanmiyur, Chennai – 600 041.

OUR REF # 1744-03/MSR/2010

February 23, 2012

REVISED RATE APPROVAL FOR ELECTRICAL WORKS FOR M/s.KALAKSHETRA FOUNDATION, CHENNAI.

Sir,

This has reference to the revised rate submitted by M/s.Kevin Electricals Pvt.Ltd for Electrical works for the above mentioned project, we are duly approved the revised rates in their offer itself.

Kindly acknowledge,

Regards,

For MADRAS ELECTRICAL CONSULTANTS

M.S.RAMESH

Madras Electrical Consultants

No.6, Park Avenue 1st Cross Street, Velachery, Chennai - 600 042. Phone: 044 - 29728201 / 03

Email: mecramesh@eth.net/msramesh@mec-india.com



Total payable

2, 85,517.00

Deductions - 2% Income tax on 2, 85,517.00 = 2% VAT on 2, 85,517.00

5710.00

page 131

5% Retention amount on 2, 85,517=14276 .00

25,696.00(-)

Mobilization Advance paid

= 736316

On Pro rata basis 16.653/49.087 Deduction @ 33.925% x 736316

= 249800

Deduction @ 28.625% x 736316

In this bill deduction

=210770(-)

(Balance to be deducted = Rs 4, 86,516/-

39,030.00(-)

Net Bill value

2, 20,791.00

M/s. M/s. Kevin Electricals (P) Ltd., - Banker details

Beneficiary Bank Name:

City Union Bank

Beneficiary A/c No

OSOD 35317

Beneficiary IFSC Code:

CIUB 0000036

Beneficiary Address:

Mandaveli, No. 67, Mandaveli Street, Chennai - 600 028


Beneficiary Name:

M/s. Kevin Electricals (P) Ltd.,

If approved, the payment of Rs. 2,20,791/- (Rupees Two lakh twenty thousand seven hundred and ninety one only) may be paid to the M/s. Kevin Electricals (P) Ltd., as 2nd and part bill payment as certified by the consulting Architect M/s.CARD and his associate M/s.Madras Electrical consultants.

Submitted for approval of payment:

S.No	Bill amount	Deductions	Gross amount
1	In this bill value	-	2,85,517.00
2	Income tax	5710.00	
3	VAT	5710.00	
4	Retention amount	14,276.00	
5	Mobilization advance	39,030.00	64,726.00(-)
Nett p	ayable to the contractor		2,20,791.00



The summary of billed items and values are,

i.

11.

Netvalue BOQ items as per tender items and value as per annexure (A)= 3,40,792.71(B) = 9,457.91 | 13,000(C) =5,04,881.99 = 6,70,54=8, 55,132.00

And difference in amount (25,26,35) Wow iii. Additional items executed by the contractor Total

BOQ items as per tender items but adopted revised rate

As regards sl.no.1) as per the items (As per BOQ) and executed by the contractor and certified by the consultants in tune of Rs. 3, 40, 792.71 say Rs.3, 40,793, this is the amount representing, the value of materials received at site and labour charges for some items as per the details recorded in the measurement book and the rate adopted as per the tender in this bill.

As regards sl.no.ii and iii items and rates may be paid after the approval of the works committee for the value of Rs 5, 14,3407 6,83,543/. (B13,000+6,70,543)-

While, working out the service tax clarification need to be obtained from the consultant has to whether service tax applicable for work order value (irrespective of materials + labour component) or labour component alone. Pending clarification from the consultant we may release 90% of material cost in this bill.

On approval a separate letter to consultant will be put please.

i) Towards supply of materials

Total value of supply of materials as certified (As per the statement) = Rs. 18, 50,350.00 Payable to the supplier @ 90% on 18, 50, 350.00 as per page 105/c = 16, 65,315.00Deduct 1st and part bill value (page 199) 14, 45,760.00(-) -----In this bill value 2,19,555.00

ii) Towards labour charges

Total value of labour charges as certified (As per the statement) = Rs. 77,978.00Payable to the supplier @ 90% on 77,978.00 as per page 105/c 70,180.00 Deduct 1st and part bill value (page 199) 2,840.00(-) In this bill value 67,340.00 Total i + ii (2, 19,555+67,340)2, 86,895.00 \(\mathbb{T}\) Discount 3% (page 9) @3% on 2, 86,895.00 8,607.00(-) 2, 78,288.00 Add service tax 10.3% on 70,180/-7,229.00 (+) Total payable

2, 85,517.00

kalakshetra

C:\ 2009-2010\V.Admin\2. Engineering\i.Plan\Koothambalam\ Electricl	December 6, 2012
installation work.doc	

Sub: Koothambalam – Electrical Installation work in Kalakshetra Foundation – 2nd and part Bill – Payment – Approval of – Reg.

Ref: i) Works Committee approval note dated 22.6.2010

P-25, 26

ii). Work order dated September 28, 2010

P-107,108

iii) Certificate of Payment as 1st and part bill, recommended by M/s.CARD

And his associates M/s. madras electrical consultant Dated 26.9.2010 P – 188-196

iv) Certificate of Payment as 2nd and part bill, recommended by M/s.CARD And his associates M/s. madras electrical consultant Dated 26.9.2010

Chronology

i) Based on the approval by the Works Committee, the work was awarded to M/s.Kevin Electricals pvt ltd at a total cost of Rs.49,08,773.27/- The work order was issued Consolidative for materials as well as labour charges at a total cost of Rs. Rs.49,08,773.27/-

However, the consultant has differentiated the materials and labour cost in his recommendation in the statement dated September 18th, 2010 and details is,

Supply of materials cost

= 39, 39,639.75

Labour charges

= 8,87,700.35

Service tax 10.3%

= 91,433.00

J1,155.0

= 9,79,133.35

Total value of work awarded

49, 08, 773.10

ii) An mobilization advance for Rs.7, 36,316/- was paid to the contractor against the Bank guarantee as per the terms

The consulting Architect M/s.CARD/Shri.Ravi Niilakantan and his associate M/s.Madras Electrical Consultants have certified and forwarded 2nd and part bill payment to M/s.Kevin Electricals for Rs.8,55,132/- (Rupees eight lakh fifty five thousand one hundred and thirty two only)

The details of items supplied and labour charges have been recorded in Measurement book by Clerks of works appointed by the Consulting Architect. The bill of quantities was checked and certified by the Consulting Architect M/s.CARD\Shri.Ravi Niilakantan and his associate M/s.Madras Electrical Consultants.

The bill value certified by the M/s.CARD and his electrical consultant to M/s.Kevin Electricals as 2^{nd} and part bill is = 8,55,132.00

(D\$5)

....2

04.04.00 S		04.02.00 \$	04.01.00	04.00.00				03,06.00		03.05.00		03.04.00		03.03.00	03.02.00		03.01.00	03.00.00	02.04.00	02.03.00	02.02.00	02.01.00	02.00.00	01.01.00	01.01.00	00,00			
Supplying, erecting, connecting & commissioning 63 Amps 4P MCB in weather proof enclosure with necessary interconnections, brackets, screws, bolts, nuts, etc. for Ac control	Supplying, erecting, connecting & commissioning 10 Amps SP MCB in weather proof enclosure with necessary interconnections, brackets, screws, bolts, nuts_erc_for_external lighting	Supplying, erecting, connecting 8, commissioning 63Amps 4P MCB on an angle Iron frame with necessary interconnections, cable box, brackets, screws, bolts, nuts, etc.	Supplying, erecting, connecting & commissioning 32Amps.4P MCB with DOL Starter for a maximum of 5HP 3 PHASE MOTOR with interconnections and sultably mounted on the wall.	FSU/ MCCB / STARTERS	Outgoing: 10-32 Amps SP MCB 18 Nos	Incomer: 63 Amps TP2N MCB 1 No.	8 Way TPN VERTICAL MCB DB	UPS Main Vertical DB	8 Way TPN VERTICAL MCB DB	AHU Vertical DB	8 Way TPN MCB DB	External LDB	8 Way TPN MCB DB	PDB	6 Way TPN MCB DB	8 Way TPN MCB DB	TOB	MCB DBs	AC PANEL (OUTDOOR TYPE)	DG PANEL	MAIN PANEL - 2	MAIN PANEL - 1	LT PANEL	01.01.00 METER BOARD	CT METER BOARD	METER BOARD /ACCESSORIES		DESCRIPTION	DATIVE STATEMENT FOR ELECTRICAL INSTALLATION TO BE CARRIED OUT FOR PROPOSED FOR M/S.
5 Sets	7 Sets	5 Sets	10 Sets		2 Sets			N. P.	1 Set		1 Set		2 Sets		RO Sets	2 Sets			1	1	1	1 Set		RO Sets	2 Sets	1 20		QTY.	AL INSTAL
2,		Į.		-					16,5		8,0								138,0	. 265,0	230,0	216,0			-		RATE RS.	Carlotte Comment	LATION TO
750.00	650.00	450.00	4,000.00		8,500.00	+			16,500.00		8,000.00	-	8,000.00		7,400.00	8,000.00			138,000.00	265,000.00	230,000.00	216,000.00	$\frac{\parallel}{\parallel}$	22,500.00	29,500.00			SUPPLY	BE CARRIE
13,750.00	4,550.00	7,250.00	40,000.00		17,000.00				16,500.00		8,000.00		16,000.00			16,000.00			138,000.00	265,000.00	230,000.00	216,000.00	2		59,000.00	4800	AMOUNT RS.	MIS.KEVIN ELECTRICALS	OUT FOR P
150.00	100.00	150.00	250.00		700.00				900.00		700.00		700.00		700.00	700.00			4,000.00	5,000.00	5,000.00	5,000.00		1,000.00	1,000.00		RATE RS.	ECTRICALS	ROPOSED F
750.00	700.00	750.00	2,500.00		1,400.00				900.00		700.00		1,400.00			1,400.00			4,000.00	5,000.00	5,000.00	5,000.00			2,000.00		AMOUNT RS.	ERECTION	OR M/S.
2,975.00	1,700.00	1,750.00	3,100.00		00.001,00.00				00 19,500.00		00.008,6 00		9,800.00		8,350.00	00.008,6 00			00 135,500.00	00.000,00	00 238,000.00	00 257,000.00		19,000.00	00 28,500.00		RATE RS.		
0 14,875.00	0 11,900.00	8	31,000.00										0.		00				135,500.00	338,000.00	238,000.00	257,000.00		00			AMOUNT RS.	M/s.K.K.S	
		,750.00 10	1		20,200.00 1,65				19,500.00 2,00		9,800.00 1,50	-	19,600.00 1,50		1,50	19,600.00 1,50					T			2,00	57,000.00 2,00		T RATE	M/s.K.K.SINGH ELECTRICALS	
100.00	75.00	100.00		14	1,650.00 .~3,			-	2,000.00 2		1,500.00 1		1,500.00 3		1,500.00	1,500.00 3			8,000.00	8,000.00	8,000.00	8,000.00		2,000.00	2,000.00 4		1.0	2	
500:00	525.00	500.00	,500.00		3,300.00				2,000.00		1,500.00		3,000.00			3,000.00			8,000.00	8,000.00	8,000.00	8,000.00			4,000.00		RS.	-	
2,100.00	550.00	2,100.00	4,500.00		15,500.00				19,000.00		12,500.00		12,500.00		12,000.00	12,500.00			119,000.00	298,000.00	215,000.00	227,000.00		19,000.00	24,000.00		RATE RS.		
10,500.00	3,850.00	10,500.00	45,000.00		31,000.00				19,000.00		12,500.00		25,000.00			25,000.00			119,000.00	298,000.00	215,000.00	227,000.00			48,000.00		AMOUNT RS.	M/s.POLAR ELECTRICALS	
200.00	0 100.00	200.00	0 300.00		0 2,000.00				0 2,000.00		0 1,500.00		0 1,500.00		1,500.00	0 1,500.00			5,000.00	0,000.00	0 5,000.00	5,000.00		2,000.00	2,500.00		RATE RS.	LECTRICALS	
1,000.00	700.00	1,000.00	3,000.00		4,000.00				2,000.00	710	1,500.00		3,000.00			3,000.00			5,000.00	6,000.00	5,000.00	5,000.00			5,000.00		TE AMOUNT	CTION	
3,000.00	0 300.00	0 2,200.00	0 3,000.00		0 13,500.00				0 25,000.00		0 13,750.00		0 13,750.00		13,500.00	0 13,750.00		A Comment	183,000.00	390,000.00	295,000.00	285,000.00		32,000.00	34,000.00		RATE RS.	The second second	
15,000.00	2,100.00	11,000.00	30,000.00		27,000.00				25,000.00		13,750.00		27,500.00			27,500.00			183,000.00	390,000.00	295,000.00	285,000.00			68,000.00			SUPPLY M/s.S.S.	
300.00	100.00	300.00	350.00		00 1,500.00				00 1,600.00		00 1,500.00		00 1,500.00		1,500.00	00 1,500.00			00 5,000.00	00 6,000.00	00 6,000.00	00 6,000.00		2,500.00	00 2,500.00		RATE RS.	ELECTRICALS	
1,500.00	700.00	1,500.00	3,500.00		3,000.00				1,600.00		1,500.00		3,000.00			3,000.00			5,000.00	6,000.00	6,000.00	6,000.00			5,000.00		AMOUNT RATE AMOUNT RS. RS. RS.	FOTTON	

B. Ober To gares man)

PAGE 1 OF 10

MADRA
S ELECTRIC
AL CONSU
ILTANTS

						33.00		100)2.00							8	0.00	7.00	6.00	5.00	1				
1		3 1/2 × 150 Sq.mm. Al.	3 1/2 × 185 Sq.mm. Al.	3 1/2 × 240 Sq.mm. Al.	Supplying,terminating,connecting and commissioning the above Underground cables commissioning the above Underground cables with Double compression type glands. The cost of earthing gland with copper strips/ wires shall also be included. The cables shall be terminated with Al / copper lugs after crimping.	TERMINATION	3C x 2.5 Sq.mm. Cu.	4C x 10 Sq.min. Ai.	TO Od	3	×	3 1/2 × 35 Sq.mm. Al.	3 1/2 × 50 Sq.mm. Al.	3 1/2 × 150 Sq.mm. Al.	3 1/2 × 185 Sq.mm. Al.	NOTE: Supply of Anchor Fastners and necessary 1.5 mm. thick GI Flat, clamps shall be included in the cost.	CLAMPED ALONG WALL/CEILING	4C x 16 Sq.mm, Al.	4C x 2.5 Sq.mm. Cu.	3C x 2.5 Sq.mm. Cu.	3 1/2 × 130 30:mm: /u.		3 1/2 × 240 Sq.mm. Al.	BURIED UNDERGROUND / LAID IN TRENCH (Inclusive of digging, back filling, bricks sand etc.)	CABLES/TERMINATIONS	Supplying, erecting, connecting & commissioning PVC weather proof type enclosure and with 32 AMPS TPN metal clad socker with 4P MCB on an angle Iron frame with necessary interconnections, cable box, hardens screws. boths nuts en	Supplying, erecting, connecting & commissioning PVC weather proof type enclosure and with 100 AMPS 4P MCCB with 125 KA rating on an angle fron frame with necessary interconnections, cable box, brackets screwe. balts nuts air	Supplying, erecting, connecting & commissioning 32 Amps 4P MCB on an angle commissioning 32 Amps 4P interconnections, Iron frame with necessary interconnections, cable box, brackets, screws, bolts, nuts, etc.		DESCRIPTION	NOTIVE STATEMENT FOR ELECTRICAL INSTALLATION TO BE CARRIED OUT FOR PROPOSED FOR M/S.		
	2 Nos	16 Nos	2 Nos	10 Nos			TOO MINO.	TOOMTDC	100 MTRS.	400 MTRS.	200 MTRS.	300 MTRS.	100 MTRS.	100 MTRS.	175 MTRS.			100 MTRS.	250 MTRS.	400 1918.5.	Ann MTDS	400 MTRS.	100 MTRS.			10 Set	1 Set	4 Sets		оту.	INSTALLATIO		
	600.00	800.00	850.00	1,000.00			90.00	90 00	90.00	115.00	130.00	165.00	210.00	415.00	525.00			115.00	110.00	20:00	90.00	415.00	650.00			3,750.00	8,500.00	1,400.00	RATE RS.	US	ON TO BE CAR		
	1,200.00	12,800.00	1,700.00	10,000.00	7		2,000.00	9 000 00		46,000.00	26,000.00	49,500.00	21,000.00	41,500.00				11,500.00	27,500.00	50,000.00	36,000,00	166,000.00	65,000.00			37,500.00	8,500.00	5,600.00	AMOUNT RS.	M/s.KEVIN ELECTRICALS	RIED OUT FOR PR		
	125.00	150.00	200.00	200.00				15.00	25.00	30.00	30.00	30.00	35.00	40.00	+0.00			145.00	120.00		120.00	170.00	200.00			300.00	400.00	150.00	RATE RS.	뙈	OPOSED FOI	- 1	
	250.00	2,400.00	400.00	2,000.00				1.500.00	2,500.00	12,000.00	6,000.00	9,000.00	3,500.00	4,000.00	,,000.00	2000		14,500.00	30,000.00		48,000.00	68,000.00	20,000.00			3,000.00	400.00	600.00	AMOUNT RS.	ECTION	RM/S.		
	580.00	715.00	875.00	1,185.00				114.00	110.00	118.00	147.00	174.00	220.00	00.626	50000	665 00		143.00	163.00		138.00	560.00	850.00			6,500.00	11,000.00	1,275.00	RATE RS.	SUPPLY			
	1,160.00	11,440.00	1,750.00	11,850.00				11,400.00	11,000.00	47,200.00	29,400.00	52,200.00	22,000.00	32,300.00	53 500 00	116 375 00		14,300.00	40,750.00	20.00	55,200.00	224,000.00	85,000.00			65,000.00	11,000.00	5,100.00	AMOUNT RS.	PLY ERE			
	100.00	125.00	150.00	200.00				15.00	15.00	15.00	25.00	25.00	30.00	2 0	35 00	35.00		20.00	20.00	20,00	20.00	35.00	40.00			100.00	250.00	100.00	RATE RS.	ECTRICALS			
	200.00	2,000.00	300,00	2,000.00				1,500.00	1,500.00	6,000.00	5,000.00	7,500.00	3,000.00	2 2000	3 500 00	6,125.00		2,000.00	2,000.00	5 000 00	8,000.00	14,000.00	4,000.00			1,000.00	250.00	400.00	RS.	NOIT			
	350.00	650.00	750.00	250.00				98.00	95.00	110.00	130.00	160.00	00.022	00 000	480.00	620.00		110.00	110 00	120.00	98.00	480.00	760.00			2,800.00	9,500.00	1,800.00	RATE RS.				
	700.00	10,400.00	1,500.00	4 500 00				9,800.00	9,500.00	44,000.00	26,000.00	48,000.00	22,000.00	22 000 00	48,000.00	108,500.00		11,000.00	11 000 00	30.000.00	39,200.00	192,000.00	76,000.00			28,000.00	9,500.00	7,200.00	RS. RS. RS.	PLY PLY			
	150.00	200.00	300.00	300.00	350			30.00	30.00	30.00	30.00	50.00	25 00	40.00	60.00	90.00			40.00	40.00	40.00	70.00	110.00			250.00	450.00	200.00	RATE RS.	TRICALS			
	300.00	3,200.00	000.00	600.00	3.500.00			3,000.00	3,000.00	12,000.00	6,000.00	10,500.00	10 500 00	4.000.00	6,000.00	15,750.00			4.000.00	10,000.00	16,000.00	28,000.00	11,000.00			2,500.00	450.00	800.00	RS.	ION			
	200.00	300.00		350.00	450.00			85.00	100.00	100.00	10.00L	150.00	175 00	225.00	365.00	410.00			100.00	105.00	85.00	365.00	/20.00			4,100.00	8,500.00	2,000.00	RS.	SUPPLY	1 1		
	400.00	4,800.00		700.00	4,500.00			8,500.00	10,000.00	40,000.00	30,000.00	20,000,00	52 500 00	22,500.00	36,500.00	71,750.00			10,000.00	26,250.00	34,000.00	146,000.00	72,000.00	77		41,000.00	8,500.00	8,000.00	RS.	PLY	M/s S S ELECTRICALS		
	150.00	200.00	200	250.00	300.00			18.00	27.00	27.00	2000	35 00	35.00	35.00	45.00	45.00			75.00	65.00	65.00	155.00	100.00	180 00		400.00	500.00	300.00	RS.	ERECI	TRICALS		
P	300.00	3,200.00	2 200 000	500.00	3,000.00			1,800.00	2,700.00	10,800.00	,,000.00	7,000,00	10,500.00	3,500.00	4,500.00	7,875.00			7,500.00	16,250.00	26,000.00	62,000.00	53,000,00	18.000.00		4,000.00	500.00	1,200.00	RS.	TON			

Dibor Borger Sond Kommond)

M	.00 Sup 2 R PVC con in F	.00 Sup 20,4 20,4 mo	00 Sup Soc flus	00 Sup 2 R PVC con alre ceil	00 RA	00 Sup 4 Ru PVC con hea ceill	JO Sup 4 Ru PVC con hea ceill	5 Ru PVC con hea celli	JO Sup 4 Ru PVC con hea ceili)0 MA:	40	3C	4C	4C	3 1/2	3 1/2			
MADRAS ELECTRICAL CONSULTANTS	Supplying, laying, connecting & commissioning 2 Runs of 6 Sq. mm. with 1 Runs of 2.5 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in in PVC Conduits open above false ceiling or in PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lance.	Supplying, fixing, connecting & commissioning 20Amps Metal clad socket combined with 20Amps DP MCB as control in Manufacturer's mounting box fixed flush with the wall and all	Supplying and fixing 6/16Amps Switched Socket in Manufacturer's mounting box fixed flush with the wall.	Supplying, laying, connecting & commissioning 2 Runs of 4 Sq.mm. with 1 Run of 2.5 Sqmm. PVC Insulated standed single core copper conductor FRLS wire for continuous earthing in already laid PVC Conduits open above false ceiling or concealed in wall / ceiling with processors barner crawme are from 101 to Bouron.	RAW /UPS POWER WIRING	Supplying, laying, connecting & commissioning 4 Runs of 6 Sq.mm, with 2 Runs of 2.5 Sqmm, PVC Insulated standed single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or concealed in wall ceiling with necessary lamps, screws etc.	Supplying, laying, connecting & commissioning 4 Runs of 4 Sqmm. 4R Runs of 4 Sqmm. With 2 Runs of 4 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc.	Supplying, Isying, connecting & commissioning 5 Runs of 25 Sq.mm. with 2 Runs of 16 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or connecised in wall / ceiling with necessary lamps, screws etc.for ups DB.	Supplying, laying, connecting & commissioning 4 Runs of 25 Sq.mm. with 2 Runs of 16 Sqmm. PVC Insulated stranded single core copper conductor FRLS wire for continuous earthing in heavy duty PVC Conduits open above false ceiling or concealed in wall / ceiling with	MAINS WIRING	x 2.5 Sq.mm. Cu.	x 2.5 Sq.mm. Cu.	x 10 Sq.mm. Al.	x 16 Sq.mm. Al.	/2 × 25 Sq.mm. Al.	/2 × 35 Sq.mm. Al.		DESCRIPTION	GATIVE STATEMENT FOR ELECTRICAL INSTALLATION TO BE CARRIED OUT FOR PROPOSED FOR M/S.
	450 Mts.	10 Nos.	25 Nos.	1500 Mts.		30 Mtrs.	30 Mtrs.	125 Mtrs.	30 Mtrs.		10 Nos	16 Nos	8 Nos	10 Nos	8 Nos	10 Nos		QTY.	AL INSTALLA
	130.00	750.00	340.00	75.00		360.00	425.00	110.00	950.00		175.00	150.00	450.00	500.00	500.00	500.00	RATE RS.		TION TO BE CA
	58,500.00	0 7,500.00	0 8,500.00	0 112,500.00		0 10,800.00	0 12,750.00	0 13,750.00	28,500.00		1,750.00	2,400.00	3,600.00	5,000.00	4,000.00	5,000.00	AMOUNT RS.	M/s.KEVIN E	RRIED OUT FOR
	0 25.00	0 100.00	0 50.00	0 10.00		0 60.00	0 75.00	150.00	0 125.00		60.00	50.00	100.00	100.00	100.00	\top	RATE RS.	M/s.KEVIN ELECTRICALS	PROPOSED FO
	11,250.00	1,000.00	1,250.00	15,000.00		1,800.00	2,250.00	18,750.00	3,750.00		600.00	800.00	800.00	1,000.00	800.00	1,250.00	AMOUNT RS.		OR M/S.
AL CONSC	128.00	1,325.00	400.00	78.00		335.00	380.00	1,325.00	1,125.00		150.00	150.00	240.00	260.00	375.00	410.00	RATE RS.		
	57,600.00	13,250.00	10,000.00	117,000.00		10,050.00	11,400.00	165,625.00	33,750.00		1,500.00	2,400.00	1,920.00	2,600.00	3,000.00	4,100.00	AMOUNT RS.	M/s.K.K.SINGH ELECTRICALS	
	20.00	100.00	50.00	4.00		25.00	25.00	40.00	40.00		50.00	50.00	75.00	75.00	100.00	100.00	RATE RS.	ECTRICALS	
	9,000.00	1,000.00	1,250.00	6,000.00		750.00	750.00	5,000.00	1,200.00		500.00	800.00	600.00	750.00	800.00	1,000.00	AMOUNT RS.	NOT	,
	120.00	1,200.00	380.00	98.00		210.00	380.00	1,270.00	1,050.00		150.00	150.00	150.00	150.00	200.00	250.00	RATE RS.	SU	
	54,000.00	12,000.00	9,500.00	147,000.00		6,300.00	11,400.00	158,750.00	31,500.00		1,500.00	2,400.00	1,200.00	1,500.00	1,600.00	2,500.00	RATE AMOUNT RATE AMOUNT RS. RS. RS. RS.	M/s.POLAR ELE	
	20.00	200.00	80.00	15.00		30.00	40.00	70.00	70.00		50.00	50.00	50.00	100.00	100.00	100.00	RATE RS.	CTRICALS	
	9,000.00	2,000.00	2,000.00	22,500.00		900.000	1,200.00	8,750.00	2,100.00		500.00	800.00	400.00	1,000.00	800.00	1,000.00	AMOUNT RS.	NON	
)	125.00	1,100.00	340.00	75.00		215.00	440.00	1,170.00	980.00		100.00	90.00	125.00	125.00	150.00	175.00	RATE RS.	SUI	
O Company of the Company	56,250.00	11,000.00	8,500.00	112,500.00		6,450.00	13,200.00	146,250.00	29,400.00		1,000.00	1,440.00	1,000.00	1,250.00	1,200.00	1,750.00	AMOUNT RS.	M/s.S.S.ELECTRICALS	
de de	30.00	300.00	100.00	22.00		30.00	32.00	50.00	50.00		75.00	70.00	100.00	100.00	125.00	125.00	RATE RS.	TRICALS	
PAGE 3	13,500.00	3,000.00	2,500.00	33,000.00		900.000	960.00	6,250.00	1,500.00		750.00	1,120.00	800.00	1,000.00	1,000.00	1,250.00	RS.	LS	



	00.00	.14.00	.13.00	.12.00	.11.00	.10.00	.09.0	.08.0	.07.0	7.06.0	7.05.00		State L	1000
	00.00 LIGHT POINT WIRING	Supplying and laying of 32 mm. Dia Heavy duty PVC Conduits concealed / open in wall / ceiling etc. with necessary clamps, screws etc. with 1 Run of 16 SWG G.I. Fish wire.	Supplying and laying of 25mm. Dia Heavy duty PVC Condults concealed / open in wall / ceiling etc. with necessary damps, screws etc. with 1 Run of 16 SWG G.1. Fish wire.	Supplying fixing connecting and commissioning of 10 - 16 AMPS SPM MENNEKES make 3 pin and type plug and socket in Manufacturer's mounting box fixed flush with the wall. For music equipment (Indian model)	Supplying, fixing, connecting and commissioning of 16 AMPS SPN MENNEKES make schuko model of 2 pin and type plug and socket in Manufacturer's mounting box fixed flush with the wall. For music equipment (german make)	Supplying, laying, connecting & commissioning 3 core 6 Sq.nm.PVC Insulated flexible copper cable in already laid PVC Conduits (or) GI tray open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	.09.00 Supplying, laying, connecting & commissioning 3 core 4 Sq.mm.PVC insulated flexibile copper cable in already laid PVC Conduits (or) Git ray open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	v.08.00 Supplying, laying, connecting & commissioning 3 core z.5 Sq.mm.PVC Insulated flexiable copper cable in already jaid PVC Conduits (or) open in ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to stage focus light point.	3 Runs of Z.5 Sq., mm. PVC. Insulated stranded single core copper conductor FRLS wire for continuous earthing in a ricayl Jaid PVC Conduits open above false ceiling or concealed in wall / ceiling with necessary lamps, screws etc from DB to Power Points.	7.06.00 Supplying and fixing 6 Amps Switched Socket in Manufacturer's mounting box fixed flush with the wall.	O Supplying, fixing, connecting & commissioning 32 Amps SPN Metal clad socket combined with 32 Amps DP as control in Manufacturer's mounting box fixed flush with the wall.		ATTIVE STATEMENT FOR ELECTRICAL INSTALLATION TO BE CARRIED OUT FOR PROPOSED FOR M/S. AT CHENNAI DESCRIPTION QTV. SUPPLY SUPPLY ERECTION	
-		1200 Mtrs	600 Mtrs	200 Nos.	40 Nos.	300 Mts.	2800 Mts.	1200 Mts.	800 Mts.	30 Nos.	5 Nos.		AL INSTA	\parallel
-		0	6	i i	9'	ļ*	,,	5.	s.	is.	ÿ.		LLATION	\parallel
		38.00	30.00	900.00	1,050.00	135.00	85.00	68.00	55,00	275.00	1,100.00	RATE RS.	TO BE CAR	
		45,600.00	18,000.00	180,000.00	42,000.00	40,500.00	238,000.00	81,600.00	44,000.00	8,250.00	5,500.00	AMOUNT RS.	CARRIED OUT FOR PROPOSED MIS.KEVIN ELECTRICALS SUPPLY	
		12.00	10.00	100.00	125.00	15.00	12.00	10.00	10.00	40.00	150.00	RATE RS.	ROPOSED F	
		14,400.00	6,000.00	20,000.00	5,000.00	4,500.00	33,600.00	12,000.00	8,000.00	1,200.00	750,00	AMOUNT RS.	FOR M/S.	
		36.00	28.00	1,100.00	710.00	145.00	85.00	70.00	56.00	280.00	1,375.00	RATE RS.		
		43,200.00	16,800.00	220,000.00	28,400.00	43,500.00	238,000.00	84,000.00	44,800.00		0 6,875.00	AMOUNT RS.	M/s.K.K.SINGH ELECTRICALS	
		12.00	10.00	100.00	100.00	4.00	4.00	4.00	4.00	50.00	100.00	RATE RS.	ELECTRICALS	
		14,400.00	6,000.00	20,000.00	4,000.00	1,200.00	11,200.00	4,800.00	3,200.00		500.00	TE AMOUNT	TO CONTRACT OF THE CONTRACT OF	
		42.00	35.00	4,500.00	6,500.00	120.00	95.00	75.00	58.00		1,300.00	RATE RS.	2	
		50,400.00	21,000.00	900,000.00	260,000.00	36,000.00	266,000.00	90,000,00	46,400.00	8,700.00	6,500.00	AMOUNT RATE AMOUNT RS. RS. RS.	M/s.POLAR EL	
		6.00	5.00	100.00	100.00	20.00	15.00	10.00	10.00	60.00	200.00	RATE RS.	ECTRICALS	
		7,200.00	3,000.00	20,000.00	4,000.00	6,000.00	42,000.00	12,000.00			1,000.00	AMOUNT RS.		
		45.00	35.00	1,340.00	900.00	140.00	90.00	60.00	82.00		1,250.00	RATE RS.		
		54,000.00	21,000.00	268,000.00	36,000.00	42,000.00	252,000.00	72,000.00	65,600.00	7,500.00	6,250.00	AMOUNT RS.	M/s.S.S.ELECTRICALS	
		10.00	8.00	300.00	400.00	22.00	20.00	12.00	15.00	100.00	300.00	RATE RS.	CTRICALS	
		12,000.00	4,800.00	60,000.00	16,000.00	6,600.00	56,000.00	14,400.00	12,000.00	3,000.00	1,500.00	E AMOUNT S. RS.		

Part +

PAGE 4 OF 10

Part Interest Part Int	22,400.00 1,200.00	2,800.00	20,000.00	2,500.00	36,000.00	4,500.00	12,000.00		42,000.00	5,250.00	16,000.00	2,000.00	20,000.00	2,500.00	o Sets	
Control Cont	a 12		_		2				00 000	7 7 7 7 7 7			20 000 00	3 500 00	2000	Sair and charcoal arc
Content Cont		. ,	,	*						•	,					
CONTINION CONTINION CONTINUE CONTINU																.00 EARTHING
CHESCALETION CT. COUNTY CAPELLY COUNTY OF PROPERTY COUNTY CAPELLY COUNTY CAPELL							Z ₁				4					The cost of Supplying, Laying and Pulling for Circuit Mains with 3 Runs of 1.5 Sq.mm. PVC Insulated Multistranded Copper condutor wires in PVC Conduits concealed in wall / ceiling or open above faise ceiling (1 he average leight shall be 7Mts from switch board to light point and 10 mtr from Da to switch board) shall be included in the Point rate for Light, Fan, Exhaust Fan, 6 Amps Sockets Etc.
																Note:-
PRECEIPTION QTY SUPPLY MAKENING LECTRICALS Make A CHICALS Make A Make A CHICALS	1,500.00	750.00	180.00	90.00	900.00		300.00	П	1,100.00	550.00	250.00	125.00	1,300.00	650.00	2 Pts.	Mounted Fan points.
PROCESSIAL PROPERTY PROPERT		800.00	900.00	90.00	4,500.00		1,500.00		5,500.00	550.00	1,000.00	100.00	6,000.00	600.00	10 Pts.	5.00 Same as the Item No. 08.01.00 but for Exhaust Fan points.
Mark Structure For Electricical Installation for Be Carberton Otto Prop.		1,600.00	700.00	140.00	4,950.00		750.00		3,000.00	600.00	1,000.00	200.00	6,750.00	1,350.00	5 Pts.	Same as Item No.08.01.00 but for TWO WAY Fan POINTS with 2 Nos. 6 Amps. Switches.
Marie Statishest for Rectalization to be Carbetted out for Rate Marie Statishest Ma		900.00	1,400.00	140.00	7,800.00		1,500.00		6,000.00	600.00	1,500.00	150.00	8,500.00	850.00	10 Pts.	.00 Same as Item No. 08.01.01 but for TWO WAY LIGHT POINTS with 2Nos. 6 Amps Switches.
Marketinal Controlled Con		900.00	1,800.00	90.00	15,600.00		4,000.00		17,000.00	850.00	3,000.00	150.00	24,000.00	1,200.00	20 Pts.	
Miss Selectric Miss Of Miss M		300.00	1,200.00	120.00	5,500.00				6,000.00	600.00	2,000.00	200.00	11,500.00	1,150.00	10 Pts.	2.00 Same as the Item No. 08.01.00 but for 6 Amps. Independant switched socket combined including supplying and fixing 6Amps Switched Snoket.
TOTIVE STATEMENT FOR ELECTRICAL INSTALLATION TO BE CARRIED OUT FOR PROPOSED FOR M/S. Mask Charles Mask Cha	15,750.00	225.00	4,200.00	60.00	16,800.00				21,000.00	300.00	4,200.00	60.00	29,400.00	420.00	70 Pts.	L.02 Same as above item with additional light point.
TOTIVE STATEMENT FOR ELECTRICAL INSTALLATION TO BE CARRIED OUT FOR PROPOSED FOR M/S. Mascelle Control Control	45,000.00	450.00	9,000.00	90.00	39,000.00				55,000.00		9,000.00	90.00	55,000.00	550.00	100 Pts.	
M/s.KK.SINGH ELECTRICALS																Commissioning the light points with 3 Runs of L5 Sq. mm. PVC insulated multistranded Copper Conductor wires (One each for Phase, Neutral and Earth) in Heavy duty PVC Conduits concealed in wall / celling or open above false ceiling with necessary clamps screws etc. including supplying and fixing 6 Amps. Switch in manufacturers mounting box fixed flush with has account.
Ms.K.K.SINGH ELECTRICALS Ms.FOLAR ELECTRICALS SIDDIV SIDDIV	RS.		AMOUNT RS.	RATE RS.	AMOUNT RS.		AMOUNT RS.	RATE RS.	AMOUNT RS.		AMOUNT RS.	RATE RS.	AMOUNT RS.			
		SUPPL	NOT	CTRICALS	M/s.POLAR ELE	SIIIS	NOITE	ELECTRICALS	M/s.K.K.SINGH	S	NOIT	ECTRICALS	M/s.KEVIN EL	dns	QTY.	DESCRIPTION
											RM/S.	ROPOSED FO	TED OUT FOR P	ION TO BE CAR	INSTALLAT	RATIVE STATEMENT FOR ELECTRICAL

D. B. D. B. B.

PAGE 5 OF 10

- 1	0.00	0.00	9.00	B.00	7.00	6.00	5.00	4.00	3.00			
	CABLE TRAY	Supplying laying and connecting 25 Sq.nmn.PVC Insulated copper conductor wires in PVC Condults laid open fashion with necessary clamps, screws, interlinks etc.	Supplying, laying and connecting 500mm long 12 x 3 mm. Copper flat with SMC Insulator in open fashion with necessary clamps, screws,etc. as earth link for Data Earthing	Supplying, laying & connecting 500mm. long 25x6mm.Copper flat with SMC Insulator in open fashion with necessary clamps, screws,etc. as earth link for UPS.	Supplying, laying, connecting and commissioning 8 SW6 bare enamelled copper wire enclosed in PVC Conduits with necessary clamps, screws etc. for earthing AC Equipments 1 motors etc.	Supplying, laying & connecting 500mm. long 25 x 6 mm. GI flat with SMC Insulator in open fashion with necessary clamps, screws, etc. as earth. link	Supplying, laying and connecting 25 x 6mm. CU Flat laid in open fashion with necessary clamps, screws, interlinks etc. for earthing the Panels J. Stahilizer J. DG. netural	Supplying, laying and connecting 25 x 6mm. G.I Flat laid in open fashion with necessary clamps, screws, interlinks etc. for earthing the Panels / Stabilizer / DG body earthing etc.	Supplying, laying and connecting 50x6mm. G.I.Tape wound in half lapped fashon with bituminious tape painted at a depth of 60hmm. In ground to interconnect the earth electrodes. The tape shall not come into contact with any unnecessary metal parts (or) cables along with its route.	Sapplying, installing and connecting a Copper Sapplying, installing and connecting a Copper plate of size 600mms. In an earth pit of 700 x depth of 3000 mm. In an earth pit of 700 x 200 x 3500 mm. Iflied with salt and charcoal mixed with sand in alternate layers 150 mm. Reach upto a height of 3000 mm, from bottom. Two copper flats of 25 x 6mm. shall be braced to this copper plate throughout the overlaping length with the copper plate and brought to the surface of the earthpit. This copper flat shall have provision for connecting wires of flats as the case may be. A suitable size of 40 mm, did GI Pipe shall have provision for connecting wires of flats as GI Pipe shall have provision for the earth pit. This GI Pipe shall have provision for sutrective shall be constructed to a depth of 450mm, and a heavy duty. CI Cover shall be 450mm, and a heavy duty. CI Cover shall be used to cover the pit. The core shall be used to cover the pit. The core shall be asked thing shall also be included. Sand, salt and charcoal are in the Contractor's scope.		THE STATE OF THE S
		100 Mtrs	10 Sets	3 Sets	150 Mtrs	4 Sets	100 Mtrs	300 Mtrs	100 Mtrs	6 Sets		QTY.
		190.00	250.00	650.00	75.00	350.00	810.00	100.00	200.00	12,000.00	RATE RS.	
		19,000.00	2,500.00	00 1,950.00	11,250.00	1,400.00	81,000.00	30,000.00	20,000.00	72,000.00	AMOUNT RS.	M/s.KEVIN EI
		0 25.00	0 100.00	0 150.00	0 15.00	0 100.00	0 30.00	0 20.00	0 30.00	2,500.00	RATE RS.	ELECTRICALS
		2,500.00	1,000.00	450.00	2,250.00	400.00	3,000.00	6,000.00	3,000.00	15,000.00	AMOUNT RS.	
		230.00	350.00	500.00	90.00	150.00	890.00	110.00	210.00	13,250.00	RATE RS.	
		23,000.00	3,500.00	1,500.00	13,500.00	600.00	89,000.00	33,000.00	21,000.00	79,500.00	AMOUNT RS.	15
The state of the s		15.00	50.00	50.00	8.00	50.00	25.00	25.00	30.00	1,500.00	RATE RS.	.K.K.SINGH ELECTRICALS
		1,500.00	500.00	150.00	1,200.00	200.00	2,500.00	7,500.00	3,000.00	9,000.000	AMOUNT RS.	
		160.00	350.00	450.00	65.00	450.00	760.00	140.00	220.00	11,500.00	RATE RS.	
		16,000.00	3,500.00	1,350.00	9,750.00	1,800.00	76,000.00	42,000.00	22,000.00	69,000.00	AMOUNT RATE AMOUNT RS. RS. RS.	M/s.POLAR ELI
		20.00	100.00	150.00	5.00	150.00	30.00	30.00	45,00	3,500.00	RATE RS.	ECTRICALS
		2,000.00	1,000.00	450.00	750.00	600.00	3,000.00	9,000.00	4,500.00	21,000.00	AMOUNT RS.	
S.		245.00	350.00	450.00	58.00	300,00	980.00	82.00	170.00	00.000,6	RATE RS.	2 -
B. Da Bayane		24,500.00	3,500.00	1,350.00	8,700.00	1,200.00	98,000.00	24,600.00	17,000.00	54,000.00	AMOUNT RS.	M/s.S.S.ELECTRICALS
C. E. M.		25.00	100.00	100.00	8.00	75.00	50.00	30.00	40.00	2,700.00	RATE RS.	CTRICALS
3		2,500.00	1,000.00	300.00	1,200.00	300.00	5,000.00	9,000.00	4,000.00	16,200.00	E AMOUNT	NOT

	٠	

	:.00 Laying of conduit et	supports a	.00 Erecting of fasterner clamp will	.00 ERECTIN	200 × 45 mm	150 x 45 mm	100 x 45 mm	Supplying the follow mm. Thic celling / li rod and ra shape and and all ac	.00 G I TRUNKING		supplying of the 6 n supports : the GI true etc.	300 mm	450 mm (600 mm	i.00 Supplying commissis Trays with Supports: Fixing to the help: capable capable capable of Fixing to the help: capable of Fixing to Fixing to grouting. shall be 2 grouting. fixing allie the contra Throughout mits. on I threaded	Supplyin commiss the fixing to the help capable resulting to grouting, shall be 6 grouting, fabrication Contracto			
	Laying of 2 core speaker cable in trunking and conduit etc.	Erecting of ceiling hung speaker with rope support upto 50 kgs weight for sub hopper with supports and clamp will be supplied by client	Erecting of wall mounted speaker with anchor fasterner for 10 kgs weight with supports and clamp will be supplied by client	ERECTING OF SPEAKER EQUIPMENT.	mm.	mm	mm	Supplying, fabricating, laying and connecting the following GI TRUNKING with cover of 1.6 mm. Thick embedded in the floor (or) open in ceiling / laid in below faise flooring with thread rod and rail supports including of L shape, T shape and necessary support, clamps screws and all accessories etc.	NKING		Supplying, erecting, connecting & commissioning of the 6 mm thread rod with slotted channel supports and welded in the stress supports for the GI trunking and related to all accessories etc.	300 mm (w) x 50 mm (H)	450 mm (w) x 50 mm (H)	600 mm (w) x 50 mm (H)	Supplying, fabricating, erecting, connecting & commissioning of the Perforated type GI Cable Trays with necessary Angle irons for cable Trays with necessary Angle irons for cable supports and other allied fabrication works. Fixing to concrete surfaces shall be done with the help of expandable type anchor fastners capable of bearing a weight of 500 Kgs. Fixing to brick walls shall be done with grouting. The distance between two supports shall be 200mm. Thematerials and labour for grouting, cable supportsand Provision for fixing allied fabrication work shall supplied by the contractor with provision for fixing GI flats Throughout with connection point once every mits, on both sides all supports shall be with threaded rods once every 1500mm.	purplied, fabricating, erecting, connecting & learning fabrication, erecting, connecting from the Powder capated Cable (1799) and other allied fabrication works, supports and other allied fabrication works, supports and other allied fabrication works, included to expandable type anchor fastners capable of bearing a weight of 500 Kgs. Fixing to brick walls shall be done with grouting. The distance between two supports shall be 60mm. The materials and labour for grouting, cable supports and other allied fabrication work shall supplied by the Contractor at no extra cost.		DESCRIPTION	ENNA!
	500 Mts	4 Set	100 Nos		50	100	200 1			-	300 Mtrs	100 Mtrs	75 Mtrs	75 Mtrs		1000 Kgs		QIY.	March
	u		io		MTS	STM	MTS	1.		1	TS .	TS.	-S	ıs		IS .	R	1	-
					475.00	425.00	350.00				160.00	550.00	650.00	760.00		60.00	RATE RS.	SUPPLY	
					23,750.00	42,500.00	70,000.00				48,000.00	55,000.00	48,750.00	57,000.00		60,000,00	RS.	LY MIS.KEVIN ELECIRICALS	מוניים וייים ווייים ווייים ווייים
	12.00	750.00	150.00		90.00	75.00	60.00				50.00	100.00	110.00	125.00		15.00	RATE RS.	ERE	0
	6,000.00	3,000.00	15,000.00		4,500.00	7,500.00	12,000.00	-			15,000.00	10,000.00	8,250.00	9,375.00		15,000.00	AMOUNT RS.	ERECTION	
					590.00	435.00	385.00				145.00	750.00	1,000.00	1,250.00		95,00	RATE RS.		
- Control of the Cont					29,500.00			•			43,500.00	75,000.00	75,000.00	93,750.00		95,000,00	AMOUNT RS.	SUPPLY ERECTION	HOWIS A A - 188
The state of the s	3.00	250.00	100.00		60.00	55.00	50.00				30.00	50.00	60.00	75.00		20.00	RATE RS.	ERE	- INCIDENT
	1,500.00	1,000.00	10,000.00		3,000.00	5,500.00	10,000.00		2		9,000.00	5,000.00	4,500.00	5,625.00	-	20,000.00	AMOUNT RS.	CTION	
					840.00	670.00	520.00				60.00	650.00	840.00	960.00		70.00	RATE RS.		
					42,000.00	67,000.00	104,000.00				18,000.00	65,000.00	63,000.00	72,000.00		70,000.00	RS.	SUPPLY ELECTRICALS	ala de los ans
	15.00	550.00	250.00		150.00	150.00	150.00				20.00	90.00	120.00	140.00		25.00	RATE RS.	ERE	O IN CIGATO
	7,500.00	2,200.00	25,000.00		7,500.00	15,000.00	30,000.00				6,000.00	9,000.00	9,000.00	10,500.00		25,000.00	RS. RS.	CTION	
					675.00	525.00	460.00				135.00	525.00	650.00	900.00		85.00	RATE RS.	SUF	
るるとなるという					33,750.00	52,500.00	92,000.00				40,500.00	52,500.00	48,750.00	67,500.00		85,000.00	RS.	l j	1100011
Sere)	15.00	850.00	175.00		50.00	40.00	40.00	P 2			35.00	100.00	100.00	125.00		25.00	RATE RS.	EREC	OVACIONA
1	7,500.96	3,400.00	. 17,500.00		2,500.00	4,000.00	8,000.00	=			10,500.00	10,000.00	7,500.00	9,375.00		25,000.00	S. RS.	TION	

2	,																	
																	Note: Only Light Fitting and Lamp will be supplied by Client. All other accessories like clamps, screws etc., shall be included in the erection rates.	
																	LIGHT FIXTURES (EXTERNAL)	.00.00
3,000.00	100.00			2,400.00	80.00			4,500.00	150.00			5,250.00	175.00			30 Nos	W CF, RECESSED PHILIPS MAKE FBS470/236 AGHFPS P5 236 (or) equivalent with Electronic Ballast complete fixing in the false ceiling with all necessary accessories.	.06.00
4,500.00	90.00		9	3,000.00	60.00			2,500.00	50.00			2,000.00	40.00			50 Nos	Fixing connecting and commissioning of 1x 40W PATTI TYPE FITTING PHILIPS MAKE TMC55/136HF fixing in the ceiling with all necessary accessories.	5.00
5,000.00	100.00			4,000.00	80.00			3,750.00	75.00		,	4,500.00	90.00			50 Nos	Fixing, connecting and commissioning of 2 x18 W PL SPOT LIGHT FITTING RECESSED DOWN LIGHTER, of PHILIPS MAKE FBS/145/218L with Horizontal lamp position (or) equivalent	.04.00
2,250.00	225.00			1,200.00	120.00			1,500.00	150.00			1,500.00	150.00	11,000.00	1,100.00	10 Nos	Supplying, fixing of Exhaust fan with louvres, brackets and necessary clamps, screws etc.	.03.00
2,200.00	110.00			2,400.00	120.00	1,800.00	90.00	3,000.00	150.00			3,000.00	150.00	29,000.00	1,450.00	20 Nos	Supplying, fixing of Ceiling fan with necessary down rods.clamps, screws etc.	.02.00
22,500.00	225.00			25,000.00	250.00	15,000.00	150.00	10,000.00	100.00			7,500.00	75.00			100 Nos	Fixing, connecting and commissioning Celling light / chandilier / wall light Fitting with necessary accessories required for the lob.	.01.00
																	FIXING OF LIGHT FITTINGS (INTERNAL-COMMON AREA)	.00.00
2,000.00	20.00	10,000.00	100.00	1,500.00	15.00	7,000.00	70.00	1,800.00	18.00	8,500.00	85.00	2,000.00	20.00	7,500.00	75.00	100 Mts	60 mm. dia PVC Conduits	.01.04
750.00	15.00	3,000.00	60.00	500.00	10.00	2,750.00	55.00	750.00	15.00	2,400.00	48.00	750.00	15.00	2,900.00	58.00	50 Mts	40 mm. dia PVC Conduits	.01.03
3,600.00	12.00	15,000.00	50.00	1,800.00	6.00	12,600.00	42.00	3,600.00	12.00	10,800.00	36.00	3,000.00	10.00	12,000.00	40.00	300 Mts	32 mm. dia PVC Conduits	.01.02
1,600.00	8.00	7,000.00	35.00	1,000.00	5.00	7,000.00	35.00	2,000.00	10.00	5,600.00	28.00	1,600.00	8.00	6,000.00	30.00	200 Mts	25 mm. dia PVC Conduits	.01.01
																	Supplying, laying of Heavy duty PVC condult laid in floor / concealed in wall / partitions with accessories, necessary clamps, screws etc.	.01.00
																	EMPTY PVC CONDUITS	.00.00
8,000.00	400.00			1,200.00	60.00			4,000.00	200.00			1,500.00	75.00	-		20 Nos	Erecting, flush mounted of connector terminal and make suitable for 4module powder coated ms base box for the terminal plate and terminal will be supplied by client	.07.00
8,000.00	400.00			1,200.00	60.00			3,000.00	150.00			3,000.00	150.00			20 Nos	Erecting, flush mounted output and input module box in the wall and proper civil finishing box will be supplied by client	:.06.00
15,000.00	30.00			7,500.00	15.00			1,500.00	3.00			7,500.00	15.00			500 Mts	Laying of 4 core speaker cable in trunking and conduit etc.	2.05.00
12,500.00	25.00			10,000.00	20.00			2,000.00	4.00			12,500.00	25.00			500 Mts	04.00 Laying of 20 core speaker cable in trunking and conduit etc.	.04.00
ERECTION E AMOUNT S. RS.	RATE RS.	AMOUNT RS.	RATE RS.	AMOUNT RS.	RATE RS.	AMOUNT RATE AMOUNT RS. RS.	RATE RS.	TE AMOUNT	RATE RS.	AMOUNT RS.	RATE RS.	AMOUNT RS.	RATE AMI	AMOUNT RS.	RATE /			
	TRICALS	M/s.S.S.ELECTRICALS			CTRICALS	M/s.POLAR ELE			ELECTRICALS	MIS.K.K.SINGH ELECTRICALS				M/s.KEVIN ELECTRICALS		QTY.	DESCRIPTION	
												FOR M/S.		IED OUT FOR PR	ON TO BE CARR	INSTALLATI	THE STATEMENT FOR ELECTRICAL INSTALLATION TO BE CARRIED OUT FOR PROPOSED	

WELACHERY OF CHENNALZ OF CHENN

PAGE 8 OF 10

								9												
NA dos descriptions and descriptions and descriptions and descriptions and descriptions and descriptions and descriptions are described and descriptions and descriptions are described and described	H	H			POCED FOR	M/G					-									
CHENNAI	TWICHT	1		M/s KEVIN EI EC	TRICALS			M/s.K.K.SINGH	LECTRICALS			M/s.POLAR ELECTRICALS	CTRICALS	NON	SUI	M/s.S.S.ELECTRICALS	CTRICALS	ERECTION		
DESCRIPTION	QTY.	\parallel	SUPPLY	LY	EREC	NOIT	1	1 1	RATE		SOF	AMOUNT	RATE	AMOUNT	RATE	AMOUNT	RATE RS.	AMOUNT RS.		
	\mathbb{H}	H	RATE RS.	RS.	RATE RS.	RS.	RATE RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	RS.	Ŗ	ē			
Fixing, connecting and commissioning of Fixing, connecting and commissioning of BDLIARO LIGHT FITTING OF PHILIPS MAKE, EAT # HS 3601 X PL C 18 FOR shall be AND FIXED TO BE AND							- E										, 18			
Fixing, connecting and commissioning Bulk Head Light fittings to be fixed on the Compound		15				-							60,00	600.00			90.00	900.00		
the inh. JUNCTION BOXES	10 Nos				60.00	000.00														
Supplying, erecting 14 G thick Junction boxes with cover of 40 mm. height of suitable sizes as per Site conditions. The Junction boxes shall be fixed flush with the floor (powder coated)	500 SQ.FT	<u> </u>	120.00	60,000.00	25.00	12,500.00	145.00	72,500.00	25.00	12,500.00	280.00	140,000.00	60.00	30,000.00	375.00	187,500.00	50.00	25,000.00		
ADVANCED TYPE LIGHTNING PROTECTION														-						
Supplying, erecting, connecting and commissioning the Dynosphere (CSE TYPE) with necessary foundation plate, mounting screws Justic, andother associated accessories to complete the system to function.	н (0	Set	90,000,00	90,000,00	5,000.00	5,000.00	155,250.00	155,250.00	5,000.00	5,000.00	95,000.00	95,000,00	15,000.00	15,000.00	110,000.00	110,000.00	5,000.00	5,000.00		
Supplying, laying, connecting and commissioning 75 kV. 36 mm dia special copper cable; only meant for these applications) in G I pipe for protection of the cable with necessary accessories as required.	140 N	Mtrs	325.00	45,500.00	50.00	7,000.00	580.00	81,200.00	100.00	14,000.00	1,800.00	252,000.00	60.00	8,400.00	3,300.00	462,000.00	75.00	10,500.00		
Supplying, providing and connecting Eath Gel in the Earth Electrode with necessary accessories. As required by the system	ω	Sets	13,500.00	40,500.00	2,000.00	6,000.00	26,000.00	78,000.00	0 2,000.00	6,000.00	15,000.00	45,000.00	4,000.00	12,000.00	17,000.00	51,000.00	1,500.00	4,500.00		
Supplying, erecting, connecting and commissioning a Lightning Event Counter of digital type in weather proof enclosure with necroscary accessories.	р-	Set	20,000.00	20,000.00	1,000.00	1,000.00	19,600.00	19,600.00	0 3,000.00		15,000.00	15,000.00			0 17,000.00	17,000.00	750.00	750.00		
Tesing and commissioning of the System (Lumpsum) J AUTO POWER FACTOR CAPACITOR BANK	ļ.	Set			5,000.00	5,000.00			20,000.00	20,000.00			5,000.00	5,000.00			1000			
Supplying, erecting and commissioning of 60 KVAR, APFC in the enclosed MS Enclosure with all interconnections of Capacitor Bank for 12 Step Relay APFC shall be incorporated to maintainpower factor suitable to accommodate thefollowing capacitor bank with all interconnections.																			-	
10 KVAR - 3 Nos 5 KVAR - 3 Nos	-	+																		
3 KVAR - 3 Nos 2 KVAR - 2 Nos		-														-		7 000 00		
1 KVAR - 1 Nos 1 No. Class 1.0 96 Sq.mm Digital Power Factor Meter.	2	Sets	75,000.00	150,000.00	1,500.00	3,000.00	88,000.00	0 176,000.00	2,000.00	4,000.00	0 78,000.00	156,000.00	3,000.00	6,000.00	185,000.00	370,000.00 3,300.	3,300.00		Par	
MADRAS ELECTRICAL CONSULTANTS								*	5	VELACHERY OF	nswo	₹.				(3 Dec.	J. Day Daysuson	PAGE 9 OF 10	OF 10	
									CC	CHENNAL-42	7.1.	Ex.				÷				



Š

MS.KEVIN ELECTRICALS
RATE AMOUNT RATE AMOUN
connecting a 5 KG
nearline and connection 5 KG
EIRE EXTINGUISHER properly liked on the well well with necessary clamps, screws, bolts and nuts etc. The extinguisher shall be suitable for all types of fires (A, B & C). 5 NOS 2,900.00 14,500.00 50.00 50.00 250.00 250.00 3,700.00 18,500.00 50.00 50.00 250.00 250.00 250.00 250.00 250.00 250.00 250.00
Supplying, erectingand connecting Treatment Chart in English and Tamil directly fixed on to the wall with necessary screws etc. 4 NOS. 350.00 1,400.00 25.00 100.00 610.00 2,440.00 25.00 100.00 2,000.00 100.00 100.00
Supplying 440 V Gloves 2 SET 450.00 900.00 345.00 690.00 15.00 30.00 450.00 900.00 50.00
Supplying, and laying 1800 mm. x 1200 mm x 6 mm. thick ISI Marked Rubber mats to be 10 NOS. 1,400.00 14,000.00 25.00 250.00 1,100.00 11,000.00 25.00 250.00 1,850.00 18,500.00
Supplying and fixing 440 V Danger Board. 3 MOS. 100.00 300.00 10.00 30.00 270.00 810.00 20.00 60.00 450.00 1,350.00 50.00
.06.00 First Aid Box 2 SET 450.00 900.00 50.00 100.00 3,800.00 50.00 100.00 1,500.00 3,000.00 100.00
Liasion with Electricity Board to avail 1 CT Meter Board connections including submission of Application Forms and otherassociated LS 125,000.00 125,000.00 125,000.00
Liasion with Electricity Board for enhancement of 1.00 Amps energy meter to CT Meter Board connections including submission of Application Forms and otherassociated works.
Shifting of pillar box with cable routing with EB person and related to necessary accessories etc. approximate shifted distance is 25 mtr. 15,000.00 7,500.00 100,000.00 15,000.00
20 Sets 250.00 5,000.00 200.00 4,000.00 100.00 2,000.00 25.00 500.00 150.00 3,000.00 ve
15 Sets 1,400.00 21,000.00 150.00 2,250.00 1,700.00 25,500.00 75.00
TOTAL LS 10,000.00 10,000.00 4,845,560.00 4,845,560.00 915,155.00
Dist @ 3% 121,535.25 Dist @ 3% 27,454.65 Disc. 6.5% 3,929,639.75 887,700.35 ST @ 10.3% 91,433.00
3,929,639.75 979,133.35
GRAND TOTAL 4,908,773.10 5,380,486.74 6,374,080.00 Regretted tender
5,060,591,00 5,754,531,27 6,374,080.00



